

**Walnut Farm**  
**68 Worminghall Road**  
**Oakley**

**British Standard 5837:2012 Arboricultural Report**

**Tom Hurley** BSc(For)Hons, MArborA

15<sup>th</sup> February 2024

# Table of Contents

Section	Page
Introduction and Heads of Terms	3
Tree Stock Appraisal	4
Arboricultural Impact Assessment	5
Tree Works Recommendations	6
Arboricultural Data Tables	7
Photographs	10
Arboricultural Drawings (including Arboricultural Guidance Sheets)	14

Drawings and Arboricultural Guidance Sheets included within this report:

- Tree Location Plan
- Tree Constraints Plan
- AGS408 Demolition of Structures and Surfaces Near Trees

# Introduction and Heads of Terms

<b>Project Reference</b>	TH/B949/0124
<b>Site Address</b>	Walnut Farm, 68 Worminghall Road, Oakley
<b>Instruction</b>	JCE Planning & Architectural Consultancy
<b>Lead Surveyor</b>	Tom Hurley, BSc(For)Hons, MArborA
<b>Report Author</b>	Tom Hurley, BSc(For)Hons, MArborA
<b>Report Checked By</b>	Joel Gray, FdSc (Arb), NCF Arb, Cert Arb (ABC, RFS), MArborA
<b>Report Published</b>	15 <sup>th</sup> February 2024
<b>Revision</b>	1.0

## **Heads of Terms and Document Limitations**

The purpose of this report is to provide a full arboricultural appraisal of the site and consider the effect of any construction proposals based on the data collected, following the principles of British Standard 5837:2012 *Trees in relation to design, demolition and construction – Recommendations*. As well as informing the overall design and layout of the site, the report shall provide a supporting statement for a planning application to the local planning authority. This report has been undertaken in accordance with the instructions of the client and is intended for their sole and specific use. Any transfer of ownership of this report will require the written consent of the original client and Advanced Arboriculture Ltd reserve the right to charge a fee for the preparation of any future Letters of Resilience.

The report has been prepared based on information available to Advanced Arboriculture Ltd at the time of writing, however, further technical, topographical, arboricultural, architectural, ecological or engineering information may come to light at any point subsequent to the site survey, including after the relevant arboricultural conditions have been cleared. It is the responsibility of the client or their delegated team to draw any changes in the project scope to our attention at the earliest opportunity.

Trees are dynamic structures and advice should be taken on validity two years after the survey was undertaken. The report may not be considered valid after more than three years. The report has been prepared using all reasonable skill and care. Opinions are provided in good faith.

The scheduling and implementation of any tree protection measures detailed in the report also remains the responsibility of the client or their delegated team. Whilst the project team may appoint any suitably qualified third-party arboricultural supervisor, Advanced Arboriculture Ltd are able to take on this role subject to the project manager's formal instruction.

Advanced Arboriculture Ltd shall not be held liable for any unauthorised deviation from the tree management recommendations, the tree protection measures and the project scheduling detailed within this report.

This report, its drawings, Arboricultural Guidance Sheets and any photographs remain © Advanced Arboriculture Ltd.

# Tree Stock Appraisal

The proposed development plot at Walnut Farm in Oakley presently comprises an extended domestic garden which is accessed from the public highway via an existing driveway which enters the site in the north-eastern corner.

In addition to the existing dwelling located towards the northern end of the plot, there is a converted stables in the north-western corner and outbuildings on the southern boundary.

To the north of the plot is another private dwelling while the southern and western boundaries neighbour an access to the small industrial unit to the north-west.

There are a total of eight individual trees within the site's redline boundary, along with a further neighbouring tree to the north whose constraints will extend into the site. There is also three sections of hedgerow and an area of trees.

The first five individual trees are all located along the northern fringe of the site. Apple T1 and Lawson Cypress T3 are both small British Standard 5837:2012 category C ornamental specimens with limited visual amenity value or future potential, with neighbouring Goat Willow T3 being another category C tree which has been reduced in the past.

Pear T4 is an interesting, old specimen which has been heavily reduced in the past but is still thriving; this is considered to be a category A specimen by virtue of its age and likely historic association. Holly T5 is a category B specimen which has also been reduced in the past, though, like Pear T4, its secluded location limits its visual amenity value.

Towards the southern end of the western boundary is a line of two category A Field Maple stems along with one category C Ash. All of these trees are young specimens, though the Ash almost certainly has a limited future potential by virtue of its likely susceptibility to Ash Dieback Disease.

Walnut T9 is located centrally on the southern lawn and is a good quality, category B tree. Its compromised structural form at the point of main crown break is the reason for its downgrading from a category A specimen.

Area A1 comprises a category A line of Field Maple stems running along the southern boundary of the site. These trees have excellent future potential and high amenity value as they can be clearly seen from Wормinghall Road. The Hawthorn understorey further enhances the screening value of this line of trees.

Hedge H1 is a young pleached feature which runs immediately adjacent to the northern boundary fence line. Whilst barely visible from the public highway, its screening value between the two properties is valuable.

Hedge H2 runs immediately to the west of Field Maples T6 and T8 and has been managed by clipping. There is a Laurel hedge immediately to the west but the Hawthorn is the dominant feature from within the garden.

Hedgerow H3 extends along the eastern roadside boundary. There is a high proportion of Elm present within the hedgerow, and many of these have already succumbed to Dutch Elm Disease, with the remainder expected to succumb in the near future. The remainder of the hedgerow is primarily Hawthorn and this maintains a reasonable screen between the road and the proposed development plot.

Hedge features H1 through H3 are all category B assets.

A comprehensive commentary on each tree, including full spatial data, is provided within the attached Arboricultural Data Tables.

## A Note on Ash

Ash Dieback Disease (ADD) is now widespread throughout the UK, though specific symptoms are not always obvious on more mature trees in the early stages of infection. The rate of decline of infected trees and the long-term prognosis for the health of Ash trees generally is currently uncertain. Some sources suggest that the UK may experience losses of up to 90% or more of its Ash trees in some areas; woodland trees in particular appear to be particularly prone to decline.

The identification of ADD infected Ash can be difficult from around October through early June, when trees are normally not

in full leaf, unless the trees are very severely affected and contain large sections of deadwood.

Once infected, trees can decline rapidly and quickly lose their structural integrity. On reaching less than 50% of their normal foliar density, they are likely to require removal where they pose a threat to persons or property. Such trees can become unpredictable and dangerous to fell or even to dismantle using normal rope access techniques, and may thus require removal using a mobile elevated work platform (MEWP) or other machinery. Hence, where trees in an early stage of infection are in locations that are inaccessible to machinery and would pose a risk to persons or property if they declined further, it may be appropriate to consider their pre-emptive removal while it is still possible to deal with them safely using conventional techniques. Each tree will need to be considered on its own merits, but the removal of good quality trees as a precautionary measure is unlikely to be recommended at this stage.

Current recommendations on those sites where Ash trees are present within falling distance of significant targets are that trees be inspected regularly, so as to account for the potentially rapid decline of currently healthy trees should ADD occur; this also applies where we may have not noted specific cases of ADD on a site at the time of survey, but we have no doubt that the disease will be present throughout the locality. Should any Ash trees on site show signs of rapid defoliation or dieback then further advice from an experienced arboriculturist should be sought.

When considering the longer-term management of Ash trees on a site, our advice is that, where such trees are within falling distance of significant targets or otherwise present a significant constraint to the site, then lesser quality trees are unlikely to be worthy of consideration for longer term retention. In these cases, removal of these lesser-quality Ash trees and their replacement with suitable alternative may well result in a net gain in amenity, landscape and biodiversity values for the site over the medium to long term.

# Arboricultural Impact Assessment

The site is the subject of an outline planning application for four dwellings with all matters reserved excluding access. The boundary lines for the four plots are all shown on the attached Tree Constraints Plan, along with the proposed access routes serving each plot. It is noted that site has already benefitted from planning consent in 2023 (Buckinghamshire Council reference: 23/02923/APP) which included the demolition of the existing dwelling and its replacement with a single, large, detached dwelling and detached garage.

The proposals have sought arboricultural advice at an early stage and this has enabled the project team to develop a layout which offers four new plots, each of which can accommodate a new detached dwelling along with garden space and parking, without encountering any undue arboricultural constraints, including rooting, canopy spreads and shading; this also includes a good allowance for future growth of trees.

Plot 1 is the south-easternmost plot on the site. The central section of the site is entirely clear and can sustain the future growth of Walnut T9 and the Field Maple stems which comprise area A1. The new access into the south-eastern corner of the site will necessitate the clearance of a very small section of the Hawthorn understorey within area A1, however, all of the Field Maple stems can be retained in their entirety.

Plots 2 and 3 extend north from plot 1 and are accessed via a new entrance which will need to be cut through hedgerow H3. This offers a good opportunity to re-establish the management of this site boundary feature, and it is noted that the visibility splays required for the new access do not impact on the hedgerow at all.

Plot 4 is the largest plot and extends along the western half of the site. The access is as per existing and there is ample space to accommodate a dwelling, parking and amenity space. It is noted that the proposed site divisions specifically allow for the retention of Walnut T9 within the ownership of plot 4 so as to maximise the potential for the safe retention of this attractive specimen.

As this is only an outline application, it is beyond the scope of this report to consider the provision of services within the layout, however, it is clear that there is space available within the site to allow for service trenches to be dug without any risk of harm to retained trees.

Also, as an outline application, there is no detailed design to apply to a Tree Protection Plan and Arboricultural Method Statement, however, it is reasonable to expect these to be submitted as a condition of any consent, along with a detailed Arboricultural Impact Assessment.

## **Recommendations and Conclusions**

Overall, it is clear that the proposals allow for the retention of all key trees with a negligible risk of any harm as a consequence of construction activities; the most significant impact is associated with the removal of a section of hedgerow H3, and this is balanced by the opportunity to actively manage the retained sections of this frontage screen. The site division and access configuration is therefore considered to be sustainable from an arboricultural perspective subject to the appropriate care being taken during construction, and robust protective fencing and ground protection being installed and maintained for the duration of the project.

Whilst the proposals are considered to be arboriculturally sustainable, a full detailed Tree Protection Plan and Arboricultural Method Statement have not yet been prepared as further practical design, construction and engineering specifics are required before any tree protection measures can be finalised. It is therefore expected that any outline planning consent granted by the local planning authority will include a pre-commencement condition requiring the submission of a detailed tree protection statement. Advanced Arboriculture Ltd are able to produce this on request.

# Tree Works Recommendations

Ref	Species	Proposed Works
A1	Hawthorn	<ul style="list-style-type: none"><li>Remove small section of Hawthorn stems at the western end to accommodate access to plot 1</li></ul>
H3	Mixed species	<ul style="list-style-type: none"><li>Remove central section of hedgerow to accommodate access to plots 2 and 3</li></ul>

## **Informatives**

These works are required to facilitate the access detailed within the outline planning application, however, it is not anticipated that the works would be undertaken until such a time as a detailed reserved matters application has been determined.

The appointed tree work contractor must ensure that all tree works comply with British Standard 3998:2010 *Tree Works – Recommendations* and it is strongly advised that the appointed tree contractor is Arboricultural Association Approved to ensure high standards and a consistency of work.

Under the Wildlife & Countryside Act 1981 & Countryside & Rights of Way Act 2000 it is an offence to recklessly damage or destroy the nest of a wild bird whilst in use or being built; planning consent does not provide a defence against prosecution under these Acts. Trees, shrubs and hedgerows on this site may contain nesting birds between 1st March and 31st August and it is advisable to undertake a survey of the site before commencing any vegetation removal between these dates, to ensure that no nesting birds are present. Advanced Arboriculture are able to undertake a survey to identify the presence of bats or nesting birds if required at the request of the client.

# Arboricultural Data Tables

## Cascade Chart For Tree Quality Assessment (Source: British Standard 5837:2012)

Category and definition	Criteria (including subcategories where appropriate)		
<b>Trees unsuitable for retention</b>			
<b>Category U</b> Those in such a condition that they cannot realistically be retained as living trees in the context or the current land use for longer than 10 years	<ul style="list-style-type: none"> <li>Trees that have a serious, irremediable, structural defect, such that their early loss is expected due to collapse including those that will become unviable after removal of other category U trees (e.g. where, for whatever reason, the loss of companion shelter cannot be mitigated by pruning)</li> <li>Trees that are dead or are showing signs of significant, immediate, and irreversible overall decline</li> <li>Trees infected with pathogens of significance to the health and/or safety of other trees nearby, or very low quality trees suppressing adjacent trees of better quality</li> </ul> Note: Category U trees can have existing or potential conservation value which it may be desirable to preserve		
	<b>1. Mainly arboricultural qualities</b>	<b>2. Mainly landscape qualities</b>	<b>3. Mainly cultural values, including conservation</b>
<b>Trees to be considered for retention</b>			
<b>Category A</b> Trees of high quality with an estimated life expectancy of at least 40 years	Trees that are particularly good examples of their species, especially if rare or unusual: or those that are essential components of groups or formal or semi-formal arboricultural features (e.g. the dominant and/or principal trees within an avenue)	Trees, groups or woodlands of particular visual importance as arboricultural and/or landscape features	Trees, groups or woodlands of significant conservation, historical, commemorative or other value (e.g. veteran trees or wood-pasture)
<b>Category B</b> Trees of moderate quality with an estimated remaining life expectancy of at least 20 years	Trees that might be included in category A, but are downgraded because of impaired condition (e.g. presence of significant though remediable defects, including unsympathetic past management and storm damage), such that they are unlikely to be suitable for retention for beyond 40 years; or trees lacking the special quality necessary to merit the category A designation	Trees present in numbers, usually growing as groups or woodlands, such that they attract a higher collective rating than they might as individuals; or trees occurring as collectives but situated so as to make little visual contribution to a wider locality	Trees, groups or woodlands of significant conservation, historical, commemorative or other value (e.g. veteran trees or wood - pasture)
<b>Category C</b> Trees of low quality with an estimated remaining life expectancy of at least 10 years, or young trees with a stem diameter below 150mm	Unremarkable trees of a very limited merit or such an impaired condition that they do not qualify in higher categories	Trees present in groups or woodlands, but without this conferring on them significantly greater collective landscape value; and/or trees offering low or only temporary/transient landscape benefits	Trees with no material conservation or other cultural value

Abbreviations used in the survey are as follows:

<b>Tree No</b>	Corresponding to plan	<b>Cr Ht</b>	Height of crown above ground level	<b>P</b>	Poor (trees with significant defects)
<b>Species</b>	Common name	<b>Age Class</b>	Y Young (grown to less than one third of life expectancy)	<b>Dead</b>	Dead
<b>Ht</b>	Detailed in metres	<b>MA</b>	Middle Aged (grown to between one to two-thirds of life expectancy)	<b>BS Cat</b>	British Standard 5837:2012 Category (see Table 1 in British Standard 5837:2012 for full details)
<b>Sprd</b>	Crown spread as measured at the four cardinal points of the compass	<b>M</b>	Mature (grown to over two thirds of normal life expectancy)	<b>m/s</b>	Denotes multistem tree along with the individual stem diameters
<b>Stem Dia</b>	Diameter at breast height in mm (1.5 metres above ground level), or measured in accordance with the prescribed British Standard protocol in the case of multi-stemmed specimens (see Annex C in British Standard 5837:2012 for full details)	<b>OM</b>	Over Mature	<b>#</b>	Denotes estimated value where access was not possible
<b>RPA</b>	Root Protection Area radius in metres (derived from the British Standard 5837:2012 formulae)	<b>V</b>	Veteran		
<b>Ht to L/B</b>	Crown height, as measured to the height of the lowest branch	<b>SULE</b>	Safe useful life expectancy range in years		
<b>Dir</b>	Direction from which the lowest branch arises	<b>Cond</b>	Condition, both physiological and structural:		
		<b>G</b>	Good (trees with no significant defects)		
		<b>F</b>	Fair (trees with some defects amenable to surgery)		

Tree No.	Species	Height (m)	Cr Sprd (m)	Stem Dia (mm)	RPA Rad (m)	RPA Area (m <sup>2</sup> )	LB Ht (m)	Cr Ht (m)	Age Cl	SULE	Cond Phys/Str	Observations	Recommendations	BS Cat
T1	Apple	6.0	N: 2.5 E: 2.5 S: 2.0 W: 2.0	160 (m/s: 120, 100)	1.80	10	2.0/S	1.5	Y	10-20	G/F	• Twin-stemmed specimen adjacent driveway	• No works required at the present time	C1
T2	Goat Willow	12.0	N: 3.5 E: 4.5 S: 6.0 W: 8.0	450 #	5.40	92	2.0/S	2.5	MA	20-40	G/F	• Neighbouring tree which has been reduced in the past	• No works required at the present time	C1
T3	Lawson Cypress	11.0	N: 2.5 E: 2.0 S: 3.0 W: 2.5	320	3.90	48	2.0/S	1.0	Y	20-40	G/F	• Ornamental conifer • Compression fork at ~2.0m	• No works required at the present time	C1
T4	Pear	10.0	N: 6.0 E: 4.5 S: 4.5 W: 4.0	560	6.60	137	2.0/N	2.0	M	>40	G/F	• Fine-quality specimen which has been heavily reduced in this past	• No works required at the present time	A3
T5	Holly	7.5	N: 3.0 E: 2.5 S: 2.5 W: 2.5	330	3.90	48	2.0/S	2.0	M	>40	G/F	• Robust specimen which has been reduced to a height of ~3.5m in the past	• No works required at the present time	B2
T6	Field Maple	7.5	N: 2.5 E: 3.0 S: 3.0 W: 3.0	200	2.40	18	1.5/S	2.0	Y	>40	G/G	• Well-balanced specimen with an indistinct leader	• No works required at the present time	A1
T7	Ash	7.0	N: 1.5 E: 2.5 S: 2.0 W: 2.5	140	1.80	10	2.0/N	2.0	Y	10-20	G/F	• Young specimen likely to succumb to Ash Dieback Disease • Indistinct leader	• No works required at the present time	C1
T8	Field Maple	7.0	N: 2.5 E: 2.5 S: 3.5 W: 2.0	180	2.10	14	2.0/S	2.0	Y	>40	G/G	• Young specimen with excellent future potential	• No works required at the present time	A1
T9	Walnut	6.0	N: 3.0 E: 3.5 S: 3.0 W: 3.5	200	2.40	18	1.5/E	2.0	Y	>40	G/F	• Good-quality young specimen which forks into three stems at ~1.5m	• No works required at the present time	B1



Ref No.	Species	Height (m)	Cr Sprd (m)	Stem Dia (mm)	RPA Rad (m)	RPA Area (m <sup>2</sup> )	LB Ht (m)	Cr Ht (m)	Age Cl	SULE	Cond Phys/Str	Observations	Recommendations	BS Cat
A1	• Field Maple • Hawthorn	<8.0	Max: 5.0m	<250	<3.00	<28	>=2.0	>=2.0	Y	>40	G/G	<ul style="list-style-type: none"> <li>Line of good quality young specimens established between domestic garden and adjacent commercial access driveway</li> <li>Field Maple stems have excellent future potential</li> <li>Hawthorn hedgerow forms understorey</li> </ul>	<ul style="list-style-type: none"> <li>Continue to manage Hawthorn understorey by clipping</li> <li>Remove short section of Hawthorn at eastern end of hedgerow to accommodate new access into plot 1</li> </ul>	A2
H1	• Hornbeam	<4.5	Max: 1.0m	<80	<0.90	<3	>=2.0	>=2.0	Y	>40	G/G	<ul style="list-style-type: none"> <li>Relatively young pleached hedge</li> </ul>	<ul style="list-style-type: none"> <li>Continue to manage by pleaching</li> </ul>	B1
H2	• Hawthorn	<3.0	Max: 0.5m	<80	<0.90	<3	>=0.0	>=0.0	Y	>40	G/F	<ul style="list-style-type: none"> <li>Clipped hedge on western boundary of site</li> <li>Laurel hedge located immediately to the west</li> </ul>	<ul style="list-style-type: none"> <li>Continue to manage by clipping</li> </ul>	B3
H3	• Hawthorn • Elm	<7.0	Max: 2.5m	<200	<2.40	<18	>=0.0	>=0.0	Y-MA	>40	P-G/P-G	<ul style="list-style-type: none"> <li>Road-frontage hedgerow in keeping with rural setting</li> <li>Elms are succumbing to Dutch Elm Disease</li> </ul>	<ul style="list-style-type: none"> <li>Clear central section to accommodate new access</li> <li>Continue to manage by clipping</li> <li>Remove dead Elms on an ongoing basis</li> </ul>	B3



Photograph 1: Apple T1



Photograph 2: Goat Willow T2

**Notes**

- Copies of these photographs in JPEG format are available from Advanced Arboriculture on request.

Drawing Title:

**Photographs**

Location:

**Walnut Farm  
Oakley**

Date:	Project Reference:	Revision:
15.02.2024	TH/B949/0124	1.2
Scale:	Paper Size:	Drawn By:
n/a	A3	TH

**Advanced Arboriculture**  
 Venmore Barn  
 Woodbury  
 Devon EX5 1LD  
 t: 01395 239002  
 e: info@advancedarb.com  
 w: www.advancedarb.com



**Photograph 3: Lawson Cypress T3**



**Photograph 4: Pear T4**

**Notes**

- Copies of these photographs in JPEG format are available from Advanced Arboriculture on request.

Drawing Title:

**Photographs**

Location:

**Walnut Farm  
Oakley**

Date:	Project Reference:	Revision:
15.02.2024	TH/B949/0124	1.2
Scale:	Paper Size:	Drawn By:
n/a	A3	TH

**Advanced Arboriculture**  
 Venmore Barn  
 Woodbury  
 Devon EX5 1LD  
 t: 01395 239002  
 e: info@advancedarb.com  
 w: www.advancedarb.com



Photograph 5: Holly T5



Photograph 6: Walnut T9

**Notes**

- Copies of these photographs in JPEG format are available from Advanced Arboriculture on request.

Drawing Title:

**Photographs**

Location:

**Walnut Farm  
Oakley**

Date:	Project Reference:	Revision:
15.02.2024	TH/B949/0124	1.2

Scale:	Paper Size:	Drawn By:
n/a	A3	TH

**Advanced Arboriculture**  
 Venmore Barn  
 Woodbury  
 Devon EX5 1LD  
 t: 01395 239002  
 e: info@advancedarb.com  
 w: www.advancedarb.com



Photograph 7: Hedge H1



Photograph 8: Hedge H2



Photograph 9: Hedge H3 (T6 through T8 in foreground)



Photograph 10: Area A1

**Notes**

- Copies of these photographs in JPEG format are available from Advanced Arboriculture on request.

Drawing Title:

**Photographs**

Location:

**Walnut Farm  
Oakley**


Date:	Project Reference:	Revision:
15.02.2024	TH/B949/0124	1.2
Scale:	Paper Size:	Drawn By:
n/a	A3	TH

**Advanced Arboriculture**  
 Venmore Barn  
 Woodbury  
 Devon EX5 1LD  
 t: 01395 239002  
 e: info@advancedarb.com  
 w: www.advancedarb.com



### Key

- T<sub>n</sub> Category A tree
- T<sub>n</sub> Category B tree
- T<sub>n</sub> Category C tree
- T<sub>n</sub> Category U tree
- Individual tree crown spread
- Collective crown spreads
- Root protection area
- BS5837:2012 shade path
- Proposed plot boundaries
- Proposed new highway access points



**Notes**

-

**Notes**

- 

Drawing Title:  
**Tree Location Plan**

Location:  
**Walnut Farm  
 Oakley**

Date:	Project Reference:	Revision:
15.02.2024	TH/B949/0124	1.2
Scale:	Paper Size:	Drawn By:
1:300	A3	TH

**Advanced Arboriculture**  
 Venmore Barn  
 Woodbury  
 Devon EX5 1LD  
 t: 01395 239002  
 e: info@advancedarb.com  
 w: www.advancedarb.com

Note: The original of this drawing was produced in colour - a monochrome copy should not be relied upon. All drawings © Advanced Arboriculture.



### Key

- T<sub>n</sub> Category A tree
- T<sub>n</sub> Category B tree
- T<sub>n</sub> Category C tree
- T<sub>n</sub> Category U tree
- Individual tree crown spread
- Collective crown spreads
- Root protection area
- BS5837:2012 shade path
- Proposed plot boundaries
- Proposed new highway access points

**N**

**Notes**

- 

Drawing Title:  
**Tree Constraints Plan**


Location:  
**Walnut Farm  
 Oakley**

Date:	Project Reference:	Revision:
15.02.2024	TH/B949/0124	1.2
Scale:	Paper Size:	Drawn By:
1:300	A3	TH


**Advanced Arboriculture**  
 Venmore Barn  
 Woodbury  
 Devon EX5 1LD  
 t: 01395 239002  
 e: info@advancedarb.com  
 w: www.advancedarb.com

Note: The original of this drawing was produced in colour - a monochrome copy should not be relied upon. All drawings © Advanced Arboriculture.

# Demolition Zone Working Directions




# Removal of Hard Surfaces Near Trees



1. tarmac / concrete (maximum depth for pick)
2. sub-base (to be loosened with a fork and removed with a shovel)

3. tarmac / concrete (maximum depth for pick)

# Mechanical Plant Operations Near Trees



- Notes**
- These specifications are for guidance only and must be reviewed by the Project Manager, Demolition Contractor and Arboricultural Supervisor prior to commencement of any works on site.
  - This information must accompany all tender documents to enable contractors to include for specific working requirements in their costings.
  - Local planning authority consent for these specifications cannot be assumed and may need to be sought prior to commencement of any demolition works.

- Site Organisation**
1. All works to be undertaken from outside of the root protection areas.
  2. Tree protection measures to be installed prior to mobilisation to site by demolition contractors.
  3. Any excavator or crane works within 2.0m of the crown spread of retained trees will require an experienced banksman or arboricultural watching brief.
  4. Structures to be demolished in opposite direction from retained trees.
  5. All arisings to be stored outside of the root protection areas in a location that allows rubble, etc. to be collected without unnecessary HGV movements across any root protection areas.
  6. Any crushed rubble piles to be located so that fine particles cannot be carried towards root protection areas by rainfall.
  7. All hard surfacing within root protection areas to be removed as detailed, working away from retained trees.

- Arboricultural Method Statement**
1. All permitted tree works, including access facilitation pruning or felling, to be undertaken as per permitted tree works specification and in accordance with BS3998:2010 and any relevant ecological legislation.
  2. Ground protection measures (as detailed within the Tree Protection Plan) which may include protective fencing, ground protection, signage, or other elements to be installed prior to demolition contractor mobilising to site.
  3. Layout of site for demolition to be set out as agreed with Arboricultural Supervisor
  4. Schedule of demolition to be agreed with Arboricultural Supervisor to allow for pre-booking of arboricultural watching brief if required.
  5. Demolition works to commence as agreed.
  6. Arboricultural Supervisor to undertake ad hoc inspections at the request of the site manager or client. All inspections to be logged on the Arboricultural Supervision Inspection Record and any issues to be raised within an Exception Report to the client.
  7. Any accidental damage to trees to be reported immediately to Advanced Arboriculture with any necessary remedial works to be agreed with the local planning authority.

Drawing Title:  
**Demolition of Structures and Surfaces Near Trees**

Date: 13.10.2021    Drawing Number: AGS408    Revision: 1.0

Scale: n/a    Paper Size: A3    Drawn By: TH

**Advanced Arboriculture**  
 Venmore Barn  
 Woodbury  
 Devon EX5 1LD  
 t: 01395 239002  
 e: info@advancedarb.com  
 w: www.advancedarb.com