

KEY:

- Roof 1 - Asphalt Flat Roof
- Roof 2 - Lead Bay and Slate Roof
- Roof 3 - Flat Felt Roof
- Roof 4 - Asphalt Flat Roof
- Roof 5 - Felt Flat Roof / Lead Barrel Vaulted Roof



- Roof 6 - Lead Cupola / Felt Covered Pitched Roof

Proposed Works

- Roof 1 - Existing asphalt roof is to be receive partial bond 30mm insulated recovery board and two layer mineral felt system. Existing upstand heights are to be maintained.**
- Roof 2 - Existing slated roof is to be stripped and related using mixture of existing slates and re-claimed scotch slates to match existing. Defective lead bay sections are to be repaired using lead to match existing code.**
- Roof 3 - Existing asphalt roof is to be receive partial bond 30mm insulated recovery board and two layer mineral felt system. Existing upstand heights are to be maintained.**
- Roof 4 - No works**
- Roof 5 - Existing leadwork is to be stripped and replaced with new to match existing style and code. Existing asphalt roof is to be receive partial bond 30mm insulated recovery board and two layer mineral felt system. Existing upstand heights are to be maintained.**
- Roof 6 - Existing lead cupola is to be repaired as required with lead code to match existing. Existing felt covers are to be repalced with new partial bond 30mm insulated recovery board and two layer mineral felt system**

Notes:

The contractor is to verify all buildings and site dimensions prior to commencement of works or preparation of shop drawings.
 This drawing and the building works depicted are COPYRIGHT of TRIDENT and may not be reproduced except by written permission,
 Use only figured dimensions Do not scale



PLANNING

Revision:	Date:	Description:	Checked:
A	26.01.24	Proposed works note added.	MS

Client:
 Ambassador Theatre Group

Property:
 Kings Theatre
 Bath Street
 Glasgow

Title:
 Roof Plan

Job No: P2023-0422	Drawn by: MD	Scale: A1@1:100
Drawing No: P005	Date: Jan 2024	Checked: MS

Trident Building Consultancy Ltd.
 Queen's House
 19 St. Vincent Place
 Glasgow
 G1 2DT
 Tel: 0141 229 4525
 www.tridentbc.com