



# Olive Grove Garden Centre

Your steel building quotation No. Andy Parrott Olive Grove 10/08/2023

**Revised gable roller shutter 10<sup>th</sup> October 2023**

This Quote includes the following: -

- P Building Material Price
- P Erecting Costs
- P Plant Hire
- P Scaffolding and Nets

Building Quality, Service & Trust



10 October 2023

Mr. A Parrott  
Olive Grove Garden Centre  
Oundle Road  
Polebrook  
Peterborough  
PE8 5LQ

Dear Andy

Please find the revised quote with the roller shutter in the right gable end.

I have also attached the deposit invoice to the same email.

Kind Regards



Jonathan Bradley  
**Managing Director**



Based on the information given. Overall sizes the Pre galvanised Sharp and Strong steel building kit will produce:

Building size and basic information:

Overall Side Elevation Length	20m
Overall Gable Width	9m
Height to Eaves (Gutter)	4.5m
Dado wall allowance (wall construction by others)	0m
No of bays allowed for	5
Building Style	Ridged
Roof Pitch	12 degrees
Odd size bays	No

## Roof

Roof Cladding	Kingspan RW 40mm Core Composite Panel
Number of Roof lights per bay	0
Roof Cladding Colour	Juniper Green BS12B29
Rain Water System	PVC - Black BS00E53
Valley/Boundary Gutters	none

## Left Gable

Left Gable Cladding	Kingspan RW 40mm Core Composite Panel
Left Gable Cladding Colour	Juniper Green BS12B29
Left Gable Flashing Colour	Juniper Green BS12B29
Any quantity of cladding removed	0
<b>Fire Boundary Base Cleats</b>	<b>No</b>

Left Gable Doors or openings

## Right Gable

Right Gable Cladding	Kingspan RW 40mm Core Composite Panel
Right Gable Cladding Colour	Juniper Green BS12B29
Right Gable Flashing Colour	Juniper Green BS12B29
Any quantity of cladding removed	0
<b>Fire Boundary Base Cleats</b>	<b>No</b>

Right Gable Doors or openings

Heavy Duty Single PA Steel Security Door

10 Multi Point Locking Security Door, fitted with internal thumb turn as standard  
5 Pin Anti-Drill Euro Profile Cylinder  
Anti-Jemmy Studs. Stainless Steel Anti-Knockout Hinges & Stainless-Steel Threshold.  
Powder coated to a standard colour of your choice.

Frame Size - 905mm wide, 2030mm high

Wind Class 5 Industrial Roller Door manufactured from 75mm Galv laths.

Fitted with Safety Brake

Supplied with 100mm top Brushes and Bottom Seals as standard.

4 m wide, 3 m high.

Colour Coated: Yes – Juniper Green

Motor: Single Phase Tube Motor

## Front Side Elevation

Front Side Elevation Cladding	Kingspan RW 40mm Core Composite Panel
Front Side Elevation Cladding Colour	Juniper Green BS12B29
Front Side Elevation Flashing Colour	Juniper Green BS12B29
Any quantity of cladding removed	0
Fire Boundary Base Cleats	No

Front Side Elevation Doors or openings

## Rear Side Elevation

Rear Side Elevation Cladding	Kingspan RW 40mm Core Composite Panel
Rear Side Elevation Cladding Colour	Juniper Green BS12B29
Rear Side Elevation Flashing Colour	Juniper Green BS12B29
Any quantity of cladding removed	0
Fire Boundary Base Cleats	No

Rear Side Elevation Doors or openings

Components covered:

- Flashings/ Trims (Corner, Drip, Eaves, Ridge and Barge)
- Fixings for frame, cladding and base cleats
- Bracing
- Eaves / Ridge Fillers

Note: Door and window frame sizes and positions may vary depending on final detail of building framework. This aspect will be agreed at pre order qualifying stage.

We have assumed a non-coastal location, and a final design and pricing check by Sharp and Strong will be required prior to commencing with any building order.

If the building is to be subject to an Air Leakage test, please advise Sharp and Strong in advance. This will not impact the Building Component price, however it may impact the installation cost. Additional time will be required for installation of extra seals needed to meet the air leakage test criteria.

Please note the above quotation will not take into account any fire boundary conditions, unless stated in the body of quotation. If we have quoted fire Boundary cleats, they will need to be used in conjunction with other materials suitable to form the required fire boundary system.

**\*PLEASE NOTE** If you would like us to quote for skip hire for the removal of the delivery packaging and subsequent left over materials, please let us know.\*