# 'AQUACELL X-TRA' STORAGE UNITS OR SIMILAR APPROVED TO ACHIEVE SGm³ (MIN) OF STORM WATER STORAGE (18m x 17.5m x 0.21mDP). UNITS TO BE INSTALLED FULLY IN ACCORDANCE WITH MANUFACTURERS GUIDANCE. FINAL VOLUME TO BE CONFIRMED FOLLOWING DISCUSSIONS WITH LEAD LOCAL FLOOD AUTHORITY. ENSURE STORAGE STRUCTURE IS VENTED AS PER MANUFACTURERS DETAILS & CONNECTED TO MANHOLE WITH MANIFOLD OR BOX FEED CONNECTION. MIN. GROUND LEVEL = 21.175. (590mm MIN COVER) TOP LEVEL = 20.585 BASE LEVEL = 20.375 F.F.L = 21.350 (TBC)IL=20.450 (150Ø) IL=20.300 (300Ø) IL=20.020 (100Ø) IL=19.970 (150Ø) PROVIDE PETROL BY-PASS SEPARATOR IF REQUIRED. TFLOW - 15.0/s. WITH A DESIGN HEAD OF 1.000m. UNIT TO BE FITTED TH EMERGENCY DRAIN DOWN \$ OVERFLOW PIPE. FINAL CONTROL CHAMBER KEITH SIMPSON ASSOCIATES LTD (Company Registration No. 2744 | 03)

# CONTRACTORS NOTE - NEW CONNECTION

# denotes new connection to be formed on extg drain  $\sharp$  made GOOD AS REQUIRED, CONTRACTOR TO INVESTIGATE SIZE, TYPE \$ DEPTH OF DRAIN AND REPORT FINDINGS TO ENGINEER, SUBJECT TO FINDINGS DRAINAGE SCHEME MAY BE AMENDED. CONTRACTOR TO OBTAIN SECTION I OG AGREEMENT IF REQUIRED WITH SEWERAGE UNDERTAKER PRIOR TO CARRYING OUT ANY WORKS. CONTRACTOR TO CONTACT CIVIL ENGINEER FOR FLOW RATES IF REQUIRED.

# CONTRACTORS NOTE - CCTV DRAINAGE SURVEY (PRE WORKS)

CONTRACTOR TO CARRY OUT A CCTV SURVEY & REPORT OF THE EXTG. DRAINAGE AT THE START OF THE PROJECT. REPORT TO BE FULLY WR $_{\mathcal{C}}$  COMPLIANT  $\sharp$  A COPY OF REPORT TO BE ISSUED TO KSA. CONTACT DRAIN INSPECT UK FOR A QUOTATION, EMAIL: SALES@DRAININSPECT.CO.UK TEL: 0115 8963 206

### CONTRACTORS NOTE - CCTV DRAINAGE SURVEY (POST WORKS)

CONTRACTOR TO CARRY OUT A CCTV SURVEY & REPORT OF THE NEW DRAINAGE AT THE END OF THE PROJECT. REPORT TO BE FULLY WRG COMPLIANT. ANY DAMAGED DRAINS TO BE MADE GOOD \$ A COPY OF REPORT TO BE ISSUED TO KSA. CONTACT DRAIN INSPECT UK FOR A QUOTATION. EMAIL: SALES@DRAININSPECT.CO.UK TEL: 0115 8963 206

# PROPRIETARY TREATMENT SYSTEM MAINTENANCE - BY BUILDING OWNER

MAINTENANCE SCHEDULE	REQUIRED ACTION	
REGULAR	REMOVE LITTER AND DEBRIS AND INSPECT FOR SEDIMENT, OIL AND GREASE ACCUMULATION	SIX MONTHLY
MAINTENANCE	CHANGE THE FILTER MEDIA	AS RECOMMENDED
	REMOVE SEDIMENT, OIL, GREASE AND FLOATABLES	AS NECESSARY
REMEDIAL ACTIONS	REPLACE MALFUNCTIONING PARTS OR STRUCTURES	AS REQUIRED
	INSPECT FOR EVIDENCE OF POOR OPERATION	SIX MONTHLY
MONITORING	INSPECT FILTER MEDIA AND ESTABLISH APPROPRIATE REPLACEMENT FREQUENCIES	SIX MONTHLY
	INSPECT SEDIMENT ACCUMULATION RATES AND ESTABLISH APPROPRIATE REMOVAL FREQUENCIES	MONTHLY DURING FIRST YEAR OF OPERATION AND THEN 6 MONTHLY

# ATTENUATION STORAGE TANKS MAINTENANCE - BY BUILDING OWNER

MAINTENANCE SCHEDULE	REQUIRED ACTION	FREQUENCY
REGULAR MAINTENANCE	INSPECT AND IDENTIFY ANY AREAS THAT ARE NOT OPERATING CORRECTLY. IF REQUIRED, TAKE REMEDIAL ACTION	MONTHLY FOR 3 MONTHS, THEN ANNUALLY
	REMOVE DEBRIS FROM THE CATCHMENT SURFACE (WHERE IT MAY CAUSE RISKS TO PERFORMANCE)	MONTHLY
	FOR SYSTEMS WHERE RAINFALL INFILTRATES INTO THE TANK FROM ABOVE, CHECK SURFACE OF FILTER FOR BLOCKAGE BY SEDIMENT, ALGAE OR OTHER MATTER; REMOVE AND REPLACE SURFACE INFILTRATION MEDIUM AS NECESSARY.	ANNUALLY
	REMOVE SEDIMENT FROM PRE-TREATMENT STRUCTURES AND/OR INTERNAL FOREBAYS	ANNUALLY, OR AS REQUIRED
REMEDIAL ACTIONS	REPAIR/REHABILITATE INLETS, OUTLET OVERFLOWS AND VENTS	AS REQUIRED
MONITORING	INSPECT/CHECK ALL INLETS, OUTLETS, VENTS AND OVERFLOWS TO ENSURE THAT THEY ARE IN GOOD CONDITION AND OPERATING AS DESIGNED	ANNUALLY
	SURVEY INSIDE OF TANK FOR SEDIMENT BUILD-UP AND REMOVE IF NECESSARY	EVERY 5 YEARS OR AS REQUIRED

# PERMEABLE PAVING MAINTENANCE - BY BUILDING OWNER

NAMINITENIANICE			
MAINTENANCE SCHEDULE	REQUIRED ACTION	FREQUENCY	
REGULAR MAINTENANCE	BRUSHING AND VACUUMING (STANDARD COSMETIC SWEEP OVER WHOLE SURFACE	ONCE A YEAR, AFTER AUTUMN LEAF FALL OR REDUCED FREQUENCY AS REQUIRED BASED ON OBSERVATIONS OF CLOGGING OR MANUFACTURERS RECOMMENDATION	
OCCASIONAL MAINTENANCE	STABILISE AND MOW CONTRIBUTING AND ADJACENT AREAS	AS REQUIRED	
	REMOVAL OF WEEDS OR MANAGEMENT USING GYPHOSPATE APPLIED DIRECTLY INTO THE WEEDS BY AN APPLICATOR RATHER THAN SPRAYING	AS REQUIRED	
REMEDIAL ACTIONS	REMEDIATE ANY LANDSCAPING WHICH, THROUGH VEGETATION MAINTENANCE OR SOIL SLIP, HAS BEEN RAISED TO WITHIN 50mm OF THE LEVEL OF THE PAVING.	AS REQUIRED	
	REMEDIAL WORK TO ANY DEPRESSIONS OR RUTTING CONSIDERED DETRIMENTAL TO THE STRUCTURAL PERFORMANCE.	AS REQUIRED	
	REHABILITATION OF SURFACE AND UPPER SUBSTRUCTURE BY REMEDIAL SWEEPING	EVERY 10 - 15 YEARS OR AS REQUIRED	
MONITORING	INITIAL INSPECTION	MONTHLY OR 3 MONTHS AFTER INSTALLATION	
	INSPECT FOR EVIDENCE OF POOR OPERATION AND/OR WEED GROWTH - IF REQUIRED, TAKE REMEDIAL ACTION	3 MONTHLY AND 48h AFTER LARGE STORMS	
	INSPECT SILT ACCUMULATION RATES AND ESTABLISH APPROPRIATE BRUSHING FREQUENCIES	ANNUALLY	
	MONITOR INSPECTION CHAMBERS	ANNUALLY	

© 2023 This drawing is copyright of Keith Simpson Associates Ltd and must not be copied or reproduced without prior written approval of Keith Simpson Associates Ltd. All rights reserved.

DO NOT SCALE. All dimensions to be checked / verified on site.

All drawings to be read in conjunction with Architects / Civil Engineers drawings \$

Drainage connections to sewers and making good to be in accordance with the latest edition Sewers for Adoption.

Any new connections, including the re-use of existing connections, to the public sewerage system will require a formal Section 106 agreement with the sewerage undertaker. The contractor / developer is responsible for obtaining Section 106 approval prior to carrying out any works. Engineer to be contacted for flow rates if

Drainage works to be in accordance with Building Regulations Part H.

he contractor must establish the line of the existing infrastructure drainage and all services prior to commencement of any new connection works.

Trenches within 1.0m of load bearing walls to be backfilled with designated concrete Gen I to at least the underside of the foundation. Where the distance is greater than .Om from the wall, concrete backfill should be to a level below the underside of the oundation equal to the distance from the wall to the near side of the trench less

Pipes to be bedded in class S granular bed \$ surround where cover is 0.6m or greater in landscaping or where cover is 1.2m or greater in driveways and road. Where cover is less than O.6m in landscaping or less than 1.2m in driveways \$ roads class A concrete bed \$ surround or concrete protection slab to be provided. See pipe beddina details.

All pipework to be vitrified clay to BS 65, BS EN 295

Contractor to carry out all necessary water testing of the drainage system prior to backfilling in order to satisfy himself of the adequacy of the workmanship.

Manhole cover levels are approximate only and may require some adjustment to suit

Internal building drainage to be detailed by Architect.

actual ground \$ finished levels.

All external levels and threshold levels to be detailed by Architect / others.


All building drainage components to be Hepworth or similar approved by KSA. All drainage to be laid with level soffit connections.

Contractor to trial hole the existing services within the development prior to commencement of drainage works as necessary to satisfy himself of the line and level

Contractor to allow for the temporary diversion of the flows associated with the

existing drainage system both on and off site, as required. The Contractor should note that ground water may be encountered during the works and should therefore make adequate provisions.

Testing to be carried out on all drainage runs prior to handover \$\pi\$ results to be issued to design team.



				1
P5	25/10/23	SITE LAYOUT AMENDED	SR	NH
P4	17/10/23	SITE LAYOUT AMENDED	SR	ИН
РЗ	12/09/23	SCHEME AMENDED	SR	Z
P2	10/02/23	SITE PLAN UPDATED	TB	Z
PΙ	01/02/23	PRELIMINARY ISSUE	TB	Z
Rev Date		Description	Drwn	Chkd



7C Colwick Quays Business Park Colwick NG4 2JY

Consulting Engineers Tel: 0115 967 3100 Structural • Civil • Web: www.ksastructures.co.uk

RADFORD HOLDINGS

Project

PARK HOUSE MILE END ROAD COLWICK NOTTINGHAM

DRAINAGE LAYOUT

Managing Engineer		NICK HUDSON		
Scale	Date		Sıze	
1:200		FEB 23		ΑI

Status

PRELIMINARY

P5

6142-DR-01