Telephone: 01579 345777 mail@mperryassociates.com www.mperryassociates.com

Ref 24004 - Harbour Hotel & Spa, St Ives

# **DESIGN AND ACCESS STATEMENT**

ON: RETAINING WALL TO EAST OF HARBOUR HOTEL, ST

IVES, TR26 2BN

FOR: THE HARBOUR HOTEL & SPA (T/A THE

PORTHMINSTER HOTEL COMPANY)

DATE: FEBRUARY 2024

PREPARED BY: N M DALEY B.Sc (Hons) MA

CHECKED BY: J A TAYLOR B.Sc (Hons) Assoc RICS



Figure 1 - Photograph showing section of collapsed boundary retaining wall.







# 1.0 INTRODUCTION

- 1.1 The purpose of this Design and Access Statement is to explain the principles and concepts applied to reconstruct a failed section of retaining wall to the East of Harbour Hotel & Spa.
- 1.2 This statement will explain the following:
  - Proposed use of the building.
  - Amount of development.
  - Proposed layout.
  - Scale of the development.
  - Proposed landscaping.
  - Appearance of the building.
  - Access to the building.

# 2.0 DESIGN PRINCIPALS AND CONCEPTS

#### 2.1 PROPOSED USE.

The use of the site will not be altered by the proposals.

# 2.2 AMOUNT OF DEVELOPMENT.

To ensure continued safe access along the public pathway to the East of Harbour Hotel, it is proposed to reconstruct a section of the boundary retaining wall. Existing stone on site will be sorted and cleaned for re-use and will face the proposed retaining structure. In order to maintain a safe working site, it will be necessary to close the public path throughout the duration of the works.

# 2.3 LAYOUT.

The proposed retaining wall position will match that of the original.

#### 2.4 SCALE.

The height of the retaining wall will closely match that of the original.

#### 2.5 LANDSCAPING.

In order to safely construct the retaining wall, it will be necessary to temporarily prop or excavate existing retained ground to a 45° angle. Landscaping items, such as planting or fences will be replaced on a like-for-like basis.

#### 2.6 APPEARANCE.

The retaining wall will be finished with existing stone using a lime-based mortar. The top of the retaining wall will be finished with a stone coping to closely match existing, where formerly present. The glass balustrade close to the failed section of the retaining wall will be temporarily removed and re-installed following remedial works.

#### 2.7 ACCESS.

Access along the public pathway will not change following reinstatement.

# APPENDIX A PHOTOGRAPHS



Figure 2 – Photograph of the North Elevation.



Figure 3 - Photograph showing existing retaining wall to the south end of the footpath.



Figure 4 – Photograph showing existing coping stones and glass balustrade.