



SYSTEM SUMMARY

Bauder Pitched XF301 Sedum System

Extensive green roof system

Bauder XF301 Single Layer Sedum System is an ultra-light weight sedum system. This makes it ideally suitable for light weight pitched roofs. The product can be laid directly onto the waterproofing without the need for a growing medium on pitches of up to 25°. XF301 also contains a moisture mat which retains up to 5 Ltr of water/m². The vegetation within the system is a mix of sedum varieties.



	Product	Description	thickness	weight
	Product	Description	unckness	weight
	1 Bauder XF301 Sedum Blanket	A single layer sedum system, GRO compliant substrate is held within a nylon mesh with attached moisture mat. The sedum blanket is grown for circa 12 months and contains up to 17 species of sedum.	28mm	44Kg/m²
	2 Bauder AL40	A bespoke edge trim which retains the XF301 system and secures the system to the underlying waterproofing.	40mm	N/A
	3 Bauder Retention Strips	Bespoke Stainless steel teeth which grip the ZF301 blanket and hold it in place. The strips are fixed in place by strips of the waterproofing membrane.	N/A	N/A
	4 Underlying Waterproofing System	Bauder's underlying waterproofing system, options for Bituminous Membrane, Hot Melt, Single-ply or Cold applied liquid systems.	N/A	N/A
	(fully satu	Green Roof Build up rated, excludes the waterproofing)	28mm	44 Kg/m²

When to specify

Where a lightweight sedum solution is required. Bauder XF301 sedum system give instant ground cover and a low maintenance solution at a fraction of the weight and depth of substrate based build-ups.

Please note: All green roofs require water during times of drought. Bauder recommend that the watering and maintenance of this roof is considered and addressed during its design.