

Existing evergreen
hedge retained

Existing evergreen
hedge retained

Line of Magnolia tree to retained
and pruned as required



New pair of 1200mm high five bar timber gates to new parking area fitted on new and existing gate posts. Gates to be fitted with remote control auto open and close

Line of new pedestrian gates

New vehicular gate post added

Dashed line of existing vehicular and pedestrian posts and gates removed subject to agreement with Midhurst Town Council

Line of new vehicular gate

Shaded area of ground controlled by Midhurst Town Council but with right of way to Court Green to be prepared for Breedon 'Graphite Granite' self binding gravel finish on MOT Type 1
Edges to be finished with Granite sets.

Existing pedestrian gate and fence refurbished and retained or replaced subject to agreement with Midhurst Town Council

ELEV. A

New 1800mm high coursed Fittleworth stone wall to match existing
ST. ANNES HILL

Edges to be finished with Granite sets.

ELEV. B

New gate post

Low Fittleworth Stone wall to retain gravel

Existing 1500-1800mm high coursed Fittleworth stone wall

New parking bay finished with Breedon 'Graphite Granite' self binding gravel on MOT Type 1 with Granite sets and Fittleworth stone edging

New pedestrian opening in existing Fittleworth stone wall finished with red brick dressings and stone edge capping to match existing
Demolition stone set aside for reused

New pedestrian opening in new Fittleworth stone wall finished with red brick dressings and stone edge capping to match existing with new 1800mm high black cast iron pedestrian gate

FRONT GARDEN

Title
PROPOSED PARKING AREA

Rev Date Amendment

Date May 2023 Drawn CPR Scale 1:60 @ A3

Job Number 1523 Prefix AMC Drawing Number 02 Revision E

COURTS GREEN, ST ANNES HILL
MIDHURST, WEST SUSSEX, GU29 9NN

MR EDWARD KNIGHTON