



- KEY**
- Existing boundary treatment retained
 - Existing stone walling and railing reconfigured to new entrance points
 - 1.8m H Welmesh fencing (PF-001)
 - 1.8m H Bowtop Playground Fencing (PF-002)
 - 3m H Welmesh Balltop Sports Fencing (PF-003)
 - 3m H Welmesh Balltop Sports Fencing (PF-004)
 - 2m H metal balustrade
 - Refer to Architectural Metalwork
 - 1.1m H metal balustrade
 - Refer to Architectural Metalwork
 - 1.3m H Stockproof fence (PF-005)
 - 0.9m H reclaimed stone walling (SW-001)
 - 1.1m H protective barrier to Engineers details
 - Handrails to LHS-002
 - 1.05m H timber postade fence (LIF-002)
 - 1.1m H viewing barrier to Sports Pitch Designer details
 - Anti-vehicle bollards (LIF-001)

- GATE SCHEDULE**
- G01 1 No. single leaf 1.2m width pedestrian gate (LGF-001) with sliding boll. postlock & dropbolt
 - G02 1 No. double leaf 2.4m width vehicular gate (LGF-001) with sliding boll. postlock & dropbolt
 - G03 1 No. single leaf 1.2m width pedestrian gate (LGF-001) with sliding boll. postlock & dropbolt
 - G04 1 No. single leaf 1.2m width pedestrian gate (LGF-001) with sliding boll. postlock & dropbolt
 - G05 1 No. double leaf 2.4m width vehicular gate (LGF-002) with sliding boll. postlock & dropbolt
 - G06 1 No. double leaf 2.4m width vehicular gate (LGF-002) with emergency push out of 1.4m above FGL
 - G07 1 No. single leaf 1.2m width pedestrian gate (LGF-001) with sliding boll. postlock & dropbolt
 - G08 1 No. single leaf 1.2m width pedestrian gate (LGF-003) with Magnadatch emergency latch at 1.4m above FGL
 - G09 1 No. double leaf 1.2m width pedestrian gate (LGF-001) with sliding boll. postlock & dropbolt
 - G10 Not used
 - G11 1 No. single leaf 1.2m width pedestrian gate (LGF-001) with sliding boll. postlock & dropbolt
 - G12 1 No. single leaf 1.2m width pedestrian gate (LGF-001) with emergency push out of 1.4m above FGL
 - G13 1 No. single leaf 1.2m width pedestrian gate (LGF-001) with sliding boll. postlock & dropbolt
 - G14 1 No. double leaf 3m width vehicular gate (LGF-001) with sliding boll. postlock & dropbolt
 - G15 1 No. double leaf 2.4m width vehicular gate (LGF-001) with sliding boll. postlock & dropbolt
 - G16 1 No. double leaf 3m width vehicular gate (LGF-001) with sliding boll. postlock & dropbolt
 - G17 1 No. single leaf 1.2m width pedestrian gate (LGF-001) with sliding boll. postlock & dropbolt
 - G18 1 No. single leaf 1.2m width pedestrian gate (LGF-003) with sliding boll. postlock & dropbolt
 - G19 1 No. single leaf 1.2m width pedestrian gate (LGF-001) with sliding boll. postlock & dropbolt
 - G20 1 No. single leaf 1.2m width pedestrian gate (LGF-001) with sliding boll. postlock & dropbolt
 - G21 1 No. single leaf 1.2m width pedestrian gate (LGF-001) with sliding boll. postlock & dropbolt
 - G22 1 No. double leaf 3m width vehicular gate (LGF-001) with sliding boll. postlock & dropbolt
 - G23 1 No. single leaf 1.2m width pedestrian gate (LGF-001) with sliding boll. postlock & dropbolt
 - G24 1 No. single leaf 1.2m width pedestrian gate (LGF-001) with sliding boll. postlock & dropbolt
 - G25 1 No. double leaf 3m width vehicular gate (LGF-001) with sliding boll. postlock & dropbolt
 - G26 1 No. single leaf 1.2m width pedestrian gate (LGF-001) with sliding boll. postlock & dropbolt
 - G27 1 No. double leaf 5m width pedestrian gate (LGF-001) with sliding boll. postlock & dropbolt. No leaf 180 hinge

BUILDING DESIGN PARTNERSHIP LTD SHALL HAVE NO RESPONSIBILITY FOR ANY USE MADE OF THIS DOCUMENT OTHER THAN FOR THAT WHICH IT WAS PREPARED AND ISSUED.

ALL DIMENSIONS SHOULD BE CHECKED ON SITE.

DO NOT SCALE FROM THIS DRAWING.

ANY DRAWING ERRORS OR DISCREPANCIES SHOULD BE BROUGHT TO THE ATTENTION OF BUILDING DESIGN PARTNERSHIP LTD AT THE ADDRESS SHOWN.

DRAWINGS SHALL BE READ IN CONJUNCTION WITH THE FOLLOWING: THE BDP RISK SERIES SCHEDULE THE BDP RISK SERIES OF DRAWINGS (IF APPLICABLE)

NOTES

- C09 G27 & fencing added to AWW55 KM SG 18/12/23
 - C08 G7 amended to MS comment 31.07 KM SG 31/07/23
 - C07 Updated to 24.07 BC comments KM SG 24/07/23
 - C06 Updated to BC comments KM SG 20/07/23
 - C05 AWW60a updates KM SG 19/06/23
 - C04 AWW025/48 + Flags and Cycle shelter updates KM SG 03/03/23
 - C03 Ironmongery add to gate schedule KM SG 02/02/23
 - C02 Updated to 2nd pitch retention KM SG 11/11/22
 - C01 Updated to AWW025 2nd pitch KM SG 25/08/22
 - 03 Boundary treatment to A77 confirmed KM SG 22/03/21
 - 02 Planting/access to 2nd pitch added KM SG 26/02/21
 - 01 Revised to MS comments KM LM 10/09/20
- FIRST ISSUE** FD LM 29/04/20

BDP.

15 Exchange Place
Glasgow
United Kingdom

T +44 (0)141 227 7900
F +44 (0)141 227 7901
www.bdp.com

PROJECT TITLE Maybole Community Campus	
PROJECT NUMBER P3000653	
DRAWING TITLE Fencing & Boundaries- Overall Site	SCALE 1:750@A1
DRAWING NO. MAY-BDP-02-ZZ-DR-L-90004	DATE 29/04/2020
REVISION C09	