

Under Storey Woodland Seed Mix (EW1) 4gms/m		
Species	Common Name	% of the Mix
Wildflowers		
<i>Alliaria petiolata</i>	Garlic Mustard	1
<i>Anthriscus sylvestris</i>	Cow Parsley	0.5
<i>Carex divulsa ssp divulsa</i>	Grey Sedge	2
<i>Carex pendula</i>	Pendulous Sedge	0.1
<i>Chaerophyllum temulum</i>	Rough Chervil	4
<i>Digitalis purpurea</i>	Foxglove	1
<i>Filipendula ulmaria</i>	Meadowsweet	1.1
<i>Galium album</i>	Hedge Bedstraw	0.5
<i>Geranium pyreniacum</i>	Hedge Crane's-bill	2
<i>Geum urbanum</i>	Wood Avens	0.8
<i>Hyacinthoides non-scripta</i>	Bluebell	1
<i>Silene dioica</i>	Red Campion	5
<i>Silene flos-cuculi</i>	Ragged Robin	1
Grasses		
<i>Agrostis capillaris</i>	Common Bent	1
<i>Anthoxanthum odoratum</i>	Sweet Vernal-grass	2
<i>Brachypodium sylvaticum</i>	False Brome	1
<i>Cynosurus cristatus</i>	Crested Dogtail	50
<i>Deschampsia cespitosa</i>	Tufted Hair-grass	2
<i>Festuca rubra</i>	Red fescue	20
<i>Poa nemoralis</i>	Wood Meadow-grass	4

Pond Edge Mix (EP1) 4gms/m		
Species	Common Name	% of the Mix
Wildflowers		
<i>Carex divulsa ssp divulsa</i>	Grey Sedge	2
<i>Carex pendula</i>	Pendulous Sedge	0.4
<i>Centurea nigra</i>	Common Knapweed	2
<i>Cruciata laevipes</i>	Crosswort	2
<i>Dipsacus fullonum</i>	Wild teasel	0.4
<i>Filipendula ulmaria</i>	Meadowsweet	2
<i>Galium album</i>	Hedge Bedstraw	0.5
<i>Geranium pyreniacum</i>	Hedge Crane's-bill	1
<i>Geum rivale</i>	Water Avens	0.3
<i>Iris pseudacorus</i>	Yellow Iris	2.6
<i>Lycopus europaeus</i>	Gypsywort	0.4
<i>Oenanthe pimpinelloides</i>	Corky-fruited Water-dropwort	0.2
<i>Prunella vulgaris</i>	Selfheal	0.1
<i>Rhinanthus minor</i>	Yellow Rattle	0.5
<i>Silene dioica</i>	Red Campion	2.6
<i>Silene flos-cuculi</i>	Ragged Robin	3
Grasses		
<i>Agrostis capillaris</i>	Common Bent	2
<i>Anthoxanthum odoratum</i>	Sweet Vernal-grass	2
<i>Briza media</i>	Quaking Grass	4
<i>Cynosurus cristatus</i>	Crested Dogtail	48
<i>Deschampsia cespitosa</i>	Tufted Hair-grass	2
<i>Festuca rubra</i>	Red Fescue	22

Standard Trees - as shown on plans						
Species	Common Name	Type/Form	Girth	Height	Clear Stem	No.
<i>Acer campestre (Ac)</i>	Field Maple	RB/Std.	08 to 10	250-300	100-150	26
<i>Quercus robur (Qr)</i>	Pedunculate Oak	RB/Std.	08 to 10	250-300	100-150	23
<i>Quercus patraea (Qp)</i>	Sessile Oak	RB/Std.	08 to 10	250-300	100-150	19
<i>Sorbus torminalis (St)</i>	Wild Service	RB/Std.	08 to 10	250-300	100-150	35
TOTAL						103

Feathered Trees - as shown on plans						
Species	Common Name	Type/Form	Girth	Height	Clear Stem	No.
<i>Betula pendula (Bp)</i>	Silver Birch	BR/Feathered	< 6	200-250	N/a	51
<i>Prunus Avium (Pa)</i>	Wild Cherry	BR/Feathered	< 6	200-250	N/a	32
TOTAL						83

Native Woodland Mix - NW @ 1.5m centres (0.44 Plants per m ²)					NW1	NW2	NW3	NW4	NW5
				Area m ²	958	92	4456	1216	1094
Species	Common Name	Type/Size	%	No.	No.	No.	No.	No.	No.
<i>Acer campestre</i>	Field Maple	BR 1+1 /60-80	10	42	4	196	54	48	
<i>Alnus glutinosa</i>	Alder	BR 1+1 /60-80	10	42	4	196	54	48	
<i>Betula pendula</i>	Silver Birch	BR 1+1 /60-80	10	42	4	196	54	48	
<i>Corylus avellana</i>	Hazel	BR 1+1 /60-80	10	42	4	196	54	48	
<i>Crataegus monogyna</i>	Hawthorn	BR 1+1 /60-80	15	63	6	294	80	72	
<i>Ilex aquifolium</i>	Holly	Container/2 ltr	10	42	4	196	54	48	
<i>Prunus avium</i>	Wild Cherry	BR 1+1 /60-80	10	42	4	196	54	48	
<i>Quercus robur</i>	Oak	BR 1+1 /60-80	15	63	6	294	80	72	
<i>Sorbus torminalis</i>	Wild Service	BR 1+1 /60-80	5	21	2	98	27	24	
<i>Tillia cordata</i>	Small-leaved lime	BR 1+1 /60-80	5	21	2	98	27	24	
TOTAL				100	422	40	1961	535	481

Native Species-rich Hedgerow Mix - NH @7 plants/m (25cm centres, double staggered row)				NH1	NH2	NH3
			Length/m	220	96	18
Species	Common Name	Type/Size	%	No.	No.	No.
<i>Cornus sanguinea</i>	Common Dogwood	BR 1+1 /60-80	5	77	34	6
<i>Corylus avellana</i>	Hazel	BR 1+1 /60-80	10	154	67	13
<i>Crataegus monogyna</i>	Hawthorn	BR 1+1 /60-80	50	770	336	63
<i>Ilex aquifolium</i>	Holly	Container/2 ltr	10	154	67	13
<i>Prunus spinosa</i>	Blackthorn	BR 1+1 /60-80	20	308	134	25
<i>Rosa canina</i>	Dog rose	BR 1+1 /60-80	5	77	34	6
TOTAL			100	1540	672	126

General Purpose Meadow Seed Mix (EM1) 4gms/m		
Species	Common Name	% of the Mix
Wildflowers		
<i>Achillea millefolium</i>	Yarrow	0.3
<i>Centaurea nigra</i>	Common Knapweed	1.5
<i>Leucanthemum vulgare</i>	Oxeye Daisy	1.5
<i>Malva moschata</i>	Musk Mallow	1.5
<i>Plantago lanceolata</i>	Ribwort Plantain	3
<i>Poterium sanguisorba (Sanguisorba minor)</i>	Salad Burnet	1
<i>Ranunculus acris</i>	Meadow Buttercup	0.2
<i>Rhinanthus minor</i>	Yellow Rattle	1
Grasses		
<i>Agrostis capillaris</i>	Common Bent	9
<i>Cynosurus cristatus</i>	Crested Dogtail	31.5
<i>Festuca rubra</i>	Red Fescue	27
<i>Phleum bertolonii</i>	Smaller Cat's-tail	4.5
<i>Poa pratensis</i>	Smooth-stalked Meadow-grass	18

Client Conrad Energy Limited				
Project Synchronous Condenser, Yaxley S73 Application (Single Condenser)				
Drawing Title Plant Schedules				
Created by CL	Reviewer NR	Sheet Size A3	Scale NTS	Date Created 01.09.23
Drawing Nr. 059-12-03 (S73)				Revision A
DRaW (UK) Ltd Morwick Hall York Road Leeds LS15 4TA t: 0113 8232871 www.draw-ltd.com				