



Urban Forestry

Bury St Edmunds



TREE CONDITION SURVEY

Project:	Tree Condition Survey at The Recreation Ground, Woolpit
Client:	Woolpit Parish Council
Date of Report	5 th December 2023

Appendix B – Tree Survey Schedule

No.	Species	Height (m)	Stem Dia. At 1.5 (mm)	Age Class	Health	Structural Condition	Observation/comments	Recommendations	Priority	Reinspection interval
T26	Field maple	9	350	Semi mature	Good	Good	Tree is in good health and condition. Some ivy on lower part of trunk.	Sever ivy by removing from ground level to height of 1m. Crown lift to 2.5m above ground level.	4 - Low	30 months
T27	Swedish whitebeam	9	300	Mature	Good	Good	Tree is in good health and condition. Crown is starting to become low.	Crown lift to 2.5m above ground level.	4 - Low	30 months
T28	Swedish whitebeam	10	120 av	Mature	Good	Fair	A multi-stemmed tree. Main fork formation at 1m height is congested with acute unions but appears at low likelihood of failure.	No work required at present.	N/A	30 months
T29	Blackthorn	7	200 av	Mature	Good	Fair	A small, rather poorly formed twin stemmed tree. Extensive ivy on main stems.	Sever ivy at base of main stems by removing from ground level to height of 1m.	4 - Low	30 months
T30	Swedish whitebeam	9	200	Mature	Good	Good	Tree is in good health and condition.	Crown lift to 2.5m above ground level.	4 - Low	30 months
T31	Rowan	12	200 av	Mature	Poor	Fair	A multi stemmed tree, it appears to be declining. Western most stem is dead. Numerous fruiting bodies of the fungus Chondrostereum purpureum on trunk and scaffold branches. Stands within falling distance of the road.	Fell to ground level and grind out the stump.	2 - High	N/a
T32	Cherry	5	200	Mature	Good	Fair	A small rather poorly formed tree.	Crown lift to 2m above ground level.	4 - Low	30 months
T33	Whitebeam	12	320	Mature	Good	Good	Tree is in good health and condition.	Crown lift to 2.5m above ground level.	4 - Low	30 months
T34	Cherry	15	640	Mature	Good	Good	Fruiting body of Ganoderma adspersum at base of trunk on north west side. Sounding did not suggest extensive decay. Trunk and scaffold branches are in good condition. Some major deadwood in lower crown due to branch shading. Crown is becoming low.	Crown lift to 2.5m above ground level. Remove major deadwood.	3 - Medium	30 months

Appendix B – Tree Survey Schedule

No.	Species	Height (m)	Stem Dia. At 1.5 (mm)	Age Class	Health	Structural Condition	Observation/comments	Recommendations	Priority	Reinspection interval
T6	Sycamore	20	500, 450	Semi mature	Good	Good	A twin stemmed tree forking at ground level. This union is in good condition. Both stems and scaffold branches are in good condition. Tree has a pronounced lean to the east. This appears to be longstanding and the tree does not appear to be unstable. Some minor deadwood in the crown. Adequate crown clearance over the playing field.	No work required at present.	N/A	30 months
G7	Field maple x 10	7 av	300 av	Mature	Good	Good	The group has been heavily crown reduced following which they have grown vigorously.	No work required at present.	N/A	30 months
T8	Lawson cypress	5	80 av	Mature	Good	Good	Tree is in good health and condition.	No work required at present.	N/A	30 months
T9	Whitebeam	8	420	Mature	Good	Good	No basal decay evident. Trunk and scaffold branches are in good condition. Some minor deadwood. Adequate crown clearance over the car park.	Remove basal suckers.	4 - Low	30 months
G10	Ash x 3, field maple x 1	9 av	350 av	Semi mature	Good	Good	The group has been managed as pollards and have reacted well to this treatment. The two south western most trees appear to have been repollarded relatively recently. The crown of the north eastern most tree is now in contact with the roof of the village hall.	Re-pollard the two ash trees closest to the village hall, retaining some smaller branches around the pollard heads to act as sap risers.	4 - Low	30 months
T11	Cherry	10	36	Semi mature	Good	Good	Tree is in good health and condition. Crown is becoming low over grassed area.	Crown lift to 2.5m above ground level.	4 - Low	30 months
T12	Cherry	10	290	Semi mature	Good	Good	Tree is in good health and condition. Ivy present on the trunk.	Remove ivy.	4 - Low	30 months
T13	Crab apple	7	100 av	Semi mature	Good	Good	A multi-stemmed tree in good health and condition. Some ivy on lower stems.	Remove ivy.	4 - Low	30 months
T14	Cherry	12	260	Mature	Good	Good	Tree is in good health and condition. Ivy on trunk. Crown is becoming low over the grassed area to the north.	Crown lift to 2.5m above ground level and remove ivy.	4 - Low	30 months
T15	Birch	16	340	Mature	Good	Good	Tree is in good health and condition. Some ivy on lower part of the trunk.	Remove ivy.	4 - Low	30 months
T16	Birch	14	280	Mature	Good	Good	Tree is in good health and condition.	No work required at present.	N/A	30 months
T17	False acacia	10	150 av	Semi mature	Good	Good	Multi-stemmed tree in good health and condition.	No work required at present.	N/A	30 months