

75 Wentworth Road, London, NW11 0RH

6th January 2024

ISSUE 01







CONTENTS

1	INTRODUCTION	. 4
2	NOISE CRITERIA	. 5
	2.1 NATIONAL PLANNING POLICY FRAMEWORK	5
	2.2 NOISE POLICY STATEMENT FOR ENGLAND	5
	2.3 PLANNING POLICY GUIDANCE	6
	2.4 BRITISH STANDARD 4142:2014	6
3	SITE SURVEYS	9
	3.1 SITE DESCRIPTION	9
	3.2 ENVIRONMENTAL SITE SURVEY PROCEDURE	9
	3.3 EQUIPMENT	10
4	NOISE SURVEY	.11
5	NOISE IMPACT ASSESSMENT	12
	5.1 PROPOSED PLANT	12
	5.2 CLOSEST NOISE SENSITIVE RECEIVER	.13
	5.3 NOISE EMMISSION CRITERION	.14
	5.4 BS4142 ASSESSMENT- Nearest Residential Window	.14
	5.5 MITIGATION MEASURES	.15
6	SUMMARY AND CONCLUSIONS	16
ΑF	PPENDIX:	
Α	ACOUSTIC TERMINOLOGY	. 17
В	CALCULATIONS	19

C MEASUREMENTS20



Author	Date	Checked	Date	Description
L. Jennings Tec. IOA	06/01/2024	M.Austin I.Eng. MIOA	06/01/2024	Information.
Disclaimer				

The opinions and interpretations presented in this report represent our best technical interpretation of the data made available to us. However, due to uncertainty inherent in the estimation of all parameters, we cannot, and do not guarantee the accuracy or correctness of any interpretation and we shall not, except in the case of gross or wilful negligence on our part, be liable or responsible for any loss, cost, damages or expenses incurred or sustained by anyone resulting from any interpretation made by any of our officers, agents or employees. The findings and opinions expressed are relevant to the dates of the site works and should not be relied upon to represent conditions at substantially later dates. If additional information becomes available which may affect our comments, conclusions or recommendations, the author reserves the right to review the information, reassess any new potential concerns and modify our opinions accordingly.

Except for the provision of professional services on a fee basis, DAA Group Ltd does not have a commercial arrangement with any person or company involved in the interests that are the subject of this report. DAA Group Ltd cannot accept any liability for the correctness, applicability or validity for the information they have provided, or indeed for any consequential costs or losses in this regard. Our efforts have been made on a "best endeavors" basis and no responsibility or liability is warranted or accepted by DAA Group Ltd.

Copyright © The material presented within this report is confidential. This report has been prepared for the exclusive use of the client and shall not be distributed or made available to any other company or person without the knowledge and written consent of DAA Group Ltd and the client. All works undertaken by DAA Group Ltd are carried out in accordance with DAA Group Ltd's terms and conditions.



1.0 INTRODUCTION

Page | 4

DAA Group has been appointed to carry out a Noise Impact Assessment at 75 Wentworth Road, London, NW11 0RH to support Planning Application Ref: 23/1295/HSE for the Installation of air conditioning units To the side elevation.

The purpose of the survey is to ensure that the development does not prejudice the amenities of occupiers of nearby premises and to satisfy the following conditions:

"3 a) No development other than demolition works shall commence on site in connection with the development hereby approved until a report has been carried out by a competent acoustic consultant that assesses the likely noise impacts from the development of the ventilation/extraction plant, and mitigation measures for the development to reduce these noise impacts to acceptable levels, and has been submitted to and approved in writing by the Local Planning Authority. The report shall include all calculations and baseline data, and be set out so that the Local Planning Authority can fully audit the report and critically analyse the content and recommendations. b) The measures approved under this condition shall be implemented in their entirety prior to the commencement of the use/first occupation of the development and retained as such thereafter.

4 The level of noise emitted from the air source heat pump hereby approved shall be at least 5dB(A) below the background level, as measured from any point 1 metre outside the window of any room of a neighbouring residential property. If the noise emitted has a distinguishable, discrete continuous note (whine, hiss, screech, hum) and/or distinct impulse (bangs, clicks, clatters, thumps), then it shall be at least 10dB(A) below the background level, as measured from any point 1 metre outside the window of any room of a neighbouring residential property"

This report has been carried out in accordance with the provisions of:

- The National Planning Policy Framework, the Noise Policy Statement for England (NPSE)
- The World Health Organisation Guidelines for Community Noise 1999 (WHO)
- The London Plan 2021.
- Barnet Local Plan

The technical content of this assessment has been provided by a Tech member of the Institute of Acoustics.

The Institute of Acoustics is the UK's professional body for those working in Acoustics, Noise and Vibration.

Email: enquiries@daagroup.co.uk Tel: 0207 101 9669 Mobile: 07957 553188 Company Registration No. 0249971



2.0 NOISE CRITERIA

2.1 NATIONAL PLANNING POLICY FRAMEWORK (NPPF)

The Department for Communities and Local Government introduced the National Planning Policy Framework (NPPF) in March 2012. The latest revision of the NPPF is dated March 2021.

The NPPF sets out the Government's planning policies for England and how these are expected to be applied. It provides a framework where local Councils can produce their own local and neighbourhood plans which reflect the needs of their communities.

In conserving and enhancing the natural environment, the planning system should prevent both new and existing development from contributing to, or being put at, unacceptable risk from environmental factors including noise.

Planning policies and decisions should aim to avoid noise giving rise to significant adverse impacts on health and quality of life as a result of new development. Conditions may be used to mitigate and reduce noise to a minimum so that adverse impacts on health and quality of life are minimised. It must be recognised that development will often create some noise and existing businesses wanting to develop in continuance of their business should not have unreasonable restrictions put on them. Reference is made within NPPF to the Noise Policy Statement for England (NPSE) as published by DEFRA in March 2010.

2.2 NOISE POLICY STATEMENT FOR ENGLAND (NPSE)

The long-term vision of the NPSE is stated within the documents scope, to 'promote good health and a good quality of life through the effective management of noise within the context of Government policy on sustainable development'. The policy aims are stated to:

- avoid significant adverse impacts on health and quality of life;
- mitigate and minimise adverse impacts on health and quality of life; and
- where possible, contribute to the improvement of health and quality of life.

The application of NPSE should mean that noise is properly taken into account at the appropriate time (for example in planning applications or appeals) where it must be considered alongside other relevant issues. The guiding principles of Government policy on sustainable development should be used to assist in the implementation of the NPSE.

The NPSE should apply to all types of noise apart from occupational noise in the workplace. The types of noises defined in the NPSE includes:

- Environmental noise from transportation sources;
- Neighbourhood noise which includes noise arising from within the community; industrial premises, trade and business premises, construction sites and noise in the street

The Noise Policy Statement England (NPSE) outlines observed effect levels relating to the above, as follows:

• NOEL - No Observed Effect Level

o This is the level below which no effect can be detected. In simple terms, below

Email: enquiries@daagroup.co.uk Tel: 0207 101 9669 Mobile: 07957 553188 Company Registration No. 0249971



this level, there is no detectable effect on health and quality of life due to the noise.

• LOAEL - Lowest Observed Adverse Effect Level

o This is the level above which adverse effects on health and quality of life can be detected.

• SOAEL – Significant Observed Adverse Effect Level

o This is the level above which significant adverse effects on health and quality of life occur.

As stated in The Noise Policy Statement England (NPSE), it is not currently possible to have a single objective based measure that defines SOAEL that is applicable to all sources of noise in all situations. Specific noise levels are not stated within the guidance for this reason, and allow flexibility in the policy until further guidance is available.

2.3 ProPG: PLANNING AND NOISE

As outlined above, the National Planning Policy Framework encourages improved standards of design, although it provides no specific noise levels which should be achieved on site for varying standards of acoustic acceptability, or a prescriptive method for the assessment of noise.

ProPG: Planning and Noise was published in May 2017 in order to encourage better acoustic design for new residential schemes in order to protect future residents from the harmful effects of noise. This guidance can be seen as the missing link between the current NPPF and its predecessor, PPG24 (Planning Policy Guidance 24: Planning and Noise), which provided a prescriptive method for assessing sites for residential development, but without the nuance of 'good acoustic design' as outlined in ProPG.

ProPG allows the assessor to take a holistic approach to consider the site's suitability, taking into consideration numerous design factors which previously may not have been considered alongside the noise level measured on site, for example the orientation of the building in relation to the main source of noise incident upon it.

It should be noted this document is not an official government code of practice, and neither replaces nor provides an authoritative interpretation of the law or government policy, and therefore should be seen as a good practice document only.

2.4 BRITISH STANDARD 4142: 2014+A1:2019

British Standard (BS) 4142:2014 "Methods for rating and assessing industrial and commercial sound" describes methods for assessing the likely effects of sound on premises used for residential purposes.

It includes the assessment of sound from industrial and manufacturing processes, M&E plant and equipment, loading and unloading of goods and materials, and mobile plant/vehicles on the site. It can be used to assess sound from proposed, new, modified or additional industrial/commercial sources, at existing or new premises used for residential purposes.

The method described in BS4142: 2014 use outdoor sound levels to assess the likely effects of sound on people who might be inside or outside a dwelling or premises used for residential purposes upon which sound is incident.

The standard describes methods to measure and determine ambient, background and

Email: enquiries@daagroup.co.uk Tel: 0207 101 9669 Mobile: 07957 553188 Company Registration No. 0249971



residual sound levels, and the rating levels of industrial/commercial sound. BS 4142: 2014 requires consideration of the level of uncertainty in the data and associated calculations. BS 4142 is not intended to be used for the derivation or assessment of internal sound levels, or for the assessment of non-industrial / commercial sources such as recreational activities, motorsport, music and entertainment, shooting grounds, construction and demolition, domestic animals, people, and public address systems for speech. The Reference Time Interval, T, is defined in the standard as the "specified interval over which the specific sound level is determined", which is 1 hour during the daytime (07:00 to 23:00 hours) and 15 minutes during the night (23:00 to 07:00 hours).

Ambient sound is defined in BS 4142: 2014 as "totally encompassing sound in a given situation at a given time, usually composed of sound from many sources near and far". It comprises the residual sound and the specific sound when present.

Residual sound is defined in BS 4142: 2014 as "ambient sound remaining at the assessment location when the specific sound source is suppressed to such a degree that it does not contribute to the ambient sound".

The background sound level is the LA90, T of the residual sound level, and is the underlying level of sound. Measurements of background sound level should be undertaken at the assessment location where possible or at a comparable location.

The measurement time interval should be sufficient to obtain a representative value (normally not less than 15 minutes) and the monitoring duration should reflect the range of background sound levels across the assessment period. The background sound level used for the assessment should be representative of the period being assessed.

The specific sound level is the LAeq,T of the sound source being assessed over the reference time interval, Tr. BS 4142: 2014 advises that Tr should be 1 hour during the day and 15 minutes at night.

The rating level is the specific sound level plus any adjustment for the characteristics of the sound (tone, impulse, intermittent or other acoustic feature). The standard describes subjective and objective methods to establish the appropriate adjustment. The adjustments for the different features and assessment methods are summarised in the table below.

Acoustic Feature Corrections in BS4142: 2014

Acoustic	Adjustment for Acoustic F	Adjustment for Acoustic Feature										
Feature	Subjective Methods	Objective Methods										
Tonality	+2 dB if just perceptible	Third Octave Analysis	Narrow Band Analysis									
	+4 dB if clearly perceptible +6 dB if highly perceptible	+6 dB if tones identified	Sliding scale of 0 to +6 dB depending on audibility of tone									
Impulsivity	+3 dB if just perceptible +6 dB if clearly perceptible +9 dB if highly perceptible	Sliding scale of 0 to +9 d of impulsive sound	B depending on prominence									
Intermittency	+ 3 dB if intermittency is readily distinctive	n/a										
Other	+ 3 dB if neither tonal nor impulsive, but otherwise readily distinctive	n/a										

Where tonal and impulsive characters are present in the specific sound within the same reference period then these two corrections can both be taken into account. If one feature



is dominant, it might be appropriate to apply a single correction. The rating level is equal to the specific sound level if there are no features present.

The level of impact is assessed by comparing the rating level of the specific sound source with the background sound level. Typically the greater the difference the greater the magnitude of the impact, depending on the context.

Other factors that may require consideration include the absolute level of sound, the character and level of the residual sound compared to the specific sound, and the sensitivity of the receptor and scope for mitigation.

When the rating level is above the background sound level, a difference of around +5 dB is likely to indicate an adverse impact and a difference of around +10 dB or more is likely to indicate a significant adverse impact, depending on the context.

The lower the rating level with respect to the background sound level, the less likely it is that the specific sound source will have an adverse impact. Where the rating level does not exceed the background sound level, this is an indication of the specific sound source having a low impact, depending on the context.



3.0 SITE SURVEYS

3.1 SITE DESCRIPTION

Page | 9

The application site is a semi-detached property situated in a predominately residential area. The site is typical of an urban cityscape environment, with the dominant source being road traffic noise from the surrounding roads. (See Figure 3.1)



Figure 3.1 – Site Location

3.2 ENVIRONMENTAL SITE SURVEY PROCEDURE

In order to characterise the sound profile of the area at the closest sensitive receptor (NSR), an environmental sound survey has been carried out from 22/06/2023 to 23/06/2023. The monitoring position was chosen in order to collect representative sound levels at the NSR and the location of the plant.

Noise Measurements were carried out Free Field. The condenser units were not operating for the duration of the noise survey. The monitoring location is shown in Figure 5.2.



3.3 EQUIPMENT

Instrument manufacturer Rion

Model NA-28

Serial Number 00501390

Microphone Type UC-59

Serial Number 14934

Calibrator NC-74

Serial Number 34504747

Cirrus CK: 675 Outdoor Kit

All equipment used during the survey was field calibrated at the start and end of the measurement period with a negligible deviation of ≤0.5 dB. All sound level meters are calibrated every 24 months and all calibrators are calibrated every 12 months, by a third-party calibration laboratory. All

microphones were fitted with a protective windshield for the entire measurements period.

3.4 METEOROLOGICAL CONDITIONS

As the environmental noise survey was carried out over a long un-manned period no localized records of weather conditions were taken. However, during the set up and collection of the monitoring equipment, the weather conditions have been documented in the following table. All measurements have been compared with met office weather data of the area, specifically the closest weather station, the data from the weather station is outlined in the table below. When reviewing the time history of the noise measurements, any scenarios that were considered potentially to be affected by the local weather conditions have been omitted. The analysis of the noise data includes statistical and percentile analysis and review of minimum and maximum values, which aids in the preclusion of any periods of undesirable weather conditions. The weather conditions were deemed suitable for the measurement of environmental noise in accordance with BS7445 Description and Measurement of Environmental Noise. The table below presents the average temperature, wind speed and rainfall range for each 24-hour period during the entire measurement.



Weather Conditions – Northolt Weather station											
Time Period	Air Temp (∘C)	Rainfall mm/h	Prevailing Wind Direction	Wind Speed (m/s)							
22/06/2023 – 00:00 – 23:59	13 - 28	0.0	WNW	2-8							
23/06/2023 – 00:00 – 23:59	14 - 27	0.0	W	2 - 12							

Page | 11

Table 3.4 – Weather Summary

4.0 NOISE SURVEY

Period	Lowest Recored LA90, 15
07:00 – 23.00	33dB
23:00 – 07:00	27dB

Table 4.1 Background Sound Level Summary Results



5.0 NOISE IMPACT ASSESSMENT


- **5.1** It is understood that the plant is comprised of the following units:
 - 1 x Daikin 2MXM50A9
 - 1 x Daikin AZAS100MV1


Page | 12

The plant location is shown below in figure 5.2

Proposed Plant	SPL (dB(A))
2MXM50A9	53
AZAS100MV1	57(night -time mode 44)

Table 5.1 – Manufacturer supplied Sound levels








Figure 5.1.1 – Manufacturer Plant Data



5.2 CLOSEST NOISE SENSITIVE RECEIVER

The closest noise sensitive receiver to the installation location of the plant has been identified as being a bedroom window at the front façade of 77 Wentworth Road located approximately 4 metres from the proposed location of the plant as shown in Figure 5.2.

Page | 13



MATERIAL STATE OF THE PROPERTY OF THE PROPERTY

Figure 5.2.1 – Plant Location



Figure 5.2 – Nearest Sensitive Window



Figure 5.2.2 - Layout of 77 Wentworth Road



5.3 NOISE EMMISSION CRITERION

It is understood that the condenser units will be operating over 24hrs.

It is determined that the proposed unit is not considered to contain tones. In addition, the proposed operation of the equipment is also unlikely to be sufficiently intermittent to attract attention at the nearest noise sensitive property. Due to the background noise levels being very low, the criteria of 5dB below the lowest background noise level is considered suitable for this application.

Page | 14

The criteria for plant sound, to be achieved at a point 1m from the closest noise sensitive window, has been set as shown in Table 5.3 in order to comply with the Local Authority requirements.

Time Period	Noise Criterion at Nearest Residential Receiver
07:00 – 23.00	28
23:00 – 07:00	22

Table 5.3 - Proposed noise emissions criterion

5.4 BS4142 ASSESSMENT – 1m outside Nearest residential Window

BS4142:2014 Assessment										
Source	Heat Pumps									
Operating Period	07.00 – 23:00	23:00 – 07:00								
Reference Time Interval (Tr)	15 mi	nutes								
Element	Level (dB)									
Specific Sound Level	37									
Representative Background Noise Level (LA90)	33	27								
Acoustic feature correction	3									
Rating Level	4	0								
Excess of Rating over Background Sound Level	+7	+13 (Night set back +9)								

Detailed calculations are shown in Appendix B.



5.5 MITIGATION MEASURES

BS 4142:2014 "Methods for rating and assessing industrial and commercial sound" presents a method for assessing the significance and possible adverse impact due to an industrial noise source, based on a comparison of the source noise levels and the background noise levels, both of which are measured or predicted at a noise sensitive receiver e.g. a residential property.

Page | 15

The specific noise level due to the source is determined, with a series of corrections for tonality, impulsivity, intermittency or other unusual characteristic. The rating level is then compared to the background noise level and the significance of the new noise source likelihood of any adverse impact is determined in accordance with the following advice:

"The significance of sound of an industrial and/or commercial nature depends upon both the margin by which the rating level of the specific sound source exceeds the background sound level and the context in which the sound occur. A difference of around +10 dB or more is likely to be an indication of a significant adverse impact, depending on the context. A difference of around +5 dB is likely to be an indication of an adverse impact, depending on the context. The lower the rating level is relative to the measured background sound level, the less likely it is that the specific sound source will have an adverse impact or a significant adverse impact. Where the rating level does not exceed the background sound level, this is an indication of the specific sound source having a low impact, depending on the context."

With a calculated Rating of 40dB, this is +7dB during the daytime and +9dB during night-time over the background noise. It is noted that this is worse case scenario and it is not likely the two units will be operating at the same time.

To comply with the Local Authority Criteria, an Acoustic enclosure would have to be installed with an insertion loss of at least 18dB. See Figure 5.5 for an example.





Figure 5.5 – Enclosures UK Acoustic Enclosure – 27 dB Noise Reduction.

Suitable suppliers include but not limited to:

www.enclosures-uk.com

www.environ.co.uk

Page | 16

With the addition of an acoustic enclosure the Rating level will be 13dB. Calculations can be found in Appendix B.

6.0 SUMMARY AND CONCLUSIONS

DAA Group has been appointed to carry out a Noise Impact Assessment at 75 Wentworth Road, London, NW11 0RH. The purpose of the survey was to assess the level of noise emanating from the proposed heat pump to the nearest residential units and to advise on the level and type of mitigation that will be required.

Manufacturer's noise data of proposed plant has been used to obtain Specific and Rated Noise Level at the nearest noise sensitive receiver in accordance with British Standard BS4142:2014+A1:2019 for compliance with Local Authority requirements.

The rating level was compared with the representative background noise level to assess the likelihood of impact considering the environmental noise context of the area as per the requirements of BS4142:2014+A1:2019.

A Rating level of 13dB has been calculated with the addition of the mitigation measures in the form of an acoustic enclosure. This is below the criteria of -5dB below the existing background noise.

It has been concluded that noise emissions from the proposed plant would not have an adverse impact on the nearest residential receivers provided that the mitigation measures presented in 5.5 is followed.



APPENDIX A ACOUSTIC TERMINOLOGY

B.1 WEIGHTED DECIBEL, dB(A)

The unit generally used for measuring environmental, traffic or industrial noise is the A-weighted sound pressure level in decibels, denoted dB(A). The weighting is based on the frequency response of the human ear and has been found to correlate well with human subjective reactions to various sounds. An increase or decrease of approximately 10 dB corresponds to a subjective doubling or halving of the loudness of a noise, and a change of 2 to 3 dB is subjectively barely perceptible.

Page | 17

B.2 EQUIVALENT CONTINUOUS SOUND LEVEL, LAeq

Another index for assessment for overall noise exposure is the equivalent continuous sound level, L_{Aeq}. This is a notional steady level which would, over a given period, deliver the same sound energy as the actual timevarying sound over the same period.

B.3 MAXIMUM NOISE LEVEL, LAmax

The maximum noise level identified during a measurement period. Experimental data has shown that the human ear does not generally register the full loudness of transient sound events of less than 125 ms in duration.

B.4 NOISE RATING, NR

Noise ratings are used as a single figure criterion for specifying services noise in buildings. Each noise rating value has an associated spectrum of defined values in each third or octave frequency band. To determine the noise rating of a room the measured spectrum is compared to a set of noise rating curves. The highest NR curve that crosses any single frequency band of the measurement determines the noise rating for the room.

The single figure noise rating is read at the 1 kHz band.

B.5 SOUND LEVEL DIFFERENCE (D)

The sound insulation required between two spaces may be determined by the sound level difference needed between them. A single figure descriptor which characterises a range of frequencies, the weighted sound level difference, D, is sometimes used (BS EN ISO 717-1). This parameter is not adjusted to reference conditions.

The standardized level difference, Dn, T is a measure of the difference in sound level between two rooms, in each frequency band, where the reverberation time in the receiving room has been normalised to 0.5 s. This parameter measures all transmission paths, including flanking paths.

The weighted standardized level difference, DnTw, is a measure of the difference in sound level between two rooms, which characterises a range of frequencies and is normalised to a reference reverberation time

B.6 SOUND REDUCTION INDEX (R)

The sound reduction index (or transmission loss) of a building element is a measure of the loss of sound through the material, i.e. its attenuation properties. It is a property of the component, unlike the sound level difference which is affected by the common area between the rooms and the acoustic of the receiving room. The weighted sound reduction index, Rw, is a single figure description of sound reduction index characterising a range of frequencies, which is defined in BS EN ISO 717-1: 1997. The Rw is calculated from measurements in an acoustic laboratory



B.7 STATISTICAL NOISE LEVELS (L_{A90}, (T) L_{A1}, (T) L_{A10}, (T) etc.)

For levels of noise that vary widely with time, for example road traffic noise, it is necessary to employ an index which allows for this variation. The L_{A10} is the level exceeded for ten per cent of the time under consideration, has historically been

adopted in the UK for the assessment of road traffic noise. The LA90 is the level exceeded for ninety per cent of the time, has been adopted to represent the background noise level. The L_{A1} the level exceeded for one per cent of the time, is representative of the maximum levels recorded during the sample period. A weighted statistical noise levels are denoted LA10, dB LA90, dB. etc. The reference time (T) is normally included, e.g. LA10, (5min), & LA90, (8hr).

B.8 TYPICAL NOISE LEVELS

Typical noise levels are given in the following table.

Noise Level dB(A)

130	Threshold of pain
120	Jet aircraft take-offs at 100 m
110	Chain saw at 1 m
100	Inside disco
90	Heavy lorries at 5 m
80	Kerbside of busy street
70	Loud radio (in typical domestic room)
60	Office or restaurant
50	Domestic fan heaters at 1m
40	Living room
30	Ventilation Noise in Theatre
20	Remote countryside on still night
10	Sound insulated test chamber
0	Threshold of hearing.

Example



APPENDIX B CALCULATIONS

Page | 19

	NOISE EMISSION CALCULATION													
ITEM	PARAMETER			ΗZ		63	125	250	500	1K	2K	4K	8K	dBA
1	Schedule of Plant	Qty												
2	Daikin													
3	2MXM50A9	1	Spl	dB		55	53	50	46	45	40	35	30	53
4	AZAS100MV1	1	Spl	dB		63	64	56	55	51	46	42	36	57
5														
6	Revised Spl:	1	Spl	dB	+	63	64	57	56	52	47	43	37	59
7														
8														
9														
10														
11	Distance to nearest receptor Metres:	4		dB	-	-12	-12	-12	-12	-12	-12	-12	-12	-12
12	SPL=L1-20log(r/D22)	1												
13														
14														
15														
16	Spl at receptor			dB	+	51	52	45	44	40	35	31	25	47
17	Barrier effect			dB	-	10	10	10	10	10	10	10	10	10
18														
19	Façade correction	3.0		dB	+	3	3	3	3	3	3	3	3	3
20	Intermittant noise correction			dB	+	0	0	0	0	0	0	0	0	0
21														
22														
23	Specific noise level at receptor			dB	+	44	45	38	37	33	28	24	18	40
24	(1m outside noise sensitive window)													
25	Lowest Background Noise Levels:(L _{A90)}													
26	Daytime (07:00 - 23:00)													33
27	Difference: (Assessment level)			dB	-									7
28														
29	Night-time (23:00-07:00)													27
30	Difference: (Assessment level)			dB	-									13
	E&OE													



	NOISE EMISSION CALCULATION													
ITEM	PARAMETER			HZ		63	125	250	500	1K	2K	4K	8K	dBA
1	Schedule of Plant	Qty												
2	Daikin													
3	2MXM50A9	1	Spl	dB		55	53	50	46	45	40	35	30	53
4	AZAS100MV1	1	Spl	dB		63	64	56	55	51	46	42	36	57
5	Acoustic Enclosure - DE034	1	IL	dB		14	17	27	31	37	39	38	39	27
6	Revised Spl:	1	Spl	dB	+	49	47	30	25	15	8	5	-2	32
7														
8														
9														
10														
11	Distance to nearest receptor Metres:	4		dB	-	-12	-12	-12	-12	-12	-12	-12	-12	-12
12	SPL=L1-20log(r/D22)	1												
13														
14														
15														
16	Spl at receptor			dB	+	37	35	18	13	3	-4	-7	-14	20
17	Barrier effect			dB	-	10	10	10	10	10	10	10	10	10
18														
19	Façade correction	3.0		dB	+	3	3	3	3	3	3	3	3	3
20	Intermittant noise correction			dB	+	0	0	0	0	0	0	0	0	0
21														
22														
23	Specific noise level at receptor			dB	+	44	45	38	37	33	28	24	18	13
24	(1m outside noise sensitive window)													
25	Lowest Background Noise Levels:(L _{A90)}													
26	Daytime (07:00 - 23:00)													33
27	Difference: (Assessment level)			dB	-									-20
28														
29	Night-time (23:00-07:00)													27
30	Difference: (Assessment level)			dB	-									-14
	E&OE													

Page | 20



APPENDIX C MEASUREMENTS

