



Clayburn Civic

TECHNICAL INFORMATION

Dimensional Tolerance:	T2
Dimensional Range:	R1
Durability against freeze/thaw:	F2
Active Soluble Salts Content Category:	S2
Gross Dry Density:	1500 kg/m3
Compressive Strength:	Greater than 40 N/mm2
Water Absorption Shown:	Less than 10%
Thermal Conductivity:	0.62 W/m.K-50% 0.69 W/m.K-90%
Dimensions:	215mm x 102.5mm x 65mm
Other Sizes Available:	215mm x 102.5mm x 73mm

Copyright Michelmersh 2013 | Legal | Cookie Policy | Michelmersh Brick Holdings PLC (registered number 03462378) Freshfield Lane, Danehill, Haywards Heath, West Sussex RH17 7HH