Sheffield Cycle Stand **BXMW/GS/Sheffield-Stand**





Standard Unit Dimensions:

Width: 715mm Height: 800mm Diameter: 48.3mm

Recommended spacing between cycle stands:

800mm

Colours/Finishes:



The colours shown are a guide only.
Please check a colour chart to see the actual colour.

RAL 5013

Product Information

The Sheffield Cycle Stand is recommended by the national cycling associations, this best selling tubular cycle stand allows the bike to be secured in a variety of ways. Simple and easy to install this cycle stand is available in a variety of different sizes, fixings and finishings. Thus allowing this best selling cycle stand to complement any external environment, and pre-existing street furniture suite.

Features

- Hot dipped galvanised to BS EN ISO 1461
- Recommended by the national cycling associations
- Available in a variety of different sizes, fixings and finishings
- Complements any external environment
- · Available root fixed or baseplated

Materials Used

Mild Steel

Finish Options

- Galvanised to BS EN ISO 1461
- Galvanised to BS EN ISO 1461 & Polyester Powder Coated

Broxap Limited, Rowhurst Industrial Estate, Chesterton, Newcastle-under-Lyme, Staffordshire, ST5 6BD T: 01782 564411 E: info@broxap.com W: www.broxap.com



RAL 9016













Sheffield Cycle Stand **BXMW/GS/Sheffield-Stand**




Guarantees, Warranties, Design-Life and Life-Expectancies

- 34 year (min) life expectancy for Hot Dip Galvanizing
- 8-10 year life expectancy on standard powder coatings
- 10-15 year life expectancy on Duplex (Zinc Coated) powder coatings
- 12 months' warranty* on parts & labour

Options

- Stands also available in junior size See Sheffield Junior Cycle Stand for details
- · Polyester powder coating to RAL and BS colours
- · Available in a range of different sizes, fixings and finishings
- Available in other materials: Grade 304 stainless steel or duracast[™] polyurethane

Diagram



Standard Unit Dimensions:

Width: 715mm Height: 800mm Diameter: 48.3mm

Recommended spacing between cycle stands:

800mm

Colours/Finishes:



RAL 5015 RAL 5013

Mid Blue Dark Blue

RAL 9016

Traffic White

The colours shown are a guide only. Please check a colour chart to see the actual colour.

Broxap Limited, Rowhurst Industrial Estate, Chesterton, Newcastle-under-Lyme, Staffordshire, ST5 6BD T: 01782 564411 E: info@broxap.com W: www.broxap.com















^{*}Maintenance and other qualifying criteria apply