

DECLARATION OF PERFORMANCE
(System 3)

Masterframe Windows Ltd
4 Crittall Road, Witham, Essex, CM8 3DR




This document declares the product performance of the described External Sash Window intended for use in domestic and commercial buildings, conforms to the product requirements of BS EN 14351-1:2006+A2:2016

Issue No': *BygS-001-5*

"Bygone Symphony (2019)" PVC-U Sliding Sash Window with PVC-U Cill– Incorporating IGU specification; 2 Panes 4mm glass + 10mm Cavity with Warm Edge Spacer & Krypton Gas, Low Emissivity en.05

Essential Characteristics	Performance	Test Standards	Name and Address of Notified Body Test Laboratory	Test report reference and issue date
Watertightness	<i>Class 5A 200 pa</i>	BS EN 1027:2000	<i>Buildcheck Ltd Montrose House Lancaster Road Cressex Business Park High Wycombe HP12 3Py</i>	<i>W14073-3 29 / 08 /2014</i>
Dangerous substances	<i>None</i>	BS EN 14351-1: 2006+A1:2010	<i>N/A</i>	<i>In house declaration</i>
Resistance to wind load	<i>Class A5 (2000pa)</i>	BS EN 12211:2000	<i>British Board of Agreement. Bucknalls Lane, Garston, Watford WD25 9BA</i>	<i>Ref 50088</i>
Impact resistance	<i>npd</i>	BS EN 13049	<i>N/A</i>	<i>N/A</i>
Load-bearing capacity of safety devices	<i>Pass</i>	BS EN 948	<i>British Board of Agreement. Bucknalls Lane, Garston, Watford WD25 9BA</i>	<i>Ref 50088</i>
Height (mm)	<i>npd</i>	BS EN 14351-1: 2006+A1:2010	<i>N/A</i>	<i>N/A</i>
Ability to release	<i>npd</i>	BS EN 179 and BS EN 1125	<i>N/A</i>	<i>N/A</i>
Acoustic performance	<i>$R_w(C;C_{tr})$ 29(-1;-3)</i>	ISO 717-1: 1997	<i>Vinci Technology Centre Stanbridge Road Leighton Buzzard LU7 4QH</i>	<i>Ref 25709 A6441-18</i>
Thermal transmittance	<i>1.4 W/m².k</i>	EN ISO 10077-1 & EN ISO 10077-2 (or EN ISO 12567-1 and prEN 12567-2)	<i>Build check Ltd Montrose House Lancaster Road Cressex Business Park High Wycombe HP12 3Py</i>	<i>Ref: CU14120-1 rev1</i>
Radiation properties	<i>npd</i>	EN 410	<i>N/A</i>	<i>N/A</i>
Air permeability	<i>Class 3 600 pa</i>	BS EN 1026:2000	<i>Buildcheck Ltd Montrose House Lancaster Road Cressex Business Park High Wycombe HP12 3Py</i>	<i>W14073-3 29 / 08 /2014</i>

Signed on behalf of *Masterframe Windows Ltd.*

Signature: ... 

Name: Ray Rabett

Position: Technical & Compliance Director

Date: 30th July 2021