



VELUX Heritage conservation roof window, GCL

Glazing 01



The VELUX Heritage conservation roof window is designed to be in keeping with historic façade aesthetics. Slim and elegant and sitting flush to the tiles, it blends beautifully into historic roofs.

- Authentic top-hung design in keeping with heritage aesthetics
- Slimmer black exterior profile for a perfect fit
- Seamless and stunning glass-to-edge fit
- Near flush installation blends into the roofing material, in keeping with the building's original character
- Central glazing bar that fulfils the design requirement for period authenticity
- Double glazing with glass-to-edge technology that comes with premium features, including safety lamination, toughened outer glass, UV filter, easy-to-clean coating and unique rain noise reduction
- The traditional roof window winding handle mechanism combines a simple operating method with a timeless heritage design

Visible features

- Glass-to-edge technology**
This roof window is precisely crafted with glass-to-edge technology for a seamless and stunning fit. The glass-to-edge technology allows water to run off the window easily.
- Glazing bar**
The vertical glazing bar delivers a classic, traditional look to the conservation window.
- Hand-winder**
The window is delivered with a hand-winder that is fixed to the bottom frame. When the handle is turned, the winder pushes out the window sash approx. 150 mm.
- Blind bracket, manual**
Easily install blinds on the window without the need for extra tools. Simply click on the blind in the pre-fitted brackets.
- Gasket**
Forming the air and sound seal between the frame and sash.
- Data plate**
Every VELUX roof window has a unique data plate with information that can be used to look up CE marking documentation, when purchasing accessories or in case of service or replacement.

Interior finish

Material Description	White-painted Finished with triple coat, white painted.
Colour code NCS, inner surface	S 0500-N
Colour code nearest RAL, inner surface	9003

Exterior covers

Material Description	Aluminium, black Black
Colour code NCS, outer surface	S 9000-N
Colour code nearest RAL, outer surface	9005

Interior finish

Material Description	White-painted Finished with triple coat, white painted.
Colour code NCS, inner surface	S 0500-N
Colour code nearest RAL, inner surface	9003

Exterior covers

Material Description	Aluminium, black Black
Colour code NCS, outer surface	S 9000-N
Colour code nearest RAL, outer surface	9005

Flashings and installation products

Flashings
The Heritage conservation roof window is constructed with a built-in insulation collar in the window frame. Install the VELUX Heritage conservation roof window by using a genuine VELUX flashing solution into slates and plain tiles. Our EDU 1500 flashing is designed specifically for the exact size and shape of the Heritage conservation roof window and includes underfelt collar BFX to create a perfect weathertight fit. The flashing is made by use of aluminum only.

PROJECT:
11-13 High Street
Wesbury-on-Trym, BS9 3BY

TITLE:
Proposed Velux Details

SCALE: 1:5 @ A1
DATE: Feb 2024
DRAWN BY: ams

DRAWING NUMBER: 4264.PL2.30
REVISION:

