

NOTES

FOUNDATIONS
 1m DEEP OR TO LA
 REQUIREMENTS
 MASS CONCRETE FOUNDATION
 MP
WALLS
 300mm CAVITY WALLS
 BRICK WORK UP TO DPC
 100mm 7N BLOCKS TO EXTEND
 SKIN ABOVE DPC &
 RENDERED
 INTERNAL SKIN CEYLON INSULATION
 BLOCKS FILLED WITH 100mm
 CAVITY WALL INSULATION
 35mm INSULATED P/BORD
 2 SKIN FINISH TO ACHIEVE
 REQUIRED VALUES

FLOOR
 150mm ROAD STONE COMPACTED
 25mm BUILDING SAND
 1200g DPM
 100mm RECTOCEL INSULATION
 WITH 25mm RECTOCEL UPGRADE
 AROUND EDGES
 100mm CONCRETE FLOOR

ROOF
 225 x 50 C16 JOISTS @
 600g/c
 150 x 50 WALL PLATE FIXED TO
 WALLS AT TOP WITH M16
 CONCRETE BOLTS
 100 x 75 WALL PLATE ON TOP
 OF INNER SKIN BLOCKWORK
 WALL PLATE RES-BRANT STRIPS
 AT MAX 2m c/c

PROPOSED EXTENSION
 4 LEONARD AVE
 STERWOOD
 NG5 2LU
 SECTION THREE A-A
 DRAW NO LSP/PH/24/09
 DRAWN LSP FEB 24
 SCALE 1:50

R/SJ/STEEL WORK
 2c RSJ's TO BE
 INSERTED TO ENGINEERS
 DETAILS. ON SOLID
 BLUE BRICK PARTITIONS
 AT EACH END
 ANCHORED IN FIRELINE
 BOARD 2 SKIN FINISH

