

Specifications Table for 5MXM-A

					5MXM90A2V1B
Sound pressure level	Heating		Nom.	dBA	52
	Cooling		Nom.	dBA	52
Standard Accessories	Installation manual				1
	Screw bag				1
	Drain plug				1
	Reducer assembly				1
	Drain cap (1)				6
	Drain cap (2)				3
Refrigerant	GWP				675
	Charge			kg	2.40
	Type				R-32
Operation range	Cooling	Ambient	Max.	°CDB	46
			Min.	°CDB	-10
Piping connections	Level difference	IU - IU	Max.	m	7.5
		IU - OU	Max.	m	15
	Additional refrigerant charge			kg/m	0.02 (for piping length exceeding 30m)
	Total piping length	System	Actual	m	75

Give Feedback

Dimensions	Unit	Width	mm	974
		Depth	mm	408
		Height	mm	734
Compressor	Type			Hermetically sealed swing compressor
Weight	Unit		kg	68
Power supply	Phase			1~
	Frequency		Hz	50
	Voltage		V	220-240
Notes				(1) - For one room
				(2) - See separate drawing for operation range
				(3) - See separate drawing for electrical data
				(4) - Contains fluorinated greenhouse gases