BERECO TIMBER SLIDING SASH WINDOWS

Specification

Manufacturer	Bereco Limited	www.bereco.co.uk	01709 838188
Туре	Contemporary Spiral Balance / Contemporary Cords & Weights Traditional Spiral Balance / Traditional Cords & Weights Heritage Spiral Balance / Heritage Cords & Weights		
Wood	Softwood - Redwood		
	Hardwood - Dark Red Meranti		
Finish	Teknos Fully Factory Finished Painto	ed	
	Teknos Fully Factory Finished Stained		
	Teknos Fully Factory Finished Dual	Colour	
Security	BS644:2012		
,	PAS24:2012 / PAS24:2016 (Secured By Design & Part Q Building Regulations)		
Glazing	Type & U-Value		Options
	Triple Glazed	0.8-1.1 W/m ² K	Laminated Safety (6.4mm)
	Double Glazed	1.2-1.5 W/m ² K	Laminated Security (6.8mm)
	Slim-Line Glazed *	1.4-1.6 W/m ² K	Toughened
	Single Glazed *	4.3 W/m ² K	Acoustic **
			Obscure & Coloured
	*Heritage Range Only / **Contemporary & Traditional Only		
Ironmongery	Fasteners	Sash Lifting	Sash Locking
	Fitch Locking (C,T,H) Fitch Non-Locking (C,T,H) Brighton Fastener Locking (T,H) Brighton Fastener Non-Locking (T,H)	Hook Lift (C,T,H)	Sash Lock (C,T)
		Ring Pull (C,T,H)	Angel Ventlock (C,T)
		H) D Handle (C,T,H)	Heritage Sash Lock (H)
	C: Contemporary / T: Traditional / H: Heritage		
Cill Extensions	168mm overall (Contemporary & Traditional Range Only)		
	140mm overall (Heritage Range)		

