



- (H) Interconnected mains operated heat detector with battery back-up. 300mm min from any light fitting
- (S) Interconnected mains operated smoke detector with battery back-up. 300mm min from any light fitting

LD2 GRADE D FIRE DETECTION & ALARM SYSTEM TO BE INSTALLED INCORPORATING DETECTORS IN ALL CIRCULATION SPACES THAT FORM PART OF THE ESCAPE ROUTES FROM THE DWELLING & IN ALL ROOMS THAT REPRESENT A HIGH RISK TO OCCUPANTS INCLUDING A HEAT DETECTOR IN THE KITCHEN

PROPOSED FIRST FLOOR PLAN

xtraroom  
loft conversions

Mr & Mrs KERMEZ

4 Mapletree Close, Cringleford,  
Norwich. NR4 7BF

PROPOSED LOFT CONVERSION

SCALE :	1:50	Drawing number :	
DATE :	Feb 2024	2700 / 3894	
BY :	A. Lloyd	Revision :	Sheet :
SHEET :	2 of 6	0	A3