

SITE – Cotham Garden PS

JOB NO. – LMT6551



All aspects of tree management

Consultancy
Tree Surgery
Site Clearance



JOB SPECIFICATION

Ref.	Species	What 3 Words	Measurements	Survey Notes	Recommendation	Work Method	W@H	Kit	Man Hrs	Timescale
NT1	Ash (<i>Fraxinus sp.</i>)	//corn.atom.actual	Height (m): 18 Crown Radius (m): 6 DBH (cm): 70 Life Stage: Mature	Tree in chronic decline. * Crown and Branches Large deadwood present in canopy. Pruning history - Topped. * Roots and Root Collar Decay present: on north side of trunk. Large sapwood decay area causing widespread dysfunction in 2x large stems. Pests and Diseases: Ash Dieback Present Ash Dieback Infection Level 2: 25% to 50%	Remove tree to a 3-4ft stump.	Climb	YES		24	6 Months
T371	Wellingtonia (<i>Sequoiadendron giganteum</i>)	//scope.bolt.sleeps	Height (m): 25 Crown Radius (m): 5 DBH (cm): 100 Life Stage: Mature	Playground built on top of root collar and below canopy. Tree intensively maintained. * Crown and Branches Minor deadwood present in canopy. * Trunk Play equipment now touching and causing bark distortion.	Remove deadwood >25mm from whole canopy. Tree intensively maintained. Cut back play equipment from trunk to provide at least 20mm clearance. Care taken not to cause damage to bark during operation.	Climb	YES		5	6 Months
T387	Goat willow (<i>Salix caprea</i>)	//foil.throw.hardly	Height (m): 16 Crown Radius (m): 3N, 5E, 5S, 5W DBH (cm): 50 Life Stage: Mature	* Crown and Branches low hanging branches over: road * Trunk Slight Leaning trunk to: south east	Crown lift to 5 m over road for highway clearance.	Work from ground level.	NO	Polesaw	3	6 Months
T366	Cherry (<i>Prunus sp.</i> 'Cherry')	//knots.wicked.fingernails	Height (m): 10 Crown Radius (m): 5N, 5E, 2S, 3W DBH (cm): 40 Life Stage: Mature	* Crown and Branches Crown bias to north east Minor deadwood present in canopy. Included bark. Cankers present. * Trunk Multiple stem crown break at: 1.5m * Roots and Root Collar Tree located in small planting pit. Causing damage to playground tarmac with girdling roots evident. Pests and Diseases: Bacterial Canker of Cherry (<i>Pseudomonas syringae</i> spp)	Reduce long over extended branches back by upto 1m.	Ladder.	YES	Large tripod ladder, wolf pole	1.5	12 Months
T377	Holm oak (<i>Quercus ilex</i>)	//pose.lists.raft	Height (m): 18 Crown Radius (m): 9 DBH (cm): 100 Life Stage: Mature	* Crown and Branches low hanging branches over: road * Trunk Trifurcated at: 1m Codominant stems. Included bark Heavy lean of trunks to: north and east	Crown lift to 6 m over road for highway clearance. Prune to clear crossing lights by at least 1m. Install ASSS support to all 3 stems using 'hub and spoke' system. 8 tonne synthetic brace installed at approx 10m to support all 3 stems in tandem.	Climb	YES	8 ton cobra, wolf pole	16	12 Months



British Association of Landscape Industries

SITE – Cotham Garden PS

JOB NO. – LMT6551



Consultancy
Tree Surgery
Site Clearance



All aspects of tree management




JOB SPECIFICATION

Ref.	Species	What 3 Words	Measurements	Survey Notes	Recommendation	Work Method	W@H	Kit	Man Hrs	Timescale
T380	Oak (<i>Quercus sp.</i>)	//showed.escape.buck	Height (m): 14 Crown Radius (m): 4 DBH (cm): 20 Life Stage: Early Mature	Tree located in poor location (small Raised planter) with poor long term retention value. Tree likely to cause excessive unwanted shade or cause structural damage in future. * Crown and Branches branches in close proximity to: telecom wires	Prune back from telecom wires to clear by at least 0.5m. Consider removal in future.		N/A		2	12 Months
T381	Silver birch (<i>Betula pendula</i>)	//paying.along.both	Height (m): 16 Crown Radius (m): 5N, 6E, 5S, 2W DBH (cm): 50 Life Stage: Over Mature	* Crown and Branches branches in close proximity to: street light Crown bias to east Pruning history - historically topped at 8m. * Trunk Dead/Missing bark. Sapwood damage. * Roots and Root Collar Sapwood damage. Fungus: Fomitopsis betulina (Piptoporus betulinus) suspected on trunk.	End weight reduce all limbs by approx 1-1.5m to alleviate weight load on decayed unions. Remove deadwood >25mm from whole canopy.	MEWP	YES	Wolfpole, MEWP	8	12 Months
T382	Cherry (<i>Prunus sp.</i> 'Cherry')	//tube.fantastic.oath	Height (m): 8 Crown Radius (m): 5 DBH (cm): 50 Life Stage: Mature	* Crown and Branches branches in close proximity to: building * Trunk Bifurcated at: 2m	Prune back from building to clear by at least 1m.	Work from ground level.	NO	Wolfpole	1	12 Months
T388	Field maple (<i>Acer campestre</i>)	//zips.cooks.tennis	Height (m): 7 Crown Radius (m): 3 DBH (cm): 20 Life Stage: Young	Young Maiden Tree. low hanging branches over: playground.	Crown lift canopy all around to achieve at least 2m clearance. Remove stake and ties.	Work from ground level.	NO		0.25	12 Months
T389	Apple (<i>Malus sp.</i>)	//museum.much.chair	Height (m): 7 Crown Radius (m): 3 DBH (cm): 20 Life Stage: Young	Young Maiden Tree. low hanging branches over: playground.	Crown lift canopy all around to achieve at least 2m clearance. Remove stake and ties.	Work from ground level.	NO		0.25	12 Months
T390	Silver birch (<i>Betula pendula</i>)	//digits.tennis.spout	Height (m): 7 Crown Radius (m): 3 DBH (cm): 20 Life Stage: Young	Young Maiden Tree. low hanging branches over: playground.	Crown lift canopy all around to achieve at least 2m clearance. Remove stake and ties.	Work from ground level.	NO		0.25	12 Months
T391	Lime (<i>Tilia sp.</i>)	//oiled.reason.hers	Height (m): 7 Crown Radius (m): 3 DBH (cm): 20 Life Stage: Young	Young Maiden Tree. low hanging branches over: playground.	Crown lift canopy all around to achieve at least 2m clearance. Remove stake and ties.	Work from ground level.	NO		0.25	12 Months
T392	Rowan (<i>Sorbus aucuparia</i>)	//tops.solar.landed	Height (m): 7 Crown Radius (m): 3 DBH (cm): 20 Life Stage: Young	Young Maiden Tree. low hanging branches over: playground.	Crown lift canopy all around to achieve at least 2m clearance. Remove stake and ties.	Work from ground level.	NO		0.25	12 Months
T797	Lombardy poplar (<i>Populus nigra italica</i>)	//movie.tins.shunts	Height (m): 20 Crown Radius (m): 5 DBH (cm): 100 Life Stage: Mature	* Crown and Branches Pruning history - Pollarded. * Roots and Root Collar Collar buried/Not visible due to tarmac around base of tree.	Re-Pollard tree at previous knuckles.	Part MEWP, part climb	YES	mewp	24	24 Months



JOB SPECIFICATION



<p>Site Overview</p> <p>Cornish Garden Services Cotham Gardens Primary School</p>	<p>Page size: A4</p> <p>1 : 1,502</p> 		
---	--	---	---

JOB SPECIFICATION



JOB SPECIFICATION

