



GROUND FLOOR CONSTRUCTION :  
 Client floor finish on 150mm reinforced concrete slab/ raft construction with smooth finish on 1200gauge polythene damp proof membrane on 100mm thick rigid insulation on 150mm thick sand blinded compacted hardcore base

reinforced concrete slab/ foundations / perimeter boot detail to be in accordance with design by qualified structural engineer with due consideration to the depth and design of the existing foundations

8000 overall width of proposed extension  
 (to be verified on site)

proposed section A - A

project no	G2021/LPS/079/10R2	<b>LLOYDS</b> <small>Property Maintenance Services Ltd        (m) 07772 698406 (e) lloydsitd@live.co.uk</small> 
date	01/2024	
scale	1:50 @ A3	
client	Mr Mark Evans	
project	Proposed Alterations : Creazione : Western Ind Estate : Caerphilly CF83.1BQ	