



Name	Size	Root condition	Habit	Density per 1sqm	Number
Acer campestre (n)	50cm	Bare rooted	Deciduous	2	568
Crataegus monogyna (n)	60cm	Bare rooted	Deciduous	3	852
Prunus spinosa (n)	60cm	Bare rooted	Deciduous	2	568
Malus sylvestris (n)	60cm	Bare rooted	Deciduous	0.5	146
Rosa canina (n)	60cm	Bare rooted	Deciduous	0.5	146

Name	Pot Size	Height	Habit	Density per sqm	Number
Cornus sanguinea (n)	3l	20-40cm	Winter red stems native plant	4	36
Cytisus scoparius 'Boskoop Ruby' (w)	2l	30-40cm	Red flowers in summer up to 1.2m	4	36
Dryopteris filix-mas (n)	3l	30-40cm	Semi evergreen native Male fern 1.2m	5	54
Hebe 'Garden Beauty White' (w)	2l	20-30cm	White summer flowers evergreen 50cm	5	36
Lavendula 'Hidcote' (w)	2l	30-40cm	Evergreen grey foliage with summer spikes of blues flowers 75cm	5	36
Rosmarinus officinalis 'Miss Jessops Upright' (w)	3l	20-30cm	Evergreen upright fragrant shrub with blue spring flowers up to 2m	3	36

Shrubs and Perennials: Native = (n); wildlife friendly = (w); multi-stemmed (MS)

Name	Pot Size	Height	Habit	Density per sqm	Number
Cornus sanguinea (n)	3l	20-40cm	Winter red stems native plant	4	36
Cytisus scoparius 'Boskoop Ruby' (w)	2l	30-40cm	Red flowers in summer up to 1.2m	4	36
Dryopteris filix-mas (n)	3l	30-40cm	Semi evergreen native Male fern 1.2m	5	54
Hebe 'Garden Beauty White' (w)	2l	20-30cm	White summer flowers evergreen 50cm	5	36
Lavendula 'Hidcote' (w)	2l	30-40cm	Evergreen grey foliage with summer spikes of blues flowers 75cm	5	36
Rosmarinus officinalis 'Miss Jessops Upright' (w)	3l	20-30cm	Evergreen upright fragrant shrub with blue spring flowers up to 2m	3	36



Hedge plants - 8 per linear metre in staggered rows: Native = (n); wildlife friendly = (w); multi-stemmed (MS)

- 110m native species hedgerow**
- 2 staggered rows
 - 220 No Acer campestre
 - 330 No Crataegus monogyna
 - 550 No Malus sylvestris
 - 550 No Rosa canina

- Planting bed 11sqm**
- drifts of 3 or 6
 - 9 No Dryopteris filix-mas
 - 9 No Cytisus scoparius 'Boskoop Ruby'
 - 9 No Hebe 'Garden Beauty White'
 - 9 No Lavendula 'Hidcote'
 - 9 No Rosmarinus officinalis 'Miss Jessops Upright'

- 40m native species hedgerow**
- 2 staggered rows
 - 80 No Acer campestre
 - 120 No Crataegus monogyna
 - 200 No Prunus spinosa
 - 200 No Rosa canina

- Planting bed 5sqm**
- drifts of 3 or 6
 - 9 No Dryopteris filix-mas
 - 9 No Cytisus scoparius 'Boskoop Ruby'
 - 9 No Hebe 'Garden Beauty White'
 - 9 No Cornus sanguinea
 - 9 No Prunus spinosa
 - 9 No Rosmarinus officinalis 'Miss Jessops Upright'

- Planting bed 7sqm**
- drifts of 3 or 6
 - 9 No Dryopteris filix-mas
 - 9 No Cytisus scoparius 'Boskoop Ruby'
 - 9 No Hebe 'Garden Beauty White'
 - 9 No Cornus sanguinea
 - 9 No Prunus spinosa
 - 9 No Rosmarinus officinalis 'Miss Jessops Upright'

- Planting bed 5sqm**
- drifts of 3 or 6
 - 9 No Dryopteris filix-mas
 - 9 No Lavendula 'Hidcote'
 - 9 No Cytisus scoparius 'Boskoop Ruby'

- 13m native species hedgerow**
- 2 staggered rows
 - 13 No Acer campestre
 - 24 No Crataegus monogyna
 - 8 No Malus sylvestris
 - 8 No Rosa canina

- 30m native species hedgerow**
- 2 staggered rows
 - 60 No Acer campestre
 - 90 No Crataegus monogyna
 - 150 No Malus sylvestris
 - 150 No Rosa canina

Name	Girth/root stock	Root condition	Habit	Number
Acer campestre (n)	10-12cm	Bare root	10-15m native tree	14
Malus 'Lady Henrick' (w)	MM105	Container	Heritage Suffolk apple bred in 1845	2
Malus 'St Edmunds Russet' (w)	MM105	Container	Heritage Suffolk apple bred in 1845	4
Malus 'Honey Pippin' (w)	MM105	Container	Heritage Suffolk apple bred in 1950	3
Malus 'Cox Self Fertile' (w)	MM105	Container	Small tree up to 8m, white spring flowers, edible red apples in autumn	2
Prunus pirus (n)	10-12cm	Bare root	10-15m native with spring flowers	5
Prunus 'Polstead Black' (w)	Cult	Container	Heritage egg bred in Suffolk 1700s	4
Prunus 'Cox Golden Drop' (w)	St Julien 'A'	Container	Heritage cherry bred in Suffolk pre 1900	5
Prunus 'Conference Self Fertile' (w)	Quince 'A'	Container	Confocal with white spring flowers and edible pears' fruits up to 12m	4

Trees - Selected Standard: Native = (n); wildlife friendly = (w); multi-stemmed (MS)

- LEGEND (SOFT WORKS)**
- Retained tree/container
 - Select standard tree or fruit tree
 - Shrubs and perennials
 - Hedging
 - Species Rich Lawn - Wild flora lawn grass - Erosigate, ELL Wild or Wildflower Turf Species Rich Lawn Turf (WFT-Species-Rich-26), or equal approved - pre grown turf
 - Activity Lawn - Boston Seeds Quality Hard Wearing Lawn Seed - or pre grown turf
 - Wildflower seed mix - Erosigate EFL1 Pond Edge Mixture (or similar)

Notes:
 The be used in conjunction with the engineer and landscape drawings.
 No measurements to be scaled off drawing. Worked from figured dimensions only.
 All dimensions shown on drawing are shown in millimetres unless otherwise stated.
 All dimensions and levels to be checked on site landscape prior to the commencement of work.

