

1046 Range Cottage - Planting Plan

Trees			
Number	Species	Specification	Density
6	Acer campestre 'Streetwise'	Heavy Standard: 3x: 12-14cm:C: 75L:350-425cm: Clear Stem min. 200cm	Counted
4	Carpinus betulus 'Frans Fontaine'	Heavy Standard:12-14cm: 3x: C: 75L: 350-425cm: Clear Stem min. 200cm	Counted
3	Malus sylvestris	Heavy Standard:12-14cm: 3x: C: 75L: 350-425cm: Clear Stem min. 200cm	Counted
3	Prunus padus 'Watereri'	Heavy Standard: 3x: C: 75L: 350-425cm: Clear Stem min: 200cm	Counted
1	Quercus robur	Heavy Standard: 12-14cm:3x:C: 75L:350-425cm: Clear Stem min. 200cm	Counted

Shrubs			
Number	Species	Specification	Density
2	Viburnum opulus	1+2: Transplant - seed raised: Branched: 3 brks: B	Counted

Herbaceous			
Number	Species	Specification	Density
15	Alchemilla mollis	2L: Full Pot: C	3/m ²
6	Euphorbia griffithii 'Dixter'	5L: Full Pot: C	Counted
4	Euphorbia griffithii 'Dixter'	5L: Full Pot: C	1/m ²
10	Geranium sanguineum	2L: Full Pot: C	4/m ²

Non thorny native planting				
Number	Species	Specification	Density	Percentage Contribution
114	Acer campestre	1+1: Transplant - seed raised: B	1/m ²	20%
57	Cornus alba	Branched: 2 brks: C	1/m ²	10%
57	Corylus avellana	1+2: Transplant - seed raised: Branched: 4 brks: B	1/m ²	10%
57	Euonymus europaeus	1+1: Transplant - seed raised: Branched: 3 brks: B	1/m ²	10%
86	Fagus sylvatica	1+1: Transplant - seed raised: B	1/m ²	15%
199	Viburnum opulus	1+1: Transplant - seed raised: Branched: 2 brks: B	1/m ²	35%
Total :570				

Native Hedge				
Number	Species	Specification	Density	Percentage Contribution
9	Acer campestre	tpt: 60-90cm	3/m ²	20%
27	Crataegus monogyna	tpt: 60-90cm	3/m ²	60%
3	Ilex aquifolium	tpt: 20-40cm	3/m ²	5%
3	Ligustrum vulgare	tpt: 40-60cm	3/m ²	5%
3	Rosa canina	tpt: 40-60cm	3/m ²	5%
3	Viburnum opulus	tpt: 40-60cm	3/m ²	5%
Total :48				

Lawns to be sown with BS Quality Hard Wearing Lawn Seed at 35grms/m²
80% amenity perennial ryegrass and 20% strong creeping red fescue






80% Dwarf Amenity Perennial Ryegrass

Varieties selected from the Sports Turf Research Institute's recommended list for wear-tolerance and recovery from stress.
High shoot density, fine-leaved and year-round colour.
Quick to establish, long-lasting and hard-wearing.
20% Strong Creeping Red Fescue

Versatile creeping fescue species to complement the rapid-growing Perennial Ryegrass. Horizontal, creeping growth suppresses weeds and ensures a thick, tough and resilient sward.

Boston Seeds, Manor Road, Kirton, Boston
Lincolnshire, PE20 1PH, UK
T: 01205 280 069

Key

-  Existing Trees to be removed
-  Existing Trees to be retained
-  Proposed Tree Planting
-  Proposed Shrub and Hedge Planting
-  Grass

Rev.	Date	Description of Revisions	Drawn	Cl'd	App

Do not scale dimensions off this drawing. Check all dimensions on site & report any errors to Petrow Harley.
This drawing is copyright & must not be reproduced without consent from PH.

PETROW HARLEY
Landscape Architects
The Studio, 57 Lime Grove, New Malden, Surrey KT3 3TP
t: 020 8949 0803 e: mail@petrow-harley.com

Client: Mr Lee Smith

Project Title: Range Cottage, Chilcomb Lane, Chilcomb, Winchester SO21 1HU

Drawing Title: Planting Plan

Status: Scale: 1:200@A1 Drawn: RP Checked: HJ Date: Jan 2024

Drawing No. 1046-L-02 Rev



- Native Hedge Mix
- 9 No. Acer campestre 20%
 - 27 No. Crataegus monogyna 60%
 - 3 No. Ilex aquifolium 5%
 - 3 No. Ligustrum vulgare 5%
 - 3 No. Rosa canina 5%
 - 3 No. Viburnum opulus 5%

- 3 No. Euphorbia griffithii 'Dixter'
- 10 No. Geranium sanguineum
- 15 No. Alchemilla mollis
- 3 No. Euphorbia griffithii 'Dixter'
- 1 No. Viburnum opulus
- 4 No. Euphorbia griffithii 'Dixter'

- 3 No. Carpinus betulus 'Frans Fontaine'
- 3 No. Acer campestre 'Streetwise'

- Leyland Cypress & Golden Monterey Cypress

- 1 No. Carpinus betulus 'Frans Fontaine'

- Non thorny native mix
- 114 No. Acer campestre 20%
 - 57 No. Cornus alba 10%
 - 57 No. Corylus avellana 10%
 - 57 No. Euonymus europaeus 10%
 - 86 No. Fagus sylvatica 15%
 - 199 No. Viburnum opulus 35%

