



**Notes**

**Floodlighting Equipment**  
 4 x 15m Masts (M1-M4)  
 Each carrying the following Floodlights :-  
 M1-M4  
 ...4 x Siteco FL11-3 Blade-PL33T  
 ...1 x Siteco FL11-2 Blade-PL33T

M1.....Rear Cowl  
 M2.....Rear & Side Cowl  
 M4.....Side Cowl

**Siteco LED - 5,000K CRI 70**

**Illuminance Levels**  
**Initial** -  
 (100hrs) E.i.ave = 336Lux  
**Maintained** -  
 (50,000hrs) E.i.ave = 302Lux

**Uniformity**  
 Emin/Eave = 0.70

Grid values in Lux(initial).  
 Grid interval = 5m.  
 Contour values in Lux (initial).  
 Contours: 5, 15, 25, 50 Lux.

**Maintenance Factor = 0.90**  
 (Based on a cleaning interval of 2 years)



[www.halliday-lighting.co.uk](http://www.halliday-lighting.co.uk)

Project  
 Ardrossan Winter Rovers

Drawing Title  
 Proposed floodlighting

Drawn By (print) DS	Date 24/08/2023
------------------------	--------------------

Project No 7113	Scale NTS
--------------------	--------------

Drawing No HLS7113	Status Proposal
-----------------------	--------------------