



NOTES
 It is the contractors responsibility to check design levels and sizes for compliance. Any discrepancies or errors to be identified to the design team.

General Arrangement drawing to indicate the new facility.

Total 3G Synthetic Turf - Pitch Area

Length	- 104.5m
Width	- 66.5m
Total	- 6950 m²

Full-size Football Line Markings

11v 11 Football	(White, in-laid)
Length	- 98.5m (3m run-off)
Width	- 66.5m (3m run-off)

Pitch Dimensions as per IFAB Laws of the Game

Additional 3G Synthetic Turf Excess Run-off Area

Total	- 665m²
(No Shockpad Requirement in this Area)	


KEY

- New 3G 50mm Synthetic Turf including Shockpad
- New 3G Synthetic Turf within Run-off Extension Area
- Indicative Team Shelter Location
- Indicative Floodlight Column Location

REVISION	DETAILS	BY	DATE	CHECKED



**ARDROSSAN WINTON ROVERS
 NEW BUILD 3G PITCH
 GENERAL ARRANGEMENT**



Date: 08/2023	Job No. 3199	Drawn by: GS
Scale: 1:500 @ A3	Checked by: DD	