



NOTES
 It is the contractors responsibility to check design levels and sizes for compliance. Any discrepancies or errors to be identified to the design team.

General Arrangement drawing to indicate the new facility.

Total Site Preparation Surface Area

Total - 7615 m²


- RESIDUAL HERBICIDE TREATMENT
 - TOPSOIL STRIP, EXCAVATE SUB SOILS TO NEW PITCH FORMATION LEVEL inc COMPACTION OF FORMATION.
 -REMOVAL OF EXISTING SOCKETED FOOTBALL GOALS

- SOIL SEPARATOR MEMBRANE
 -TRI-AXIAL GEO-GRID
 -INSTALLATION OF SUB-BASE, COMPACTED AND SUITABLY GRADED MOD TYPE 1 inc BLINDING LAYER
 - OPTIONAL POROUS ASPHALT ENGINEERED LAYER
 - NEW DRAINAGE SYSTEM

REVISION	DETAILS	BY	DATE	CHECKED



ARDROSSAN WINTON ROVERS
 NEW BUILD 3G PITCH
 SITE PREPARATION



Date: 08/2023 Scale: 1:500 @ A3	Job. No. 3199	Drawn by: GS Checked by: DD
------------------------------------	---------------	--------------------------------