



Domiz[®] Prime



If you are looking for a slightly greyer finish to your roof, Domiz is the perfect choice. Its rich blue-grey overtones, coupled with a deep, bold texture, give you a stunning finish every time.



Product information



Product profile

SSQ Domiz slate is mined and hand split exclusively for SSQ from the Orense region in North-West Spain. The region is renowned for its high-performance roofing slates. Domiz slate has been in use in the UK and Ireland since 1996, offering a long track record of proven quality and lasting aesthetic beauty.

Domiz achieves excellent results when tested to the BS EN 12326 achieving the all-important “W1-T1-S1” classification. Domiz also complies with the arduous Norm Francais (NF 228), which has the strictest slate testing criteria and procedures in the world.*

* Test results are available on request

Minimum headlap for fixing slates with nails or hooks according to BS 5534: 2014+A2:2018 Code of Practice for Slating and Tiling Moderate exposure (< 56.5 l/m2 per spell)*

Size (mm)	Rafter pitch								
	20°	22.5°	25°	27.5°	30°	35°	40°	45°	80°
600 x 300	130	120	95	85	80	70	60	55	50
500 x 250	–	150	120	100	80	70	60	55	50
400 x 250	–	–	–	–	80	70	60	55	50
400 x 200	–	–	–	–	80	70	60	55	50

Severe exposure (≥ 56.5 l/m2 per spell)*

Size (mm)	Rafter pitch								
	20°	22.5°	25°	27.5°	30°	35°	40°	45°	80°
600 x 300	150	140	130	120	100	90	80	70	65
500 x 250	–	–	–	130	100	90	80	70	65
400 x 250	–	–	–	–	100	90	80	70	65
400 x 200	–	–	–	–	120	110	105	100	65

Size and weight

Size (mm)	Thickness (mm)	Weight per 1000 (kg)
600 x 300	6 - 8	3900
600 x 300	5 - 7	3024
500 x 250	5 - 6	2100
400 x 250	5 - 6	1680
400 x 200	5 - 6	1344

The information, both technical and otherwise contained within this guide, is intended to provide illustrations on some of the ways in which SSQ products may be used and should be read in conjunction with all relevant British Standards, Codes of Practice and Health and Safety Legislation. Nothing contained in this brochure nor any advice or recommendation given by or on behalf of SSQ is intended to be relied upon in substitution for an appropriate technical and design appraisal of the specific use to which SSQ products will be put. SSQ will accept no responsibility for any loss or damage howsoever caused that may arise through the reliance being placed on the content of the brochure.

SSQ reserve the right to change designs and specifications without prior notice. All products are subject to our Terms of Business, available on request. The information and illustrations in this publication were correct at the time of publication.

SSQ Head Office: 301 Elveden Road, Park Royal, London NW10 7SS

T: +44 (0) 20 8961 7725 F: +44 (0) 20 8965 7013

SSQ Northern Irish Office: The YARD Group, 50 Moira Road, Aldergrove, Crumlin, BT29 4JL

T: +44 (0) 79 1239 0505

SSO Spanish Office: C/Academia Dequit No. 11° A, 32300 El Barco de Valdeorras, Orense, Spain

E: info@ssq.co.uk W: www.ssqgroup.com

© Registered trademark, SSQ Group, September 2020

Appearance

Domiz is rich in blue-grey overtones, coupled with deep bold texture, similar in appearance to the Ffestiniog Welsh quarry. It is increasingly being chosen by specifiers as a robust alternative to this material

Guarantee

SSQ Domiz Prime blue-grey roofing slate is covered by a 75-year guarantee.**

In addition to the above fitness for purpose guarantee, SSQ now also offers a full Rust Free guarantee to ensure total peace of mind and 100% satisfaction.

SSQ is the only company in the industry that provides this, given the confidence it places in its premium range of slates.

For more information on the terms of this industry leading guarantee, please visit www.ssqgroup.com/rustfree

** Guarantees to be requested within 6 months of the date of completion of the roof.

Coverage

Nail fixing method

Size (mm)	Lap (mm)								
	50	65	75	80	90	100	110	115	120
	Number of slates/m ²								
600 x 300	12.1	12.5	12.7	12.8	13.1	13.3	13.6	13.7	13.9
500 x 250	17.8	18.4	18.8	19.0	19.5	20.0	20.5	20.8	21.0
400 x 250	22.9	23.9	24.6	25.0	25.8	26.7	27.6	28.1	28.6
400 x 200	28.6	29.9	30.8	31.3	32.3	33.3	34.5	35.1	35.7

(NB: No allowance has been made for wastage*)

Hook fixing method

Size (mm)	Lap (mm)								
	50	65	75	80	90	100	110	115	120
	Number of slates/m ²								
600 x 300	12.1	12.5	12.7	12.8	13.1	13.3	13.6	13.7	13.9
500 x 250	17.8	18.4	18.8	19.0	19.5	20.0	20.5	20.8	21.0
400 x 250	22.9	23.9	24.6	25.0	25.8	26.7	27.6	28.1	28.6
400 x 200	28.6	29.9	30.8	31.3	32.3	33.3	34.5	35.1	35.7

(NB: No allowance has been made for wastage*)

* Please refer to the SSQ Natural Roofing Slate Design and Fixing Guide for full details (available on www.ssqgroup.com).



EXCLUSIVELY NATURAL SLATE