



**CLUMBER RED MIXTURE**

**BUTTERLEY**  
BRICK

# CLUMBER RED MIXTURE



**Manufactured to BS EN 771-1**

**Brick type**

Category II, U, Clay Masonry Unit

**Standard work size**

215 x 102.5 x 65mm

**Dimensional tolerances**

Tolerance category: T2

Range category: R1

**Compressive strength**

≥ 30N/mm<sup>2</sup>

**Water absorption**

≤ 17%

**Durability**

F2

**Active soluble salts content**

S2

**Configuration**

Vertically Perforated 13-25% Voids

**Dry weight per brick**

2.05kg

**Pack size**

495

**Factory**

Kirton

**EAN**

5057595001672

**SKU**

SKIRCLX1600VO

**Sales** +44 (0) 330 1231017

**Technical** +44 (0) 330 1231018

**Email** [bricks@forterra.co.uk](mailto:bricks@forterra.co.uk)

Disclaimer: The reproduction of colours and textures is only as accurate as the printing process will allow. Photographic samples should be used when shortlisting products but we advise that an actual sample should be seen before ordering.

