



NOTES:-

1. All surface water drainage to be 110mm dia Osmadrain or similar approved all bedded as detailed on drawing 17404/17.
2. All inspection chambers to be OSMA Universal polypropylene inspection chambers (PPICs) (or similar) 450mm dia up to 1200 depth and 600mm up to 3000 depth unless otherwise noted.
3. Covers to PPICs to be B125.
4. All RWP droppers to have rodding access covers at low level.
5. Intesio Aquacell Lite soakaway to be wrapped in Terram 1000 non-woven geotextile (or similar) and surrounded with 100 thk coarse sand.

AquaCell Lite Soakaway (or similar approved) Depth of units on plan. Top of units 44.00. All to manufacturer's recommendations

6LB600 silt trap bedded on and surrounded with pea gravel
CL 45.50
IL 42.70

ACO RainWater outlet

New precast concrete manhole

4000

2000

Vent

New pathway in landscape

| Rev | Details | Date | Checked |
|-----|---|----------|---------|
| E | ACO outlet moved. | 31.01.24 | |
| D | Inverts and notes amended. | 30.01.24 | |
| C | Plan and drainage updated, new path added. | 17.11.23 | |
| B | Drainage re-routed around new terrace and soakaway increased. | 16.11.23 | |
| A | SWS moved away for porch | 23.03.22 | |

HWA (Structural Engineers) Ltd
 Consulting Civil & Structural Engineers
 64 Yoxall Road, Shirley, Solihull, West Midlands. B90 3RP
 Tel 0121 745 7600 e-mail engineers@h-w-a.co.uk

Architect:-
 Brownhill Hayward Brown
 Georgian House
 24 Bird Street
 Lichfield
 Staffs WS13 6PT

Project
Brinton Park
Kidderminster DY11 6QU
Parks for People

Title
Sons of Rest
Drainage Scheme
Details

Drawing No.
17404/16 E

Scale As shown @ A3
 Drawn jsm Date Nov 2023
 Checked