

Fittings / LED Floodlights


150/225/300W Skyline Virtus Wattage Switchable Asymmetric Floodlight - 4000K



Designed and engineered in the UK specifically to meet the requirements for sports lighting and to reduce light pollution levels. The Skyline Virtus is a high specification floodlight, wattage switchable as standard with a 50,000 hour lifespan, 7 year warranty and 2 year on site warranty.

- Wattage Switchable
- Perfect for sports, building facade's, landscape, security & car park lighting
- Asymmetric distribution, low light pollution
- Aerodynamic, streamlined design for reduced windage
- Air pressure equalisation feature to eliminate capillary effect
- Nichia GRT-V1 LED
- Surge protected 10,000V
- Fully encapsulated IP54 TUV certified driver
- Supplied pre-flexed (1.5M)
- Robust construction, supplied with standard universal mounting bracket

Technical Specification



	50/75/100W	100/150/200W	100/225/300W
A	35mm	447mm	495mm
B	287mm	359mm	419mm
C	65mm	75mm	75mm

Product Code 11491

Reference

Guarantee 7 Years

Country Of Origin CN

Technical Specification

Volts (V)	110-240
Watts (W)	150/225/300
Colour Temp (K)	4000
Lumens (lm)	22400-46050
Life Hours	50,000
CRI (Ra)	80
Switching Cycles	100,000
Frequency (Hz)	50/60
Energy Consumption (kWh/1000h)	132
IP Rating	IP66

Dimensions

Height (mm)	495
Width (mm)	417
Depth (mm)	75

Packaging Information

Single Carton Height (mm)	52.5
Single Carton Width (mm)	45
Single Carton Depth (mm)	11.5
Single Carton Weight (KG)	7.1
Individual Volume	0.027168750000000002