










Element		Product	Finish	Colour	Example Image
Walls	Facing Brickwork	Reclaimed Brickwork	Stretcher Bond	Red	
	Flint and brick Walls	Knapped Flints framed with reclaimed bricks	Laid in courses with hydraulic lime mortar	Natural	
	Cladding to Dormer Windows	Timber shiplap boards	Light Oak	Natural	
Roof	Clay Roof Tiles	Reclaimed plain tile	To match existing	Red	
	Leadwork to Dormer Roofs	Lead Roof Covering with wood cored rolls	As Supplied	Natural	
Window and doors	Timber Framework and Panels	Oak framed windows and doors	Light Oak	Natural	
	Rooflights	Conservation Rooflights	As supplied	Black	
Rainwater goods	Gutter, Brackets and Downpipes	Cast Iron	As supplied	Black	
Hardstanding	External Paving to Courtyard	Stone Cobbles	Stone	Natural	

notes:

revisions: A | 08.02.2024 | JT | Updated to include flint wall specification

revisions:

Mr a& Mrs Cornell  
**Corner Cottage**  
 High Street, Bosham



**drawing information** title : **New Extension Materials Schedule**

status : Information  
 date : Nov 23  
 scale : N/A  
 drawn : JT  
 checked : IV

job: 5961 dwg: 7000 rev: A

PWP Architects Ltd 61 South Street, Havant, Hampshire PO9 1BZ  
 t: 02392 482494 f: 02392 481152  
 e: design@pwp-architects.com  
 w: www.pwp-architects.com



NOTE: The contractor is responsible for checking all site dimensions and levels. These should be checked prior to the ordering of any components and before the commencement of the works. All discrepancies should be brought to the attention of the Contract Administrator.

100mm @A3