

MANHOLE SCHEDULE

Manhole Number	Cover Level	Connections	Pipe			Manhole Size	Types	
			Code	Inverts	Diams		Manhole	Cover
H8								
E. 509020.890 N. 154502.701							PCC HEADWALL 45DEG TS	
AS28								
E. 509021.592 N. 154507.893	59.500 1.375		1	1.006	58.575	225	1500	Control D400
H9								
E. 509023.090 N. 154521.643							PCC HEADWALL	
H11								
E. 509018.223 N. 154546.438							PCC HEADWALL 45DEG TS	
H12								
E. 509011.647 N. 154579.192			1	4.000	56.500	300		PCC HEADWALL
H15								
E. 509012.643 N. 154584.119			0	1.011	56.500	300		PCC HEADWALL 45DEG TS

MANHOLE SCHEDULE

Manhole Number	Cover Level	Connections	Pipe			Manhole Size	Types	
			Code	Inverts	Diams		Manhole	Cover
AS33								
E. 509020.731 N. 154589.887	57.790 1.160		1	1.011	56.480	300	1500	Control D400
H16								
E. 509023.236 N. 154594.799			1	1.012	56.439	150		INSITU HEADWALL
AS35								
E. 509009.561 N. 154492.772	60.017 1.270		0	2.000	58.675	225	1200	C D400
H17								
E. 509019.088 N. 154497.222			1	2.000	58.600	225		PCC HEADWALL
AS37								
E. 508900.835 N. 154414.071	60.583 1.126		0	3.000	59.157	300	1200	C D400
AS38								
E. 508891.534 N. 154437.669	60.281 1.206		1	3.000	58.755	300	1200	C D400

MANHOLE SCHEDULE

Manhole Number	Cover Level	Connections	Pipe			Manhole Size	Types	
			Code	Inverts	Diams		Manhole	Cover
AS39								
E. 508884.811 N. 154455.284	60.032 1.200		1	3.001	58.532	300	1500	C D400
AS40								
E. 508908.191 N. 154464.248	60.097 1.422		1	3.002	58.375	300	1200	C D400
AS41								
E. 508936.017 N. 154477.430	59.717 1.287		1	3.003	58.130	300	1500	C D400
AS42								
E. 508945.705 N. 154489.145	59.583 1.216		1	3.004	58.067	300	1500	C D400
AS43								
E. 509004.804 N. 154512.935	59.800 1.645		1	3.005	57.780	375	1500	B D400
H10								
E. 509020.544 N. 154524.396			1	3.006	57.725	375		PCC HEADWALL

MANHOLE SCHEDULE

Manhole Number	Cover Level	Connections	Pipe			Manhole Size	Types	
			Code	Inverts	Diams		Manhole	Cover
AS45								
E. 508934.906 N. 154505.196	59.468 1.068		0	4.000	58.100	300	1200	C D400
AS46								
E. 508915.013 N. 154544.646	58.996 1.471		1	4.001	57.225	300	1500	C D400
AS47								
E. 508968.782 N. 154570.600	58.400 1.450		1	4.001	56.650	300	1200	C D400
H14								
E. 508995.813 N. 154576.904			1	4.002	56.500	300		PCC HEADWALL
AS49								
E. 508995.547 N. 154557.732	58.704 1.200		0	5.000	57.279	225	1200	C D400
H13								
E. 509001.472 N. 154576.703			1	5.000	56.500	225		PCC HEADWALL

MANHOLE SCHEDULE

Manhole Number	Cover Level	Connections	Pipe			Manhole Size	Types	
			Code	Inverts	Diams		Manhole	Cover
AS51								
E. 509036.919 N. 154433.105	60.400 1.369		0	1.005	58.655	375	1350	C D400
AS54								
E. 509081.672 N. 154455.350	59.900 1.577		1	1.003	58.098	225	1200	B D400
AS55								
E. 509074.346 N. 154444.186	59.500 1.341		1	1.004	58.099	150	1200	C D400
AS56								
E. 509075.215 N. 154433.117	59.500 1.415		1	1.005	57.935	150	1200	C D400
AS57								
E. 509018.311 N. 154564.933	58.750 1.410		1	1.006	57.935	150	1200	C D400

REV	DATE	AMENDMENT	BY	CHKD
H	13.02.24	Headwall types noted	LK	LRW
G	27.04.23	AS43 and AS35 inverts amended	LRW	LRW
F	26.04.23	Control chamber diameters updated to 1500	LRW	LRW
E	21.04.23	Control chamber diameters issued for construction	LRW	LRW
D	29.03.23	AS51 co-ords updated	DJB	LRW
C	02.02.23	Schedule Updated	DJB	LRW
B	25.11.22	AF1-AFS Cover Levels and Depth to Soffit Levels updated.	DJB	LRW
A	10.08.22	Control chambers noted Infrastructure Phase Manhole added	DJB	LRW

PROJECT Ockham Road East Horsley	CLIENT Taylor Wimpey	DRAWING Adoptable Manhole Schedules Sheet 2 of 2	DATE 05.05.22	<p>13 Capricorn Centre Dunelm Farm Road Bristol Bris 5014 3JJ</p> <p>01280 330 000 01280 330 000 www.walker-associates.co.uk</p>
DRAWN BY DJP		DRG NO.	C7476/CE23	
CHECKED BY LRW		STATUS TENDER		