

Eastern Green Link 2 Environmental Statement Addendum – Relocated Haul Route East of Newsholme

National Grid Electricity Transmission

March 2024

Delivering a better world

### Quality information

| Prepared by   | Verified by                      | Approved by |
|---|----------------------------------|-------------|
| Adele Knowles<br>Senior Environmental<br>Consultant | Simon Wild<br>Technical Director |             |

Prepared for: National Grid Electricity Transmission

Prepared by:

Adele Knowles Senior Environmental Consultant E: adele.knowles@aecom.com

AECOM Limited 2 City Walk Holbeck Leeds LS11 9AR

T: +44(0)113 391 6800 aecom.com

© 2024 AECOM Limited. All Rights Reserved.

This document has been prepared by AECOM Limited ("AECOM") for sole use of our client (the "Client") in accordance with generally accepted consultancy principles, the budget for fees and the terms of reference agreed between AECOM and the Client. Any information provided by third parties and referred to herein has not been checked or verified by AECOM, unless otherwise expressly stated in the document. No third party may rely upon this document without the prior and express written agreement of AECOM.

## **Table of Contents**

| Non-  | Technical Summary                       | 1  |
|-------|---|----|
| 1.    | Introduction                            | 2  |
| 2.    | Original ES Introduction                | 3  |
| 3.    | Alternatives                            | 3  |
| 4.    | Project Description                     | 3  |
| 5.    | Planning Policy Context                 | 4  |
| 6.    | Approach to EIA                         |    |
| 7.    | Stakeholder Engagement and Consultation | 4  |
| 8.    | Technical Topics Chapters 7 - 16        | 5  |
| 9.    | Outline CEMP                            | 12 |
| 10.   | Summary                                 | 12 |
| Figur | es                                      | 13 |
| Appe  | endix A : Outline CEMP                  | 14 |

# **Abbreviations and Definitions**

| Term                          | Definition   |
|-------------------------------|--|
| EGL2                          | Eastern Green Link 2   |
| EOS                           | English Onshore Scheme - Approximately 69 km of underground high-voltage direct current (HVDC) cable from the landfall at Fraisthorpe within East Riding Yorkshire Council (ERYC). |
| ES                            | Environmental Statement  |
| Original ES                   | The Environmental Statement submitted in June 2022 for the English Onshore Scheme element of Eastern Green Link 2.   |
| Proposed Relocated Haul Route | The subject of this ES Addendum. Relocated haul route for the construction of EGL2 EOS East of Newsholme.  |
| HDD                           | Horizontal Directional Drilling. A construction technique whereby a tunnel is drilled and a pipeline or other utility is pulled through the tunnel.                                |
| NGET                          | National Grid Energy Transmission (The Applicant)  |

# **Non-Technical Summary**

AECOM prepared an Environmental Statement (ES) (referred to as the 'Original ES' herein) for the English Onshore Scheme (EOS) element of Eastern Green Link 2 (EGL2) that accompanied the planning application submitted in June 2022 for the "Construction of sub-surface cable route from Drax Power Station to Fraisthorpe Coastline with associated accesses and temporary construction compounds in association with the Scotland to England Green Link". The planning application was approved by East Riding of Yorkshire Council (ERYC) in March 2023.

The Original ES has been updated (in the format of this ES Addendum) to consider the impact of design changes to Section 3: Market Weighton to River Ouse of the EOS sub-surface cable route, located east of Newsholme. The design alternatives are in response to engagement with landowners affected by the EOS east of Newsholme. While the cable route passes under and avoids the affected land via Horizontal Directional Drilling (HDD) in a broadly north to south direction, a temporary haul route designed for use during the construction works follows the path of the cable route above ground, and has impacts on a Christmas tree farm in this location. Moving the temporary haul route further to the east (referred to herein as 'the Proposed Relocated Haul Route') provides an alternative which would avoid disruption to the business, whilst also meeting the construction requirements of EGL2.

This ES Addendum concludes that the Proposed Relocated Haul Route East of Newsholme to support the EOS design/ alignment would result in no changes to the significance of environmental effects as reported within the Original ES. Therefore, the conclusions of the Original ES remain unchanged.

# 1. Introduction

- 1.1.1 The Eastern Green Link 2 (EGL2) comprises the Scottish Onshore Scheme, the Marine Offshore Scheme and the English Onshore Scheme (EOS). This document concerns the EOS which comprises approximately 69 kilometres (km) of underground high-voltage direct current (HVDC) cable from the landfall at Fraisthorpe within the administrative area of East Riding of Yorkshire Council (ERYC), to the proposed converter station at Drax, located within the administrative area of North Yorkshire Council (NYC) (formerly Selby District Council) (hereafter referred to as the 'Approved Development').
- 1.1.2 An Environmental Statement (ES) was prepared by AECOM on behalf of National Grid Energy Transmission (NGET) (referred to hereafter as 'the Applicant') for the EOS, reporting the results of the Environmental Impacts Assessment (EIA). The ES (hereafter referred to as the 'Original ES') reported the environmental impacts and effects associated with the EOS construction, operation and decommissioning, and was submitted with the planning application in June 2022. ERYC approved the planning application for the Approved Development in March 2023.
- 1.1.3 The extent of the Approved Development spans a number of landownership boundaries. While the cable route passes under the affected land via a HDD in a broadly north to south direction, a temporary haul route designed for use during the construction works follows the path of the cable route above ground, and has impacts on a Christmas tree farm in this location. Since submission of the planning application, the applicant has engaged with the affected landowners of the Christmas tree farm east of Newsholme, with a desire to understand and work positively and safely with their business requirements during the construction period.
- 1.1.4 Moving the temporary haul route further to the east (referred to herein as 'the Proposed Relocated Haul Route') provides an alternative which would avoid disruption to the business, whilst also meeting the construction requirements of EGL2. As a result, a planning application is being submitted to ERYC for a relocated temporary haul route and associated accesses, avoiding the Christmas tree farm by crossing north to south within an adjacent agricultural field.
- 1.1.5 This ES Addendum has been prepared to set out the findings of a review of the EIA conclusions reported in the Original ES with regards to amendments to the design of the EOS (namely the Proposed Relocated Haul Route) (see Section 3 for further information) refer to Figure 1 at the back of this ES Addendum and Plate 1 below.
- 1.1.6 The Proposed Relocated Haul Route East of Newsholme is located within Section 3: Market Weighton to River Ouse of the EOS. This ES Addendum reports an update to the impact assessments as presented in the Original ES taking account of the characteristics of the Proposed Relocated Haul Route to determine whether the conclusions of the Original ES remain valid and robust.
- 1.1.7 This ES Addendum is structured in the same way as the Original ES to enable easy cross-reference, and should be read in conjunction with the Original ES which details the existing and future baseline conditions, the assessment methodology, relevant legislation and policy, the original impact assessment findings, as well as impact avoidance and mitigation measures.
- 1.1.8 All sections of this ES Addendum have been prepared by suitably qualified environmental specialists at AECOM.




Plate 1: Site Location Plan showing the Proposed Relocated Haul Route East of Newsholme

# 2. Original ES Introduction

2.1.1 Chapter 1 of the Original ES remains unchanged and therefore remains valid.

# 3. Alternatives

- 3.1.1 Chapter 2 of the Original ES sets out the alternative design options considered prior to the definition of a preferred alignment for the EOS. No changes have been made to the alternatives considered, therefore the Original ES chapter remains valid.
- 3.1.2 The Proposed Relocated Haul Route East of Newsholme was not considered as an alternative route option within the Original ES, as it does not alter the cable route of the original EOS. Therefore, it is the subject of the assessment reported herein.

# 4. Project Description

4.1.1 Chapter 3 of the Original ES provides a description of the Site and the surrounding area, as well as a description of the EOS. While additions to the layout of the EOS are proposed (refer to paragraph 4.1.2), these design changes are localised to the area east of the village of Newsholme. The remainder of the EOS planning application red line boundary (see Figure 1: Site Location Plan) and reported distances to identified sensitive receptors remain unchanged. Changes to the distances between the EOS and receptors as a result of the Proposed Relocated Haul Route East of Newsholme are discussed below and within Section 8 of this ES Addendum.

- 4.1.2 The relocation of the temporary haul route for the EOS has been presented since the Original ES was prepared and is an alternative to avoid economic impacts on the affected landowners (as shown on Figures 1, 2 and 3). The EOS design changes comprise the following:
  - Provision of a new temporary haul route (the Proposed Relocated Haul Route), approximately 1 km in length and accessed via the A63 Hull Road approximately 290 m to the east of the EOS cable alignment. The new temporary haul route north of the A63 Hull Road will cross an unnamed minor drain via a new culvert and follow back alongside this road from east to west to meet the EOS cable alignment, where the A63 (Newsholme) Primary Compound, one of three primary compounds on the EOS route, can be accessed. South of the A63 Hull Road, the new temporary haul route will travel south for approximately 130 m through agricultural land and will cross New Drain via a new culvert, where it follows the drain from east to west to meet the EOS cable alignment.
  - Provision of three temporary drainage ponds. One will be situated immediately east of the new temporary haul route and north of the A63 Hull Road, whilst two will be situated immediately east of the new temporary haul route, north and south of the southern unnamed drain respectively.
- 4.1.3 The new temporary haul road will comprise a circa 0.5 m deep layer of unbound granular material with the potential for geogrid layers to be used for stabilisation. Where the haul road will be built up, pipes will be installed to ensure natural drainage pathways are maintained across the haul road.
- 4.1.4 All temporary accesses will be removed at the end of the construction programme, and the land returned to its previous use.

# 5. Planning Policy Context

- 5.1.1 Chapter 4 of the Original ES provides an overview of the planning policies relevant to the EOS.
- 5.1.2 Since the submission of the planning application (and Original ES) minor changes have been made to the emerging local plan (submitted for examination March 2023), the National Planning Policy Framework (NPPF) (updated September and December 2023) and the Overarching National Policy Statement for Energy (EN-1) (November 2023), though these updates are not considered to be directly relevant to the Proposed Relocated Haul Route east of Newsholme. For this reason, there have been no material updates to national or local legislation or policies of relevance to the EOS, so the Original ES chapter remains valid.

# 6. Approach to EIA

6.1.1 Chapter 5 of the Original ES sets out the EIA methodology. No changes have been made to the EIA methodology, therefore, the Original ES chapter remains valid.

# 7. Stakeholder Engagement and Consultation

7.1.1 Chapter 6 of the Original ES sets out an overview of the consultation activities that were carried out during the EIA process for the EOS. No additional consultation activities have been undertaken since the submission of the Original ES, and therefore the Original ES chapter remains valid.

# 8. Technical Topics Chapters 7 - 16

- 8.1.1 Figures 2 and 3 show the environmental constraints located within proximity to the Proposed Relocated Haul Route east of Newsholme. Taking into account the characteristics of the Proposed Relocated Haul Route (as detailed in Section 4) and the nearby environmental constraints, Table 8-1 presents a summary of potential changes to the EIA findings as reported in the Original ES.
- 8.1.2 Table 8-1 indicates that the Proposed Relocated Haul Route east of Newsholme does not result in any changes to the conclusions as reported within the Original ES.
- 8.1.3 The screening questions as detailed in Table 8-1 are in line with the Town and Country Planning (Environmental Impact Assessment) Regulations 2017 Screening Matrix, provided by the Planning Inspectorate<sup>1</sup>.

<sup>1</sup> <u>https://www.gov.uk/government/publications/environmental-impact-assessment-screening-checklist</u>

| (Part A) Screening Criteria Question  | (Part B-1) Summary of effects as reported in the Original ES (as consented), and references to further information (Part B).<br>Answer to the question and explanation of reasons (Yes/No or Not Known (?) or N/A).  | (Part B-2) Summary of potential change to effects as reported in the<br>Original ES.<br>If applicable and/ or known, include name of feature and proximity to<br>site.  | (Part C) (only if potential change to effects<br>(Yes/No or Not Known (?) or N/A)<br>Is a significant effect likely, having regard p   |
|---|--|---|--|
|   | (If answer in Part B is 'No Change', the answer to Part C is 'N/A')  |   | <ul> <li>(including population size affected), nature,<br/>duration, frequency and reversibility of the<br/>impact?</li> <li>If the finding of no significant effect is reliar<br/>envisaged to avoid, or prevent what might of</li> </ul>   |
|   |  |   | environment, these should be identified in t   |
| NATURAL RESOURCES   |  |   |  |
| Will construction, operation or<br>decommissioning of the project<br>involve actions which will cause<br>physical changes in the topography<br>of the area?   | Yes – installation of the haul route during construction of the EOS will<br>result in very minor, temporary changes to the topography of the area<br>east of Newsholme.<br>All temporary haul routes and accesses will be removed at the end of<br>the construction programme, resulting in no permanent changes to<br>the topography of the area east of Newsholme.   | Proposed Relocated Haul Route is longer in length (approx.1 km) than that<br>originally proposed (approx. 308 m). However, the same installation<br>methodology as proposed in the original ES will be implemented, whilst the<br>same mitigation measures as outlined in the Original ES Chapter 18: Outline<br>Construction Environmental Management Plan (CEMP) (and Appendix A of<br>this document) will be used.   | No likely significant effects after mitigation.  |
| Will construction or operation of the<br>project use natural resources above<br>or below ground such as land, soil,<br>water, materials/minerals or energy<br>which are non-renewable or in short<br>supply?                | N/A – irrelevant to the EOS.   | N/A   | N/A  |
| Are there any areas on/around the<br>location which contain important,<br>high quality or scarce resources which<br>could be affected by the project, e.g.<br>forestry, agriculture, water/coastal,<br>fisheries, minerals? | N/A – there are no areas applicable in proximity to the EOS.   | N/A   | N/A  |
| WASTE   |  |   |  |
| Will the project produce solid wastes<br>during construction or operation or<br>decommissioning?  | After the implementation of relevant mitigation measures (as detailed<br>in the Original ES) during construction, generation and management<br>of waste effects are assessed as being minor adverse (not<br>significant). Decommissioning effects are assumed to be similar to<br>those that would occur during the construction phase in terms of<br>waste generation.  | Waste arising from haul road establishment during construction is anticipated<br>to be minimal based on professional judgement. Final waste arisings will be<br>subject to contractor design. The materials (aggregates and/or stones)<br>required for temporary construction of haul roads is likely to be re-used by<br>other projects after the completion of the construction works.<br>The increased length in the Proposed Relocated Haul Route is not  | No likely significant effects after mitigation. The to Chapter 16: Waste and Materials Managemen Management Plan (SMP) and Site Waste Mana Contractor. Implementation of such measures the generation and management of waste that significant).   |
| POLILITION AND NURSANCES  | There will be no waste generated during the operation phase.   | anticipated to generate significantly more waste than the original haul road.   |  |
| POLLUTION AND NUISANCES<br>Will the project release pollutants or<br>any hazardous, toxic or noxious<br>substances to air?  | No change – an air quality assessment was scoped out of the EIA.   | N/A   | N/A  |
| Will the project cause noise and<br>vibration or release of light, heat,<br>energy or electromagnetic radiation?  | During construction works within Section 3, with the adoption of best practicable means and enforcement actions (as detailed in the Original ES), it was assessed that there would be a negligible/minor (not significant) adverse noise effect at Receptor 57, which is considered representative of the residents in Newsholme Village, located approximately 278 m from the original temporary haul route. Any effects would be short term and temporary.   | The Proposed Relocated Haul Route is positioned at a distance further away<br>from Receptor 57 (Newsholme Village), resulting in the working area moving<br>away from residential receptors.<br>The Proposed Relocated Haul Route will, however, be situated<br>approximately 110 m closer to Park House Farm, which is located<br>approximately 230 m north-east of the relocated haul route.  | No likely significant noise effects after mitigatio<br>(refer to Section 13.7 and Appendix A: Outline<br>construction activities, means there will be no o<br>the Original ES. The significance of the noise e<br>significant) at Receptor 57.<br>It is anticipated that construction noise at Park<br>of the closer proximity to the Proposed Relocat   |
|   | Construction traffic effects were assessed as being negligible (not significant).<br>Construction vibration effects were assessed, at worst, as minor adverse (not significant) at the nearest sensitive receptors due to separation distances.<br>The impact of light, heat, energy and electromagnetic radiation are not considered relevant and were scoped out of the assessment.  |   | temporary nature of the construction works, co<br>Outline CEMP, will not result in a significant ad<br>from noise.   |
| Will the project lead to risks of<br>contamination of land or water from<br>releases of pollutants onto the<br>ground or into surface waters,<br>groundwater, coastal waters or the<br>sea?                                 | With the incorporation of appropriate mitigation measures (as detailed<br>in the Original ES and Appendix A: Outline CEMP), the residual<br>effects during construction from haul roads, accesses and water<br>crossings on water resources within Section 3 of the EOS range<br>between negligible and minor adverse (not significant).<br>New Drain, a non-designated ordinary watercourse with an Internal<br>Drainage Board (IDB) maintained channel, will be crossed by the<br>temporary haul route presented in the Original ES, using an existing<br>culvert. No other water resources cross or lie in the vicinity of the<br>temporary haul route as presented in the Original ES. | Two non-designated watercourses intersect the Proposed Relocated Haul<br>Route. These are New Drain and an unnamed unmaintained minor drain. In<br>both cases, it is intended by the applicant to cross these watercourses using<br>new temporary culverts. These will be installed using the same methodology<br>described in the Original ES Chapter 11: Hydrology and Land Drainage. No<br>other water resources cross or lie in the vicinity of the Proposed Relocated<br>Haul Route.<br>Aside from the two temporary water crossings, the Proposed Relocated Haul<br>Route is materially no different in establishment methodology and frequency/<br>nature of use by construction vehicles to that proposed in the Original ES. | <ul> <li>The low sensitivity of the minor drains and implichange to the risk of contaminated runoff, and adverse (not significant). The same mitigation of CEMP (Appendix A) to prevent and manage rist.</li> <li>A Drainage Strategy incorporating a Site D commencement of works. The Drainage Strategy drainage systems detailed drainage investigations (e.g. to ide and hydrological assessments, which will or water and natural environment and identify</li> </ul> |

#### Table 8-1: Summary of changes within the technical topic chapters within the Original ES as associated with the Proposed Relocated Haul Route East of Newsholme

#### s reported in Part B-2) – Is a Significant Effect Likely?

I particularly to the magnitude and spatial extent re, intensity and complexity, probability, expected onset, e impact and the possibility to effectively reduce the

iant on specific features or measures of the project t otherwise have been, significant adverse effects on the n bold.

The mitigation measures as set out within the Original ES (refer ement and Appendix A: Outline CEMP) that includes a Soil Management Plan (SWMP) to be developed by the appointed res means that there will be no change to the residual effect for hat is reported in the Original ES (minor adverse, not

ation. The mitigation measures as set out within the Original ES ine CEMP) and given the distance to receptors from no change to the significance of noise effects as reported within se effect, therefore, remains as negligible/minor adverse (not

ark House Farm will increase by approximately 3dB as a result ocated Haul Route. This minor increase in noise levels and the , combined with embedded mitigation outlined in Appendix A: t adverse effect to the residential receptors at Park House Farm

mplementation of embedded mitigation would result in minimal and therefore the significance of effect remains negligible/minor on measures as outlined in the Original ES Chapter 18: Outline e risks of contamination will be used. These include:

e Drainage Plan (SDP) will be prepared prior to the e Strategy will specify measures to minimise the impact of ms (manmade and natural). This will be developed following identify underground sewers and surface water drains etc.) *i*ll determine potential location specific risks in relation to the ntify appropriate control measures to reduce the risks.

| (Part A) Screening Criteria Question  | (Part B-1) Summary of effects as reported in the Original ES (as consented), and references to further information (Part B).<br>Answer to the question and explanation of reasons (Yes/No or Not Known (?) or N/A).   | (Part B-2) Summary of potential change to effects as reported in the<br>Original ES.<br>If applicable and/ or known, include name of feature and proximity to<br>site.   | (Part C) (only if potential change to effects<br>(Yes/No or Not Known (?) or N/A)<br>Is a significant effect likely, having regard (   |
|---|---|--|--|
|   | (If answer in Part B is 'No Change', the answer to Part C is 'N/A')   |  | (including population size affected), nature<br>duration, frequency and reversibility of the<br>impact?<br>If the finding of no significant effect is relia  |
|   |   |  | envisaged to avoid, or prevent what might<br>environment, these should be identified in  |
|   |   |  | <ul> <li>An appropriate drainage system will be ind<br/>This will include header and filter drains, u<br/>crossings and ensure runoff is directed int<br/>contaminants before discharging (to local<br/>agreed with the relevant regulator.</li> </ul>   |
|   |   |  | Suitable sizing of the culvert pipe to accom<br>accordance with the Design Manual for Re   |
|   |   |  | <ul> <li>Sitting of the culvert at hard bed level whe potential for scour. These will allow free pahabitat/morphological bar and riffle feature bed level, however this will be limited to ch concern for fish and eel passage. These w stakeholder (Environment Agency, Local L</li> <li>All hard banks and bed added during consto its original stabilised state after construct vegetating/seeding to replace any lost habitation.</li> </ul>   |
| Are there any areas on or around the<br>location which are already subject to<br>pollution or environmental damage,<br>e.g. where existing legal<br>environmental standards are<br>exceeded, which could be affected<br>by the project?                   | N/A – there are no applicable areas located in the vicinity of the Proposed Relocated Haul Route.   | N/A  | N/A  |
| POPULATION & HUMAN HEALTH   |   |  |  |
| Will there be any risk of major<br>accidents (including those caused<br>by climate change, in accordance<br>with scientific knowledge) during<br>construction, operation or<br>decommissioning?   | No – an assessment of major accidents and disasters was scoped out of the EIA.  | N/A  | N/A  |
| Will the project present a risk to the<br>population (having regard to<br>population density) and their human<br>health during construction,<br>operation or decommissioning? (for<br>example due to water contamination<br>or air pollution)             | No – with the incorporation of appropriate mitigation measures (as detailed in the Original ES and Appendix A: Outline CEMP), the EOS will not present a human health risk to the local population.<br>An assessment of human health was scoped out of the EIA.   | N/A  | N/A  |
| WATER RESOURCES   |   |  |  |
| Are there any water resources<br>including surface waters, e.g. rivers,<br>lakes/ponds, coastal or underground<br>waters on or around the location<br>which could be affected by the<br>project, particularly in terms of their<br>volume and flood risk? | With the incorporation of appropriate mitigation measures (as detailed<br>in Chapter 11: Hydrology and Land Drainage of the Original ES and<br>Appendix A: Outline CEMP), the residual effects during construction<br>from haul roads, accesses and water crossings on flood risk within<br>Section 3 of the EOS ranges between negligible and minor adverse<br>(not significant).<br>New Drain, a non-designated ordinary watercourse with an IDB<br>maintained channel, was to be crossed by the temporary haul route<br>as presented in the Original ES using an existing culvert. No other<br>water resources cross or lie in the vicinity of the temporary haul route<br>as presented in the Original ES.<br>Part of the haul road as presented in the Original ES lies within Flood<br>Zone 2 from fluvially dominated sources. | Two non-designated watercourses intersect the Proposed Relocated Haul<br>Route. These are New Drain and an unnamed unmaintained minor drain. In<br>both cases, it is intended by the applicant to cross these watercourses using<br>new temporary culverts. These will be installed using the same methodology<br>described in the Original ES Chapter 11: Hydrology and Land Drainage. No<br>other water resources cross or lie in the vicinity of the Proposed Relocated<br>Haul Route.<br>The section of the Proposed Relocated Haul Route south of the A63 Hull<br>Road lies within Flood Zone 3 from fluvially dominated sources (see Figure<br>2). | <ul> <li>With the incorporation of appropriate mitigation<br/>Drainage of the Original ES and Appendix A: 0<br/>during construction from haul roads, accesses<br/>EOS (negligible/minor adverse, not significant</li> <li>A Drainage Strategy incorporating a SDP<br/>The Drainage Strategy will specify measure<br/>drainage systems (manmade and natural)<br/>investigations (e.g. to identify underground<br/>assessments, which will determine potenti<br/>environment and identify appropriate contri-<br/>this will include header and filter drains, un<br/>crossings and ensure runoff is directed int<br/>contaminants before discharging (to load<br/>agreed with the relevant regulator.</li> <li>Suitable sizing of the culvert pipe to accom-<br/>accordance with DMRB standards.</li> <li>Sitting of the culvert at hard bed level whe<br/>potential for scour.</li> </ul> |

#### ts reported in Part B-2) – Is a Significant Effect Likely?

d particularly to the magnitude and spatial extent ure, intensity and complexity, probability, expected onset, he impact and the possibility to effectively reduce the

liant on specific features or measures of the project ht otherwise have been, significant adverse effects on the in bold.

incorporated to manage surface water and sediment runoff. s, use of sandbags either side of the haul road at watercourse into attenuation ponds to remove sediment and potential cal watercourse or infiltration) at a controlled rate which is to be

commodate the natural water regime (volumes and flows), in Roads and Bridges (DMRB) standards.

where possible and orientated with flows to limit obstruction and e passage for fish and eels and be sited to avoid spawning tures. In some cases, temporary culverts may be above hard o channels which are balanced systems with little flow and no e will be determined on a case by case basis with the relevant al Lead Flood Authority, IDB).

onstruction will be temporary and the bankside will be returned truction, including re-grading were required and rehabitat and vegetation or trees.

tion measures (as detailed in Chapter 11: Hydrology and Land A: Outline CEMP), there will be no change in the residual effects ses and water crossings on flood risk within Section 3 of the ant). Measures include:

DP will be prepared prior to the commencement of the works. Issures to minimise the impact of construction on existing ral). This will be developed following detailed drainage und sewers and surface water drains etc.) and hydrological ential location specific risks in relation to the water and natural portrol measures to reduce the risks.

incorporated to manage surface water and sediment runoff. s, use of sandbags either side of the haul road at watercourse into attenuation ponds to remove sediment and potential cal watercourse or infiltration) at a controlled rate which is to be

commodate the natural water regime (volumes and flows), in

here possible and orientated with flows to limit obstruction and

| (Part A) Screening Criteria Question   | (Part B-1) Summary of effects as reported in the Original ES (as consented), and references to further information (Part B).<br>Answer to the question and explanation of reasons (Yes/No or Not Known (?) or N/A).   | (Part B-2) Summary of potential change to effects as reported in the<br>Original ES.<br>If applicable and/ or known, include name of feature and proximity to<br>site.   | (Part C) (only if potential change to effects re<br>(Yes/No or Not Known (?) or N/A)<br>Is a significant effect likely, having regard pa   |
|--|---|--|--|
|  | (If answer in Part B is 'No Change', the answer to Part C is 'N/A')   |  | <ul> <li>(including population size affected), nature,<br/>duration, frequency and reversibility of the in<br/>impact?</li> <li>If the finding of no significant effect is relian<br/>envisaged to avoid, or prevent what might of<br/>environment, these should be identified in b</li> </ul>   |
| BIODIVERSITY (SPECIES AND HABIT  | ATS)  |  |  |
| Are there any protected areas which<br>are designated or classified for their<br>terrestrial, avian and marine<br>ecological value, or any non-<br>designated / non-classified areas<br>which are important or sensitive for<br>reasons of their terrestrial, avian and<br>marine ecological value, located on<br>or around the location and which<br>could be affected by the project?<br>(e.g. wetlands, watercourses or<br>other water-bodies, the coastal zone,<br>mountains, forests or woodlands,<br>undesignated nature reserves or<br>parks. (Where designated indicate<br>level of designation (international,<br>national, regional or local))). | Yes.<br>One statutory designated site, the Barn Hill Meadows Site of Special<br>Scientific Interest (SSSI), was scoped into the assessment located<br>within Section 3 of the EOS (where the Proposed Relocated Haul<br>Route east of Newsholme is situated). The SSSI site is identified as a<br>UK Priority Habitat, made up predominantly of Lowland Meadow and<br>Deciduous Woodland, and part of the SSSI also makes up the<br>Yarmshaw Plantation Local Wildlife Site (LWS). The SSSI is<br>approximately 692 m south-east from the planning application<br>boundary at its nearest point.<br>There will be no direct impacts on the SSSI, which is entirely avoided<br>by the EOS. Two indirectly connecting non-designated watercourses<br>are New Drain and Black Dyke which cross the A63 between the<br>planning application boundary and the SSSI. The temporary access<br>route reported in the Original ES uses an existing farm track along the<br>southern side of New Drain and crosses the watercourse using<br>existing culvert crossings which were not proposed to be widened.<br>It is assessed that with embedded mitigation, the potential effect upon<br>the SSSI and LWS is negligible (not significant). | In addition to New Drain, which will be crossed using a new temporary<br>culvert rather than using an existing culvert (as per the original ES), there is<br>one other non-designated unnamed and unmaintained dry ditch connected<br>to Black Dyke which will be crossed by the Proposed Relocated Haul Route.<br>This will be crossed using the same methodology as assumed in the Original<br>ES. The culverts will be installed using the same methodology as described<br>in the Original ES Chapter 11: Hydrology and Land Drainage. | No likely significant effects after mitigation.<br>The nature and location of the Proposed Reloca<br>assessed within the Original ES, and thus the a<br>additional direct or indirect environmental impac<br>LWS.<br>As assessed in the Original ES Chapter 11: Hyd<br>water resources when construction temporary h<br>construction surface water management plan. T<br>any discharge from the installation of the cable a<br>measures will be secured within the CEMP, alor<br>quality is maintained and water flow is not imper |
| Could any protected, important or<br>sensitive species of flora or fauna<br>which use areas on or around the<br>site, e.g. for breeding, nesting,<br>foraging, resting, over-wintering, or<br>migration, be affected by the<br>project?  | Habitat type         Yes - The section of the EOS route and temporary haul route east of Newsholme was identified in the Original ES as being made up of a mix of cultivated/disturbed arable land, improved grassland, coniferous woodland plantation, mixed woodland plantation and some non-designated drainage ditches with species poor hedgerows around the perimeter of some fields.         The temporary access route reported in the Original ES crosses New Drain, as previously described. The impact of the EOS during construction on non-designated running water (including drains) causing a decrease in quality and loss of habitat function was assessed to be negligible to minor adverse (not significant) with the implementation of defined embedded mitigation measures.         All other habitat types were not considered to be of more than site nature conservation value and therefore were not considered within the EIA.         For further information refer to the Original ES Chapter 7: Ecology and Nature Conservation.   | The Proposed Relocated Haul Route does not impact any habitat types<br>considered to be more than of site nature conservation value. The Proposed<br>Relocated Haul Route will impact a similar mix and quantity of natural habitat<br>types when compared to the alignment as assessed within the Original ES.<br>An additional non-designated drain will be crossed by the Proposed<br>Relocated Haul Route.   | No likely significant effects after mitigation.<br>Embedded mitigation, particularly the use of mid<br>detailed in Appendix A: Outline CEMP, applies t<br>Mitigation specific to non-designated running wa<br>discharge or abstraction into watercourses, min<br>removal and restoration of channel bed materia<br>on channel and adjacent vegetation. Reconstru-<br>also be undertaken.<br>For further information see the original EOS ES<br>and Chapter 18: Outline Construction Environm                                       |
|  | Bats         Yes – A bat roost potential assessment carried out to inform the         Original ES identified two structures as having low bat roost potential         (ID312 and ID313). Both sit within the planning application boundary         of the EOS, however only ID313 is within the working width of the         cable route and is likely to be affected by the temporary haul route (as         proposed in the Original ES).         The effects of the EOS cable route as a whole during construction on         roosting and foraging bats were assessed to be negligible to minor         adverse (not significant) after implementation of defined mitigation         measures.         For further information see the Original ES Chapter 7: Ecology and         Nature Conservation and Appendix 7B: Bat Survey Report.   | No Change.<br>The Proposed Relocated Haul Route would not change the impacts upon<br>ID312 and ID313 as assessed in the Original ES.   | N/A  |
|  | Water vole and Otter<br>Yes - A water vole and otter habitat assessment undertaken to inform<br>the Original ES identified two small drains intersecting/in close<br>proximity to the temporary haul route as presented in the Original ES,<br>east of Newsholme (WC79 and WC80, Black Dyke and New Drain<br>respectively).<br>WC79 was identified as a shallow 10 cm deep ditch and assessed to<br>be unlikely to support Otter or Water Vole. The watercourse is not  | The Proposed Relocated Haul Route will cross New Drain (WC80) at a section further east than was presented in the Original ES. This will also be subject to further assessment as proposed in the Original ES.<br>The Proposed Relocated Haul Route will result in the crossing of an additional drain. This drain was not considered in the assessment presented in the Original ES, as it was unlikely from desk-based studies to support  | <ul> <li>No likely significant effects to Water Vole and O mitigation. This includes:</li> <li>At watercourse crossings where Otter and/o potential for Otter and/or Water Vole to be p inform detailed design and where possible t</li> <li>Where Otter and/or Water Vole are identifie – restriction of night time working in proximation</li> </ul>   |

#### s reported in Part B-2) – Is a Significant Effect Likely?

I particularly to the magnitude and spatial extent re, intensity and complexity, probability, expected onset, re impact and the possibility to effectively reduce the

iant on specific features or measures of the project t otherwise have been, significant adverse effects on the n bold.

ocated Haul Route is not materially different from that as e amended haul route alignment will not cause any new or pacts upon the Barn Hill Meadows SSSI/Yarmshaw Plantation

Hydrology and Land Drainage, effects upon local surface ry haul roads will be mitigated through adoption of a n. This includes measures to intercept run-off and ensure that ble and temporary haul road construction is controlled. These along with pollution prevention measures to ensure water npeded by temporary culverts.

micro-siting to avoid and/or minimise vegetation clearance as tes to the Proposed Relocated Haul Route.

g water include pollution control measures and preventing minimisation of working width, reduction in encroachment, erials and reinstatement of marginal habitat to minimise effects struction of the bank and channel to preconstruction state will

ES Volume 2 Chapter 7: Ecology and Nature Conservation, nmental Management Plan.

d Otter are anticipated with the implementation of applicable

nd/or Water Vole have been identified previously or there is be present, pre-construction surveys will be undertaken to ble to avoid habitat suitable to support Otter and/or Water Vole. tified:

oximity to known Otter and/or Water Vole habitat;

| (Part A) Screening Criteria Question  | (Part B-1) Summary of effects as reported in the Original ES (as consented), and references to further information (Part B).<br>Answer to the question and explanation of reasons (Yes/No or Not Known (?) or N/A).   | (Part B-2) Summary of potential change to effects as reported in the<br>Original ES.<br>If applicable and/ or known, include name of feature and proximity to<br>site.  | (Part C) (only if potential change to effects<br>(Yes/No or Not Known (?) or N/A)<br>Is a significant effect likely, having regard   |
|---|---|---|--|
|   | (If answer in Part B is 'No Change', the answer to Part C is 'N/A')   |   | <ul> <li>(including population size affected), natur<br/>duration, frequency and reversibility of the<br/>impact?</li> <li>If the finding of no significant effect is reli<br/>envisaged to avoid, or prevent what might<br/>environment, these should be identified in</li> </ul>   |
|   | directly affected by the orignal temporary haul route east of<br>Newsholme as presented in the ES, however further assessment to<br>determine presence/absence is required at other sections of the EOS<br>route. WC80 was identified as a slow flowing ditch approximately 3 m<br>wide and up to 40 cm deep, and assessed to be likely to support<br>water vole and/or otter. Further assessment for riparian mammals will<br>be required prior to haul route crossing.<br>The effects of the EOS cable route as a whole during construction on<br>water vole and otter were assessed to be negligible to minor adverse<br>(not significant) after the implementation of defined mitigation<br>measures.<br>For further information refer to the Original ES Chapter 7: Ecology<br>and Nature Conservation and Appendix 7C: Water Vole and Otter<br>Survey Report. | Otter or Water Vole due to its small size. However, the drain does feed into<br>and connect to Black Dyke (WC79) which is subject to further assessment.  | <ul> <li>maintenance of barrier free movemen<br/>proposed.</li> <li>Once works are complete the constru-<br/>reinstated and enhanced where spec<br/>habitat will be re-seeded with plant sp<br/>or reed will be included in the seed m<br/>bank side top soil immediately followi</li> <li>Embedded mitigation will be implement<br/>measures and preventing discharge</li> <li>For further information see the original EOS I<br/>and Chapter 18: Outline Construction Environ</li> </ul> |
|   | <b>Breeding Birds</b><br>No breeding birds of conservation concern were either confirmed,<br>probably or possibly breeding within the region of the temporary haul<br>route east of Newsholme as assessed within the original EOS ES.<br>The impact of the EOS as a whole during construction on breeding<br>birds was assessed to be minor adverse (not significant) after<br>mitigation measures were considered.<br>For further information see original EOS ES Volume 2 Chapter 7:<br>Ecology and Nature Conservation, and Volume 3 Appendix 7D:<br>Ornithology Report.   | No change.<br>The nature and location of the Proposed Relocated Haul Route is not<br>materially different from that as assessed within the Original ES, so it is not<br>anticipated to result in any new or additional direct or indirect environmental<br>impacts on breeding birds of conservation concern.<br>A small section of hedgerow will need to be removed to facilitate the<br>Proposed Relocated Haul Route, however given the abundance of other<br>available suitable habitat within the vicinity, and with the implementation of<br>defined embedded mitigation measures, there is no change (or additional<br>effects) to those as reported in the Original ES.<br>The same mitigation measures for breeding birds as detailed in the Original<br>ES will be applied to the Proposed Relocated Haul Route works.  | N/A  |
|   | Great Crested Newt (GCN)<br>Waterbodies P239 and P240 are located to the north-west of the<br>EOS, within 250 m from where the temporary haul route as presented<br>in the Original ES is situated. P240 is assumed to have GCN<br>presence.<br>As agreed with Natural England, GCN have been scoped out of the<br>EIA as National Grid are committed to the adoption of District Level<br>Licensing (DLL) scheme for the EOS.  | The Proposed Relocated Haul Route is located outside of the 250 m buffer<br>for Waterbodies P239 and P240. The Proposed Relocated Haul Route is<br>however located to the west of Waterbodies P238 and P237, within 250 m of<br>the new access off the A66 Hull Road. From desk based studies, GCN are<br>absent from P238, however both waterbodies were scoped out of further<br>assessment in the Original ES due to the distance from the EOS as<br>submitted. Whilst no direct effects on these waterbodies will occur, there are<br>no significant barriers to GCN dispersal into terrestrial habitat within the<br>Proposed Relocated Haul Route. It is a requirement that changes to the<br>extent of land affected by the EOS after the issue of the GCN District Level<br>Licensing Impact Assessment & Conservation Payment Certificate (refer to<br>Appendix 7G of the Original ES, received May 2022) are communicated to<br>Natural England during the course of the licensing process. | No change - as agreed with Natural England,<br>The proposed changes do not present a sign<br>the DLL scheme. National Grid is working wit<br>ongoing, to ensure that any design changes a  |
| LANDSCAPE & VISUAL  |   |   |  |
| Are there any areas or features on or<br>around the location which are<br>protected for their landscape and<br>scenic value, and/or any non-<br>designated/ non-classified areas or<br>features of high landscape or scenic<br>value on or around the location<br>which could be affected by the<br>project? Where designated indicate<br>level of designation (international,<br>national, regional or local). | Section 3 extends approximately 25 km across parts of the Vale of<br>York (NCA 28), the Humberhead Levels (NCA 39) and the Yorkshire<br>Wolds (NCA27).<br>The majority of the Zone of Influence of Section 3 does not fall within,<br>or lie in close proximity to, any designated landscape, apart from the<br>westernmost extent of Section 3 which includes a very a small part of<br>the River Derwent Corridor and Lower Derwent Valley Important<br>Landscape Area.<br>The local landscape character context for Section 3 of the EOS<br>comprises Flat Open Farmland, Wooded Open Farmland, Foulness<br>Open Farmland, Open Farmland and River Corridors.<br>No significant effects are reported in the Original ES on landscape   | The Proposed Relocated Haul Route east of Newsholme will not result in the EOS extending into any different designated landscape areas or landscape character areas, therefore there will be no change to the potential impact on designated or featured landscape areas or features (as reported within the Original ES).  | No additional effects on landscape designation Route.  |
| Is the project in a location where it is<br>likely to be highly visible to many<br>people? (If so, from where, what<br>direction, and what distance?)   | designations as a result of the EOS.<br>Yes.<br>The original temporary haul route presented in the Original ES is<br>located to the east of the village Newsholme, approximately 164 m<br>from the nearest residential properties.<br>The nearest Representative Viewpoint Locations to Newsholme are<br>Viewpoint 7: North Howden/Brind public right of way (PRoW) and   | The Proposed Relocated Haul Route will result in a section of the working<br>area moving approximately 91 m further from residential receptors in<br>Newsholme village. Therefore, views of the temporary and short term<br>construction works will be further away than with the original design as<br>assessed within the Original ES.<br>The proposed relocated haul route will, however, be situated approximately<br>110 m closer to Park House Farm, which is located approximately 200 m   | No change in the significance of effects on vi<br>Relocated Haul Route. Despite the works bei<br>will appear in views for a temporary period of<br>not be visible to visual receptors as it will be i<br>roads will be removed and land returned to th   |

cts reported in Part B-2) – Is a Significant Effect Likely?

ard particularly to the magnitude and spatial extent ture, intensity and complexity, probability, expected onset, the impact and the possibility to effectively reduce the

eliant on specific features or measures of the project ght otherwise have been, significant adverse effects on the I in bold.

nent particularly where haul roads over watercourses are

struction access will be removed and the habitat will be becific additional measures are agreed. Bank side grassland it species which are favoured by Water Vole e.g. rushes, sedges d mix or supplemented by re-instatement of removed turves or owing completion of the works.

emented to protect water quality including pollution control ge or abstraction into watercourses.


S ES Volume 2 Chapter 7: Ecology and Nature Conservation, ironmental Management Plan.

nd, GCN have been scoped out of the EIA. ignificant change that would impact the agreed licensing under with Natural England on the DLL process for the EOS, which is es are taken into consideration within the DLL.

ations are anticipated due to the Proposed Relocated Haul

n visual receptors are anticipated as a result of the Proposed being closer to the residents of Park House Farm, construction d of time and for a short duration. Once operational the EOS will be installed underground, and temporary structures such a haul to their previous use.

| (Part A) Screening Criteria Question  | (Part B-1) Summary of effects as reported in the Original ES (as consented), and references to further information (Part B).<br>Answer to the question and explanation of reasons (Yes/No or Not Known (?) or N/A).  | (Part B-2) Summary of potential change to effects as reported in the<br>Original ES.<br>If applicable and/ or known, include name of feature and proximity to<br>site.   | (Part C) (only if potential change to effects<br>(Yes/No or Not Known (?) or N/A)<br>Is a significant effect likely, having regard p   |
|---|--|--|--|
|   | (If answer in Part B is 'No Change', the answer to Part C is 'N/A')  |  | (including population size affected), nature<br>duration, frequency and reversibility of the<br>impact?<br>If the finding of no significant effect is relia  |
|   |  |  | envisaged to avoid, or prevent what might of<br>environment, these should be identified in l   |
|   | Viewpoint 8: Asselby PRoW which are north-east and south-west of Newsholme, respectively. Both Viewpoints were assessed in the Original ES as experiencing minor adverse (not significant) effects during construction of the EOS.   | north-east of the Proposed Relocated Haul Route. Views of the temporary<br>and short term construction works at this property will be closer than with the<br>original design as assessed within the Original ES.  |  |
| CULTURAL HERITAGE/ ARCHAEOLO  | GY   |  |  |
| Are there any areas or features<br>which are protected for their cultural<br>heritage or archaeological value, or<br>any non-designated / classified<br>areas and/or features of cultural<br>heritage or archaeological<br>importance on or around the<br>location which could be affected by<br>the project (including potential<br>impacts on setting, and views to,<br>from and within)? Where designated<br>indicate level of designation<br>(international, national, regional or<br>local). | There are no designated heritage or archaeological assets within<br>proximity to the original temporary haul route as presented in the<br>Original ES, east of Newsholme.<br>After mitigation there are no non-designated heritage assets that<br>would experience significant adverse effects to their setting within<br>proximity to the original temporary haul route as presented in the<br>Original ES. This includes Park House Farm (Reference AECOM100<br>on Figure 2 and in Chapter 9: Archaeology and Cultural Heritage of<br>the Original ES), a non-designated heritage asset of low value. This is<br>assessed as a low magnitude of impact, resulting in a negligible effect<br>of temporary duration (not significant) during the construction period.<br>Known non-designated archaeological assets have been identified in<br>this section of the scheme in relation to the original temporary haul<br>route, namely AECOM020, AECOM021 and AECOM003 (see Figure<br>2, and Chapter 9:Archaeology and Cultural Heritage of the Original<br>ES for further information). The assessment of these non-designated<br>assets within the planning application boundary has determined there<br>would be no effect as a result of construction of the EOS, or that<br>impacts on these assets are considered to be negligible (not<br>significant) due to the low value of the assets. | There is no change to the proximity of designated heritage or archaeological<br>assets in relation to the Proposed Relocated Haul Route.<br>The Proposed Relocated Haul Route will be situated approximately 110 m<br>closer to Park House Farm, which is located approximately 230 m north-east<br>of the relocated haul route.<br>The Proposed Relocated Haul Route is closer to known non-designated<br>archaeological assets identified as MHU18167 and MHU22306. However,<br>the relocated haul route will not transect these assets. The relocated route<br>avoids transecting of AECOM020, while the impacts on AECOM003 and<br>AECOM021 remain unchanged (as reported in the Original ES). | Despite being closer to the non-designated he<br>and temporary duration of the effect, would res<br>the Original ES.<br>With the incorporation of appropriate mitigation<br>Cultural Heritage of the Original ES and Apper<br>significance of effect to non-designated archae<br>value, and the Proposed Relocated Haul Route<br>measures include limiting stripping for haul roa<br>is recorded to avoid disturbance, and instead u   |
| TRANSPORT & ACCESS  |  |  |  |
| Are there any routes on or around<br>the location which are used by the<br>public for access to recreation or<br>other facilities, which could be<br>affected by the project?   | Wressle Footpath no.5 runs north-west of the EOS through<br>Newsholme, but is not intersected by the scheme. No direct impacts<br>on this footpath during construction are anticipated. The traffic impact<br>significance during construction on the A63 Hull Road as a result of<br>heavy goods vehicle (HGV) construction traffic within Section 3 of the<br>EOS was assessed to be negligible (not significant). See Chapter 14:<br>Traffic and Transport of the Original ES for further information.  | The same impacts during construction apply to the Proposed Relocated Haul<br>Route as those reported in the Original ES. No new routes will be affected,<br>and the traffic data forming the basis of the assessment in the Original ES<br>remains the same.<br>The new bellmouth position has greater visibility splays than the original<br>position as assumed in the Original ES. The revised access locations have<br>been developed using the same technical principles which informed the<br>approved access locations under the planning permission for the EOS.   | No change in the significance of effects on tran<br>Proposed Relocated Haul Route. The conclusi<br>remain valid.   |
| Are there any transport routes on or<br>around the location which are<br>susceptible to congestion or which<br>cause environmental problems,<br>which could be affected by the<br>project?  | No – as detailed above.  | N/A  | N/A  |
| LAND USE  |  |  |  |
| Are there existing land uses or<br>community facilities on or around<br>the location which could be affected<br>by the project? E.g. housing,<br>densely populated areas, industry/<br>commerce, farm/agricultural<br>holdings, forestry, tourism, mining,<br>quarrying, facilities relating to<br>health, education, places of worship,<br>leisure/ sports/ recreation.  | Yes – agricultural land will be impacted by construction works and<br>such works may temporary affect access and use of the land.<br>The land impacted by construction works will be returned to its former<br>agricultural use once construction is complete. As such, there would<br>be no permanent impacts as a result of the EOS.   | The Proposed Relocated Haul Route avoids impacts on local business.<br>The 'need' for the planning application comes from project team engagement<br>with affected landowners and a desire to understand and work positively and<br>safely with their business requirements during the construction<br>period. Moving the temporary haul route further south would allow for this<br>objective to be met, whilst also meeting the construction requirements of the<br>EGL2 project.  | It is anticipated that the Proposed Relocated H<br>have on land use in the area east of Newsholm<br>significance of effect from the EOS as a whole<br>Further mitigation measures related to constru<br>Outline CEMP (Appendix A: Outline CEMP) wi<br>Access to agricultural lands will be maintai<br>Damage to the agricultural capability of so<br>stripping, handling and storage of soil mate<br>Existing field drainage systems will be re-in<br>drainage related to flooding issues will not |
| Are there any plans for future land<br>uses on or around the location<br>which could be affected by the<br>project?   | No planning submissions have been registered on the ERYC planning<br>site pertaining to land which is already required for construction of the<br>EOS east of Newsholme.<br>Once operational there will be no additional land use or land take   | N/A  | N/A  |



| (Part A) Screening Criteria Question   | (Part B-1) Summary of effects as reported in the Original ES (as<br>consented), and references to further information (Part B).<br>Answer to the question and explanation of reasons (Yes/No or<br>Not Known (?) or N/A).<br>(If answer in Part B is 'No Change', the answer to Part C is 'N/A') | (Part B-2) Summary of potential change to effects as reported in the<br>Original ES.<br>If applicable and/ or known, include name of feature and proximity to<br>site. | <ul> <li>(Part C) (only if potential change to effects<br/>(Yes/No or Not Known (?) or N/A)</li> <li>Is a significant effect likely, having regard<br/>(including population size affected), nature<br/>duration, frequency and reversibility of the<br/>impact?</li> <li>If the finding of no significant effect is relia<br/>envisaged to avoid, or prevent what might<br/>environment, these should be identified in</li> </ul> |
|--|--|--|--|
| LAND STABILITY & CLIMATE   |  |  |  |
| Is the location susceptible to<br>earthquakes, subsidence,<br>landslides, erosion, or extreme<br>/adverse climatic conditions, e.g.<br>temperature inversions, fogs, severe<br>winds, which could cause the<br>project to present environmental<br>problems? | No – the EOS (including the Proposed Relocated Haul Route) is not located in an area at risk to land stability issues or assessed as being at risk from climatic changes.  | N/A  | No.  |
| CUMULATIVE EFFECTS   |  |  |  |
| Could this project together with<br>existing and/or approved<br>development result in cumulation of<br>impacts together during the<br>construction/operation phase?  | No – no significant cumulative effects are anticipated as a result of the EOS (including the Proposed Relocated Haul Route).   | N/A  | N/A  |
| TRANSBOUNDARY EFFECTS  |  |  |  |
| Is the project likely to lead to transboundary effects?  | No – not relevant to the EOS.  | N/A  | N/A  |

ts reported in Part B-2) – Is a Significant Effect Likely?

rd particularly to the magnitude and spatial extent ure, intensity and complexity, probability, expected onset, the impact and the possibility to effectively reduce the

eliant on specific features or measures of the project ght otherwise have been, significant adverse effects on the i in bold.


# 9. Outline CEMP


- 9.1.1 Chapter 18 of the Original ES presents the Outline Construction Environmental Management Plan (CEMP). There are no changes required to the Outline CEMP as a result of the Proposed Relocated Haul Route east of Newsholme. The Outline CEMP as submitted in the Original ES is appended to this ES Addendum (refer to Appendix A).
- 9.1.2 As detailed with the Table 8-1, the mitigation measures as detailed within the Outline CEMP (refer to Appendix A) will be applied to the Proposed Relocated Haul Route, where relevant.


# 10. Summary

- 10.1.1 Chapter 19 of the Original ES provides a summary of the EIA undertaken for the EOS.
- 10.1.2 Taking into account the findings of this ES Addendum (as reported in Table 8-1), the Proposed Relocated Haul Route will not result in any new or additional significant environmental effects compared to those as reported in the Original ES. For this reason, the conclusions and findings of the Original ES remain valid.












| REFERENCE                  |      |
|----------------------------|------|
| SEGL2_T_ESA1_2_v1_20240304 |      |
| SHEET NUMBER               | DATE |

04/03/2024

1 of 1

Scale @ A3 1:5,000

200 m



# nationalgrid

PROJECT

**EASTERN GREEN LINK 2 - AMENDED** 

HAUL ROUTE EAST OF NEWHOLME KEY Planning Application Boundary Approximate Location of Required Temporary Attenuation Pond and Outfall (To be designed) HDD - Proposed HDD - Unless Otherwise Agreed to be Open Cut DC Cable Alignment – Open Cut Haul Road where Alignment Differs from HVDC Cables DC Cable Route Working Width (40m) Temporary Attenuation Pond and Outfall \* Temporary Construction Compound Temporary Bellmouth and Visibility Splay Watercourse Pond Site of Special Scientific Interest Local Wildlife Site Structure with Bat Roost Potential Low Phase 1 Habitat A3.1 - Broadleaved parkland/scattered trees J2.1.2 - Intact hedge - species-poor HHHH J2.3.2 - Hedge with trees - species-poor J2.6 - Dry ditch A1.1.1 - Broadleaved woodland - semi-natural A1.1.2 - Broadleaved woodland - plantation A1.2.2 - Coniferous woodland - plantation A1.3.2 - Mixed woodland - plantation A2.1 - Scrub - dense/continuous <sup>1</sup> B4 - Improved grassland B6 - Poor semi-improved grassland G1 - Standing water G2 - Running water A J1.1 - Cultivated/disturbed land - arable J1.2 - Cultivated/disturbed land - amenity grassland J3.6 - Buildings J4 - Bare ground Z99 - Hardstanding

\* Temporary Attenuation Pond and Outfall not to scale TITLE

Figure 3 **Environmental Constraints - Ecology** 

| REFERENCE    |                |
|--------------|----------------|
| SEGL2_T_ESA1 | _3_v1_20240304 |

SHEET NUMBER 1 of 1

DATE 04/03/2024

# **Appendix A : Outline CEMP**

Appended directly from the Original ES

# Scotland England Green Link 2 -English Onshore Scheme

Environmental Statement: Volume 2

Chapter 18: Outline Construction Environmental Management Plan

May 2022

For: National Grid Electricity Transmission

## **Table of Contents**

| 18. | Outlin | ne Construction Environmental Management Plan |      |
|-----|--------|---|------|
|     | 18.1   | Introduction                                  |      |
|     | 18.2   | Project Location                              |      |
|     | 18.3   | Roles and Responsibilities                    | 18-5 |
|     | 18.4   | Communications, Reporting and Training        |      |
|     | 18.5   | Construction Environmental Management         |      |
|     | 18.6   | Specific Environmental Requirements           |      |
|     | 18.7   | Summary                                       |      |
|     | 18.8   | References                                    |      |

## **Figures**

| Figure 18-1: English Onshore Scheme |       |
|-------------------------------------|-------|
| Figure 18-2: Water Hierarchy        | 18-23 |
| Figure 18-3: Waste hierarchy        | 18-58 |

### **Tables**

| Table 18-1: Pre-Construction Plans and Procedures                        | 3-4 |
|--|-----|
| Table 18-2: Permitted Waste Sites in 10 km of the English Onshore Scheme | -59 |

## 18. Outline Construction Environmental Management Plan

## **18.1 Introduction**

### **18.1.1 Project Summary**

National Grid Electricity Transmission (NGET) owns and operates the high voltage electricity transmission system in England and Wales. NGET has a statutory duty to ensure electricity is transported safely and efficiently from where it is produced to where it is needed. To meet this obligation, in collaboration with Scottish and Southern Energy Networks (SSEN) who own and operate the high-voltage electricity transmission network in northern and western Scotland, NGET is proposing the construction a new High Voltage Direct Current (HVDC) link from Peterhead in Aberdeenshire, Scotland, to Drax in North Yorkshire, England, via a subsea connection. This Outline Construction Environmental Management Plan (CEMP) relates to the English Onshore Scheme only. The English Onshore Scheme comprises the following elements:

- Transition Joint Pit (TJP) which will connect the offshore HVDC cables to the onshore cables, at a landfall located landward of the existing headland at Fraisthorpe, East Yorkshire;
- Approximately 69 km of two underground HVDC cables (and fibre optic cable(s) for performance monitoring) between the TJP and the proposed converter station immediately east of the existing Drax Power Station;
- New converter station buildings and outdoor electrical equipment together with formation of internal roads, erection of security fencing and provision of landscaping as well as the construction of a permanent access road from New Road; and
- Approximately 500 m of six underground HVAC cables connecting the new converter station to the National Electrical Transmission System (NETS) via the existing Drax 400 kilovolt (kV) Substation.

Additionally, to enable construction activities, there will be a requirement for associated temporary construction areas referred to as compounds, laydown and storage areas. These temporary construction areas are typically utilised for the storage of plant and machinery and stockpiling materials, as well as the provision of site management offices, welfare facilities for staff (kitchen facilities, storerooms, toilet facilities), parking, and plant and material storage. A summary of the construction compounds to be established for the English Onshore Scheme is provided below:

- One landfall-specific compound provided for HDD installation across the intertidal area. This area will also accommodate the TJP to join marine and terrestrial cables together;
- Three primary major cable compounds at either end of the scheme and one central location;
- 10 secondary construction compounds; and
- Four tertiary construction compounds.

### **18.1.2 Purpose of the Construction Environmental Management Plan**

This Outline CEMP aims to ensure that any adverse effects of construction on the environment and local communities are minimised. To achieve this, the Outline CEMP establishes a framework within which the appointed Contractor (including any sub-contractors or suppliers involved in the works) will plan, implement and deliver environmental management, mitigation and monitoring requirements during the construction phase of the English Onshore Scheme. The controls and procedures contained within it are the practical means by which the mitigation commitments made in the Environmental Statement (ES) will be implemented. The objectives of these controls and procedures are:

- Provide a mechanism for ensuring that measures to mitigate potentially adverse environmental impacts are implemented;
- Ensure that environmental good practices are adopted throughout the construction of the English Onshore Scheme;

- Ensure a prompt response if any unacceptable adverse impacts are identified, with the provision of appropriate additional mitigation measures as required;
- Provide a means for mitigating impacts that may not be anticipated or become apparent until construction is underway;
- Provide assurance to consultees and other stakeholders that requirements with respect to environmental mitigation are being addressed;
- Provide a mechanism for compliance auditing to ensure mitigation measures are being effectively implemented and maintained through construction;
- Implement a policy of potential reuse of all waste with disposal off site being a last resort (aligned to the waste hierarchy; and
- Enable full compliance to be maintained with all relevant legislation.

It is intended that this Outline CEMP will be finalised by the appointed Contractor prior to the start of construction based on a detailed scheme design and construction programme. The Detailed (or construction issue) CEMP will cover all construction activities, clearly set out roles and responsibilities and provide contact details for key personnel. It is also intended that the Detailed CEMP will be a 'live' document and will be updated as and when there are changes to the project team or when additional information becomes available (for example through detailed civil design or additional data supply or surveys such as pre-construction ecological surveys). Due to the scale of the English Onshore Scheme different Contractors may be appointed to deliver different elements of the scheme, additionally the Contractor(s) are likely to produce separate detailed CEMP for the different elements of the English Onshore Scheme (for example for DC cable installation, and the converter station) to better focus of the specific environmental considerations of each element. The various CEMPs will all include the foundations of the Outline CEMP and the relevant mitigation per component in Section 18.6.

Compliance with the contents of the Detailed CEMP is therefore intended to provide a systematic approach to environmental management so that environmental risks are identified, incorporated in all decision-making and managed appropriately. Detailed construction techniques and supporting Risk Assessment Method Statements (RAMS), which will outline further mitigation requirements based on the measures discussed in the CEMP and any supporting appendices, will be produced by the Contractor.

The Detailed CEMPs will be agreed with ERYC and SDC in advance of the start of construction. As a minimum the Detailed CEMPs should be formally reviewed every six months by the project HSE team and within a week following a high potential environmental incident; and passed to NGET for approval prior to reissue.

### 18.1.3 Compliance with Project Environmental Management Systems (EMS) and Sustainability

NGET is committed to delivering sustainability and good environmental stewardship. In accordance with this proactive approach to sustainable design and construction, NGET and the appointed Contractor will seek to maximise resource efficiency through reducing the amount of waste generated, minimising water consumption and making the most efficient use of energy.

The carbon footprint of the English Onshore Scheme will be reduced during construction by avoiding CO<sub>2</sub> emissions where possible through, for example, keeping construction vehicle movements to the minimum necessary. The design of the converter station will also incorporate sustainability principals and Building Research Establishment Environmental Assessment Method (BREEAM) certification, which considers energy and water use, the internal environment (health and well-being), pollution, transport, materials, waste, ecology and management processes. The aim is for 'Very Good' with aspiration towards CEEQUAL "Excellent" for a Whole Team Award.

NGET manages and reduces their effects on the environment via an Environmental Management System (EMS). The EMS is accredited to ISO14001:2015 and provides a framework for NGET to deliver continual environmental assessment and improvement and comply with current legislation and environmental commitments. The appointed Contractor will prepare their own Project EMS in accordance with NGET's EMS prior to construction commencing. The Project EMS is expected to be integrated into the Contractor's own EMS arrangements and will address:

- Compliance with the CEMP and any other control and management documents;
- Compliance with environmental consents and permits;
- Overall compliance with environmental legislation, approved codes of practice, British Standards and industry best practice;
- Detailed environmental management procedures to deliver the CEMP and other control and management plans including roles and responsibilities;
- Monitoring and review arrangements;
- Emergency procedures that are defined and adopted; and
- Appropriate training and information for personnel.

### 18.1.4 Considerate Constructors Scheme (CCS)

The English Onshore Scheme will be registered with the Considerate Constructors Scheme (CCS). CCS is a national initiative through which construction sites and companies (contractors, subcontractors and suppliers) are monitored against a Code of Considerate Practice. The Code is designed to encourage environmental and social best-practice during the construction period beyond statutory requirements.

The main areas of focus are respecting the local community, valuing the workforce and caring for the environment. In light of the size of the English Onshore Scheme, it is envisaged that there will be a minimum of two CCS audit visits.

### 18.1.5 Structure

This Outline CEMP is split into six sections as detailed below:

- Section 18.1: Introduction provides background information about the English Onshore Scheme and an overview of the contents of this Outline CEMP;
- Section 18.2: Project Description provides an overview of the proposed English Onshore Scheme including a description of construction methods;
- Section 18.3: Roles and Responsibilities Sets out the roles and responsibilities of the parties involved in construction;
- Section 18.4: Communications, Reporting and Training Sets out the requirements for regular communications and reporting as well as staff training;
- Section 18.5: Construction Environmental Management Sets out the general requirements with respect to environmental management during construction; and
- Section 18.6: Specific Environmental Requirements Sets out the specific environmental requirements identified by each topic discipline within the ES, per phase of the English Onshore Scheme.

**Appendix 18A** presents an indicative list of legislation that is typically applicable to the construction phase of projects, for example those relating to protected species listed under the Wildlife and Countryside Act 1981 (as amended) and invasive species listed under Schedule 9 of the Wildlife and Countryside Act 1981 (as amended). The list will need to be reviewed by the Contractor prior to the commencement of construction. Legislation confirmed as applicable to the English Onshore Scheme will form the basis of the legal register.

### **18.1.6 Other Construction Mitigation Plans**

Error! Reference source not found. lists the plans and procedures that could be developed prior to construction to set out in detail the management systems and approach that will be implemented during construction to comply with the Detailed CEMP. These will be produced as part of the development of the Detailed CEMPs where relevant to the applicable component of the English Onshore Scheme (i.e. DC cable and/or the converter station).

### Table 18-1: Pre-Construction Plans and Procedures

| Plan / Procedure   | Description   |
|--|---|
| Stakeholder<br>Communications Plan<br>(SCP)  | To be developed by the Contractor post-consent. This plan will include measures for community engagement before and during work on site.  |
| Safety Health and Environment (SHE) Plan   | To be developed by the Contractor post-consent. The plan will detail the relevant safety, health and environmental information relating to construction activities.   |
| Site Waste Management<br>Plan (SWMP)   | To be developed by the Contractor post-consent based upon the Outline SWMP presented in <b>Appendix 16A</b> of this ES. This will set out and identify site-specific measures for the collection, segregation, treatment and disposal of waste.   |
| Construction Traffic<br>Management Plan (CTMP)   | To be developed by the Contractor post-consent based upon the Outline CTMP presented in <b>Appendix 14D</b> of this ES. This will set out the requirements for the safe movement of project related traffic both within the site and <i>en route</i> to and from the site.  |
| Travel Plan  | Prior to the commencement of works, the Contractor will prepare a Travel Plan that supports and encourages sustainable travel by workers (public transport, cycling, walking and car-sharing).  |
| Construction Logistics Plan  | Prior to the commencement of works, the Contractor will prepare a Construction Logistics Plan to manage the sustainable delivery of goods and materials. This will be a live document and will be reviewed updated throughout the lifetime of the construction works as required.   |
| Traffic Incident<br>Management Plan  | Prior to the commencement of works, the Contractor will prepare a Traffic Incident<br>Management Plan. This will set out emergency response measures, including<br>reporting requirements, in the event of a traffic accident either on site, or involving<br>site traffic on the public highway.   |
| Construction Route Hazard<br>Risk Register   | Prior to the commencement of works, the Contractor will produce a Construction<br>Route Hazard Risk Register (or similar). This will identify risks and locations along<br>with possible additional mitigation measures to be considered further during<br>detailed design and Detailed CTMP implementation.  |
| Abnormal Indivisible Load<br>Report  | Prior to the commencement of works, the Contractor will produce an Abnormal<br>Indivisible Load (AIL) report to assess the transformer delivery to the converter<br>station to demonstrate that a suitable route is available from the port of import to<br>the proposed converter station site.  |
| Road Condition Survey  | The Contractor will carry out a Road Condition Survey (also referred to as a dilapidation survey) prior to any enabling works or construction commencing to determine the areas which require remedial works to ensure they are suitable to accommodate construction traffic associated with the English Onshore Scheme.  |
| Soil Management Plan<br>(SMP)  | To be developed by the Contractor post-consent based upon the Outline SWMP presented in <b>Appendix 12B</b> of this ES. This plan will set out the measures to ensure the protection and sustainable management and reuse of soil resources.  |
| Spill Response Plan  | To be developed by the Contractor post-consent. This will set out emergency response measures in the event of accidental spillage or leakage.   |
| Concrete Washout<br>Procedure  | To be developed by the Contractor post-consent. This will set out how the project will undertake concrete washout, including details of the emptying of concrete washout skips (if used) and the treatment of high pH washout water.  |
| Incident Response Plan<br>(IRP)  | To be developed by the Contractor (in agreement with NGET) post-consent. This will set out how the project will respond to incidents including pollution events, and how these are to be reported (both internally to the project and externally). The IRP will comply with Schedule 3 Annex 2 of National Grid's Contractor Health & Safety Performance Requirements (CHSPR).  |
| Drainage Strategy<br>(Also commonly referred to<br>as a Drainage<br>Management Plan (DMP)) | A detailed drainage strategy is to be developed by the Contractor. The Drainage<br>Strategy identifies all known risks to the water environment and identifies<br>appropriate measures to prevent pollution during construction; and to manage<br>runoff rates. The Drainage Strategy will define the installation of pre-construction<br>drainage measures to intercept run-off and ensure that discharge and runoff rates<br>are controlled in quality and volume, in turn causing no degradation to water<br>quality. This may include specific measures to be used in high-risk areas (for<br>example construction along or across steep gradients and water course |

| Plan / Procedure  | Description  |
|---|--|
|   | crossings). A phased approach may be taken to the development of the Drainage<br>Strategy to reflect the phasing of the construction programme. The Drainage<br>Strategy will include a Site Drainage Plan.  |
| Surface Water<br>Management Plan<br>(SWaMP)   | To be developed by the Contractor post-consent to define surface water<br>management controls to mitigate the potential for watercourse pollution and<br>environmental degradation; and to manage runoff rates. This may include specific<br>measures to be used in high-risk areas (for example construction along or across<br>steep gradients and water course crossings).  |
| Hydrological Risk<br>Assessment (HyRA)  | Prior to the commencement of works, the Contractor will prepare a HyRA where the cable route passes through SPZ2 designations. The HyRA will consider potential effects on the groundwater regime as well as potential pollution risk from the construction activities. This will expand upon the preliminary HyRA presented in <b>Appendix 10C.</b> The identified mitigation requirements will be incorporated into the detailed CEMP(s).  |
| Dewatering Scheme   | If dewatering is required, a detailed dewatering scheme will be developed by the Contractor prior to construction to manage the water arising from dewatering operations and treat the water prior to controlled discharge. It is anticipated that this will form part of the detailed CEMP(s).  |
| Construction Ecological<br>Management Plan<br>(CEcMP)   | Prior to the commencement of works, the Contractor will prepare a Construction Ecological Management Plan (CEcMP) to prescribe the required site-specific mitigation in relation to habitats and protected species to ensure compliance with relevant legislation and best practice. It is anticipated that this will be an appendix to the Detailed CEMP(s).  |
| Species Protection Plans<br>(SPP) (or similar)  | Prior to the commencement of works, the Contractor will prepare Species<br>Protection Plans (SPP) (or similar) for the sensitive/protected species that may<br>be encountered by the English Onshore Scheme (currently identified as Badger,<br>Bats, Otter, breeding birds and Water Vole), to ensure compliance with relevant<br>legislation and best practice. These will form part of the CEcMP.   |
| Invasive Non-Native<br>Species Method Statement<br>(INNSMS)   | Prior to the commencement of works, the Contractor will prepare an Invasive<br>Non-Native Species Method Statement This plan will set out the measures which<br>will be implemented to avoid the spread of invasive non-native species (INNS)<br>during construction and ensure legal compliance.  |
| Environment Agency<br>consent application and<br>accompanying Scheme of<br>Ecological Mitigation and<br>Reinstatement for works at<br>the River Hull SSSI | Prior to construction the Contractor will prepare a consent application and accompanying Scheme of Ecological Mitigation and Reinstatement setting out the mitigation methods to be employed and a methodology for the reinstatement of bank top habitats.   |
| Tree and Hedgerow<br>Protection Strategy  | Prior to the commencement of works, the Contractor will prepare a Tree and Hedgerow Protection Strategy. This will include a schedule of all trees and hedgerows to be removed, a schedule of all trees which require pruning coppicing or pollarding, a schedule of all trees and hedgerows to be retained including specification for temporary physical protection, including root protection areas and details of an auditable system of compliance. It will also include details of any hedgerows where a remove/store/replant methodology has been identified as appropriate through landowner consultation. |
| Ground Gas Risk<br>Assessment (GGRA)  | If the pre-commencement ground investigation identifies significant thicknesses of Made Ground (>3m) in the vicinity of manned buildings (i.e. the converter station), the Contractor will prepare a GGRA.   |
| Piling Risk Assessment  | Prior to the commencement of works, the Contractor will prepare a Piling Risk Assessment for locations where piled foundations are proposed (e.g., the converter station),   |
| Generic Quantitative Risk<br>Assessment (GQRA)<br>(Contamination)   | Prior to the commencement of works, the Contractor will prepare a Generic Quantitative Risk Assessment to identify potential risks to identified human health and groundwater receptors from soil, soil vapour and groundwater contamination. This is particularly pertinent at the proposed converter station where permanent above ground, potentially manned buildings will be present.   |
| Remediation Strategy<br>(Contamination)   | Should the GQRA identify any soil, soil vapour or groundwater contamination risks, prior to the commencement of any remediation works the Contractor will  |

| Plan / Procedure   | Description   |
|--|---|
|  | prepare a Remediation Strategy. This is to be agreed with the regulatory authorities and it is expected that the Strategy would be an appendix to the detailed CEMP(s).   |
| Materials Management<br>Plan (MMP)   | To be developed by the Contractor post-consent, where/if required. This will set<br>out how clean excavated materials are to be managed to ensure that the quality<br>of site-won materials is maintained so that they remain suitable for re-use and do<br>not become contaminated; or will detail the correct management of contaminated<br>soil materials to be removed from site. |
| Flood Management Plan<br>(FMP)   | To be developed by the Contractor post-consent, if required. The FMP will include details on the frequency of weather and stream flow observations, how forecasts, alert and actions will be disseminated, signage, roles and responsibilities, and emergency response procedures including detailed evacuation plan and procedures for making safe plant and equipment.              |
| Water Efficiency<br>Management Plan  | To be developed by the Contractor post-consent. The Plan will include measures to reduce water consumption by all water-using processes, activities and equipment on site. It will also include details of staff engagement and training for relevant staff as well as setting out monitoring and reporting requirements (as per CEMP) and how these will be implemented.             |
| Archaeological Mitigation<br>Strategy (also known as a<br>Written Scheme of<br>Investigation (WSI) for<br>archaeological mitigation) | To be developed by the Contractor post-consent to fully describe the additional mitigation measures to be implemented to protect buried archaeological features.  |
| Landscape and Ecology<br>Management Plan (LEMP)  | Prior to the commencement of works, the Contractor will prepare a Landscape<br>and Ecology Management Plan (LEMP) to ensure that habitats created/<br>enhanced for biodiversity net gain offsetting will meet the required habitat<br>conditions; and that long-term management requirements are clearly defined.   |
| Landscape Mitigation Plan  | To be developed by the Contractor post-consent based upon the Outline Landscape Mitigation Plan presented as Figure 8-5 of the ES. The plan describes the proposed landscape planting and habitat creation/enhancement at the converter station and is also used to inform BNG.   |
| Public Right of Way<br>(PRoW) Management Plan  | If required, a PRoW Management Plan will be developed by the Contractor post-<br>consent to set out appropriate measures to ensure that safe accessibility to<br>recreational routes and PRoW, is maintained throughout construction. These<br>measures may instead be directly reported in the detailed CEMP(s).   |

## **18.2 Project Location**

The English Onshore Scheme comprises the following principal elements, the locations of which are illustrated on **Figure 18-1**. Further detail regarding the description of the English Onshore Scheme including construction details is contained in **Chapter 3: Description of the English Onshore Scheme**.

As noted in 18.1.2, multiple contractors will be appointed to construct/install the different elements of the English Onshore Scheme due to the specialist electrical components required. As such, and to align to the varying risks and receptors likely to be encountered during the works for the elements, different Detailed CEMPs will be prepared as agreed between the Project and the relevant planning authority.

### 18.2.1.1 Landfall

The subsea cables will connect to onshore cables at a buried transition joint pit (TJP), which is located at Fraisthorpe, East Yorkshire. The TJP will be set back from the coastline, beyond the coastal erosion risk area to avoid future cable exposure and to reduce risk of exacerbating any existing erosion. The TJP is located approximately 150 m inland from the MHWS. The offshore cables will make landfall via horizontal directional drill (HDD) under the intertidal zone.

A temporary compound area (up to approximately 100 m x 100 m) will contain all necessary plant and equipment plus parking and welfare facilities required for the installation activities at the landfall location.

### 18.2.1.2 Underground DC Cable Route

The English Onshore Scheme comprises two underground DC cables (and fibre optic cables for performance monitoring) laid within a single trench (or where constraints dictate pulled through preinstalled ducts).

The term proposed route is used throughout this report and refers to the DC cables, trench (or installation area) and associated temporary working areas required for cable installation.

The English Onshore Scheme is split into four Route Sections as follows:

### 18.2.1.2.1 Route Section 1 – Landfall to Bainton

From the TJP the proposed route extends across Carnaby Moor in a westerly direction north of Fraisthorpe Wind Farm, before crossing the A165 and extending southwards across open agricultural land. The route crosses the Earl's Dyke and the Burton Agnes to Paull gas pipeline west of the A165 before continuing in a south-westerly direction.

The proposed route continues in this direction for approximately 6 km, passing the settlement of Gransmoor to the north and between the villages of Great Kelk (south of the route) and Little Kelk (north of the route). The proposed route crosses minor roads, PRoWs, smaller watercourses and unnamed drains until reaching Kelk Beck. After crossing Kelk Beck via HDD, the proposed route continues for approximately 4 km to the village of Wansford.

The proposed route runs approximately 750 m north of the village of Wansford and crosses the B1249, Driffield Canal and the River Hull between Whinhill Lock and Wansford Lock. South of this crossing the proposed route extends further westwards towards the village of Bainton crossing the Driffield to Hull railway line and the A164 whilst bypassing the villages of Skerne and Hutton Cranswick.

### 18.2.1.2.2 Route Section 2 – Bainton to Market Weighton

From Bainton, the proposed route extends south to Middleton-on-the-Wolds through the Yorkshire Wolds. Between Middleton-on-the-Wolds and Lund the proposed route continues south through areas of open agricultural land. The proposed route continues south to the crossing of the Wilberforce Way Long Distance Walking Route and Local Nature Reserve (LNR) (Etton-Gardham Disused Railway/Kiplingcotes Road Earthworks).

The proposed route then continues for approximately 6 km in a south-westerly direction towards the town of Market Weighton. There are crossings of the Yorkshire Wolds Way and two trunk roads, the A1079 and A1034, as the route passes Market Weighton to the south and extends into Route Section 3.

### 18.2.1.2.3 Route Section 3 – Market Weighton to River Ouse

Route Section 3 starts to the south of Market Weighton, and the proposed route continues southwesterly for approximately 15 km passing through agricultural land, between Holme upon Spalding Moor (north of the route) and the Tollingham industrial estate (south of the route) towards Howden. Crossings are also required of the Market Weighton Canal, River Foulness and the A614 before reaching Howden.

The proposed route extends north of Howden before extending immediately south across the Selby railway line (ensuring a right-angle crossing) to the west of the settlement. The alignment again continues to the southwest towards Asselby, extending through agricultural and plantation land and crossing the A63. The proposed route crosses Main Street to the west of Asselby village in a largely north-south direction before heading in an easterly direction to the proposed crossing point of the River Ouse and in to Route Section 4.

#### 18.2.1.2.4 Route Section 4 – River Ouse to Drax Substation

The crossing of the River Ouse is to the south of Redhouse Lane, with the proposed route extending to the southwest to cross Main Road (through Drax) to the north of Read School. The proposed route continues west, to the south of Wren Hall, and into the proposed converter station site immediately to the east of the Drax Power Station and existing Drax 400 kV Substation.

### 18.2.1.3 Associated Temporary Construction Areas

Temporary construction compounds are typically utilised for the storage of plant and machinery and stockpiling materials, as well as the provision of site management offices, welfare facilities for staff (kitchen facilities, storerooms, toilet facilities), parking, and plant and material storage.

Construction of these areas will require vegetation clearance and soil removal as required. It is likely that the working surface will be formed of crushed rolled stone on a geotextile membrane over subsoil (the membrane will prevent mixing of construction materials with the underlying soil resources). The stripped topsoil will be stored on site.

A summary of the proposed temporary construction compounds is provided below:

- Landfall specific compound (measuring approximately 1 ha (100 m x 100 m)) provided for HDD installation across the intertidal area. This area will also accommodate the Transition Joint Pit (TJP) to join marine and terrestrial cables together.
- Primary (main compound) major cable compounds at either end of the scheme and one central location. These are approximately 2.25 ha (22,500 m<sup>2</sup>). There are three primary compound locations on the proposed route:
  - A165 (Fraisthorpe);
  - A1034 (Market Weighton); and
  - A63 (Newsholme).
- Secondary (strategic location with good access). These are approximately 1.3 ha (13,000 m<sup>2</sup>). There are 10 secondary compound locations on the proposed route:
  - B1249 (Wandsford);
  - Driffield Road (Skerne) (1 of 2);
  - Driffield Road (Skerne) (2 of 2);
  - A164 (Hutton) (1 of 2);
  - A164 (Hutton) (2 of 2);
  - Beverley Road (Lund);
  - Skiff Lane (Tollingham);
  - A614 east (Bursea);
  - A614 west (Portington); and
  - Redhouse Lane (Drax).

- Tertiary (satellite compound accessed from the haul road). Sized at approximately 0.5 ha (5,000 m<sup>2</sup>) and generally located where there is flat ground and otherwise a large gap between compounds. There are four tertiary compound locations along the DC cable route:
  - Gransmoor Lane (Gransmoor Quarry);
  - Cliffe Lane (North Cliffe);
  - Unnamed road (east of Middleton on the Wolds); and
  - Unnamed road (Kiplingcotes, South Dalton).

### 18.2.1.4 Converter Station

The proposed converter station site is located to the immediate east of the existing Drax Power Station, North Yorkshire, within an agricultural field. The site is bounded by New Road to the west, and Wren Hall Lane to the south and east. The permanent converter station will be approximately 5 ha (within the security fence line).

### 18.2.1.5 Underground AC Cable Route

The underground AC cables will connect the converter station to the existing 400 kV Drax substation. Six underground AC cables (two sets of three cables) will be installed utilising open cut installation methods. The AC connection will be up to 500 m in length from the converter station site, across New Road and into the Drax Substation site.

