



New traditional roled lead flat roof with code 5 lead finish to extend under slate, existing roof covering to be removed, breather membrane inserted along with insulation, exposing existing joists. Re-use existing slate (or second hand slates to match if any are broken), new flashings, fascias, cast iron gutters

New Rooflight -Clement conservation rooflights ref Clement 0 aperture size 332x444

1 Roof
1 : 100

GENERALLY
 Refurbish roof and insulate - see A(20)-03
 repair/ replace any damaged slates & flashings
 new matching fascias if necessary and cast iron
 rw goods to match existing
 See Clement conservation rooflight drawings D-
 CRPM-01 to 04
 & Leadworx drawing 03 for Roof Vents

A	Conservation and roof notes added	CM	12/03/24
	first issue	Author	-
rev	description	by	date

St. Andrew, High St, Llandaff, CF5 2DX
 Matthew Skuse

GA Plan Roof

job no.	drawing no.	rev	status	scale @ A3
348	A(00)-03	A	Information	1 : 100