


MULTI CATERING TECHNOLOGIES - CHERRY TREE RESTAURANT.



Hi Nigel

Hope this helps. I have attached the design worksheet for the canopy and ductwork.

The ventilation ductwork will come out of the wall in two places then turn on to the roof and connected to a single 500 diameter duct the ductwork will run across the flat roof, and includes a filter box which is 1200 x 600. The filter box will house 2 x 600 x 600 pleated panel filters and 2 x 600 x 600 carbon bag filters with 300 deep pockets.

The fan is mounted on anti vibration feet on the roof after the filter box with a silencer is mounted just after the fan. The ductwork will rise up the gable end of the building terminating approx level with the apex of the building.

More information in the attached document

kindest regards

Nigel Marshall.



and

**Multi Catering Technologies**

43A Hurricane Way
 Norwich
 Norfolk
 NR6 6HE
 United Kingdom

VAT Number: GB 846829480
 T: 01603 369859
 E: nigel@mctonline.co.uk

Mr EMDAD HUSSAIN
 The Cherry Tree
 The Cherry Tree
 1 Old Norwich Road
 Yaxley
 Eye
 IP23 8BH
 United Kingdom

QUOTES

QUOTES Number: 4630
QUOTES Date: 23rd Feb '24
Valid For: 30 Days
Account: CHERRY01
Job Ref:: Ventilation canopy, Ductwork and Gas Services

Qty	Description	Rate	Total
1	<p>DESCRIPTION: Installation of a Commercial Extract Canopy / Hood, Extract Ductwork, Fan and Speed Controller.</p> <p>TESTING & COMMISSIONING: Included. INSTALLATION LABOUR: INSTALLATION MATERIALS:</p> <p>DATE: To be Confirmed.</p> <p>Canopy dimensions: 4630 long, 1200 wide, 450 deep (mm). Grease Filters: 495 x 395 x 45 (mm) Stainless steel Baffle.</p> <p>Fan & Controller: Twin prop. Silencer: on extract side of fan. Filtration: Fabric filters pre-filters and Bag filters included.</p> <p>INCLUDES: Electrical. EXCLUDED: Building work.</p>	9,454.00	9,454.00
1	<p>PROJECT DESCRIPTION OF WORK. Stainless steel wall cladding to underside of the canopy only</p>	1,226.00	1,226.00

Qty	Description	Rate	Total
1	DESCRIPTION OF WORK. Supply and installation of interlocking system for the gas and ventilation system for a commercial kitchen.	2,640.00	2,640.00
	GAS PARTS REQUIRED: Gas solenoid valve with automatic reset. Gas lever valve Gas Pipe fittings.		
	ELECTRICAL COMPONENTS REQUIRED: Emergency Panic button Mushroom type. Air pressure switch for monitoring air flow. Conduit and cable for the wiring of the interlocking system.		

Thank you for allowing Multi Catering Technologies to Tender for the above project.

1	MAINTENANCE CUSTOMER AGREED DISCOUNT	-820.00	-820.00
---	--------------------------------------	---------	---------

Total Net Amount: £12,500.00
VAT @ 20%: £2,500.00
QUOTES Total: £15,000.00