

#### **4 Bay Oak Fronted Catslide Frame, Gable End, 12x6m**

Oak front top plate, oak posts (200x200) & oak curved braces on front elevation  
Softwood sole & top plate, softwood posts, softwood curved braces, softwood infill stud work @ 600 centres & softwood tie beams to the rear & side elevations  
Softwood pre cut roof rafters @ 400 centres  
Oak dowels and bolts for frame assembly  
4x2 provided for the catslide rafters @ 400 centres **to be cut on site**  
Pre made stud walls for catslide rear  
Tanalised 7" featheredge cladding (tanalised trims included, 2x2 to front, 4x2 to rear)