

## Technical note

<b>Project</b>	66 Pollard Hill North	<b>Date</b>	01 January 2024
<b>Note</b>	Drainage Strategy	<b>Ref</b>	22-9600-D101D
<b>Author</b>	Arwyn Norris		

**This technical note is produced to accompany the Syntegra Drainage General Arrangement Drawing ref 22-9600-6005 and 22-9600-6006 and 22-9600-6010-6011 in support of discharge of the drainage condition under planning ref 21/03908/FUL. This Note is further updated in response to LLFA comments dated 09/01/2024**

The design has been based upon the submitted drainage strategy prepared by Sweco Uk Ltd (July 2021)

In order to simplify maintenance requirements and ownership of the suds systems, the proposed SuDS layouts have been amended. The drainage strategy for the scheme has been modified to take into account the current layout, proposed levels and site constraints.

Attenuation will be provided via a combination of cellular attenuation systems and permeable paving systems with flow control devices. In line with LLFA comments permeable paving systems have been added to all driveways.

The existing discharge rates as per the approved drainage strategy were calculated as follows:

Storm	Existing Runoff Rate l/s
1 in 1 year	1.5
1 in 30 year	4.8
1 in 100 year	7.3

Table 1 Greenfield runoff rates

In undertaking the detailed design, consultation was undertaken with Thames Water. I was agreed that a single point of connection was to be provided for a foul and surface water and that a discharge rate for surface water of approximately 2l/s was to be provided. This is controlled using a hydrobrake system prior to discharge.

A new connection to the surface water sewer within Beach Road was previously agreed and will be utilised. Therefore In accordance with Thames Water policy the connections and discharge rates are in line with the drainage and connection hierarchy. Consent for the connections has been provided.

An increase in discharge rates over the proposed strategy is required due to the increase in impermeable areas and change in levels, as such a small increase is required and has been agreed. Whilst the LLFA note that previous discharge rates were less, it is not possible to provide further reductions without reducing the orifice size (to which the LLFA was against) and providing significant additional storage which space is limited. Hydraulically due to topography the proposed strategy represents the most stable and efficient system. In addition Thames Water have no issue with the rates proposed which have been developed in consultation and have accepted the proposals.

Proposed impermeable areas are calculated as 0.149ha. Of note is that some of these areas relate to garden paths to which runoff would not be conveyed to the drainage system but the garden areas. The existing impermeable area of the site is indicated as 0.016ha.

Water butts are proposed to each property to further reduce runoff and provide water for irrigation.

The attenuation has been sized to accommodate the rainfall events up to and including the 1% AEP event inclusive of 40% climate change

Storm	Proposed Runoff Rate l/s	Existing Runoff Rate l/s
1 in 2 year	1.9	1.5 (1 in 1)
1 in 30 year	2.0	4.8
1 in 100 year	2.0	7.3
1 in 100 year +40% CC	2.0	n/a

Table 2 Proposed vs Existing runoff rates

1 in 2 year discharge rates are provided as FEH13 data does not allow for simulations at 1 in 1 year rates. The LLFA have stipulated use of FEH13 data which has been used.

See drawing 6010 for Drainage Standard Details to provide details on connectivity and attenuation systems.

### Management and Maintenance

All drainage will be required to be maintained by the contractor during construction, following which the post construction phase maintenance would apply as per manufacturer recommendations and as appended to this document.

The proposed drainage system for the site adopts a series of SuDS measures to control the rate of storm water discharge and the quality of the water in line with current practice. A site management company will be in place to maintain the drainage to ensure that SuDS elements operate effectively for their lifetime.

This document should be read in conjunction with the drainage system drawings. Responsibility of maintenance will lie with the client and an appropriate management company is to be appointed to oversee future maintenance.

### Overview of Maintenance

All drainage systems, whether piped systems or SuDS systems require regular maintenance. The maintenance of the SuDS system should be included alongside other regular maintenance tasks. The table below gives an overview of typical maintenance tasks and the frequency with which they need to be undertaken.

Activity	Indicative frequency	Typical tasks
Routine/regular maintenance	Monthly to annually (for normal care of SuDS)	Litter picking Inspection of inlets, outlets and control structures
Occasional maintenance	Annually up to 25 years (dependent on the design)	Silt control around components Vegetation management around components Suction sweeping of permeable paving Silt removal from catchpits, soakaways and cellular storage
Remedial maintenance	As required (tasks to repair problems due to damage or vandalism)	Inlet/outlet repair Erosion repairs Reinstatement of edgings Reinstatement following pollution Removal of silt build up

### Typical maintenance tasks and frequency for SuDS drainage

The required maintenance for each of the elements that make up the SuDS systems, is scheduled below. The following guidance is based on CIRIA C753 – The SuDS Manual.

#### Permeable Pavements

Permeable surfaces including permeable block paving, porous asphalt, gravel or free draining soils that allow rain to percolate through the surface into underlying drainage layers. They must be protected from silt, sand, compost, mulch, etc. Permeable block paving and porous asphalt can be cleaned by suction brushing. It is proposed that the access and parking areas will be constructed utilising permeable paving techniques to mimic the natural process of water percolating into the underlying strata.

Regular inspection and maintenance is important for the effective operation of the pervious pavement. Maintenance responsibility for the pavement and its surrounding area should be placed with Landowner via a management company.

Sediment\material removal should be undertaken in consultation with the environmental regulator to confirm appropriate protocols, as run-off is taken from potentially contaminated areas such as car parks/service yards.

Maintenance Schedule	Required Action	Frequency
----------------------	-----------------	-----------

Monitoring (to be undertaken more regularly within the first year of operation and adjusted as required)	Initial inspection.	Monthly for three months after installation
	Inspect for evidence of poor operation and/or weed growth. If required, take remedial action.	3-monthly, 48 hours after large storms in first six months
	Inspect silt accumulation rates and establish appropriate brushing frequencies. Silt can also be caused by adjacent landscaping areas which should be reprofiled to provide a flat area or berm adjacent to the paving.	Annually.
	Monitor inspection chambers.	Annually.
Regular maintenance\inspection	Brushing and vacuuming (standard cosmetic sweep over whole surface).	Once a year, after autumn leaf fall, or reduced frequency as required, based on site-specific observations of clogging or manufacturer's recommendations – pay particular attention to areas where water runs onto pervious surface from adjacent impermeable areas as this area is most likely to collect the most sediment
Occasional maintenance	Stabilise and mow contributing and adjacent areas.	As required
	Removal of weeds or management using glyphosates applied directly into the weeds by an applicator rather than spraying	As required – once per year on less frequently used pavements
Remedial actions	Remediate any landscaping which, through vegetation maintenance or soil slip, has been raised to within 50 mm of the level of the paving.	As required.
	Remedial work to any depressions, rutting and cracked or broken blocks considered	As required.

	detrimental to the structural performance or a hazard to users.	
	Rehabilitation of surface and upper sub-structure. This could include replacement of the jointing and bedding material. The upper geotextiles layer may also need replacing if clogged and Terram 1000 has a life span of 25 years.	Every 10 to 15 years or as required (if infiltration performance is reduced due to significant clogging)

## Geocellular Systems

Regular inspection and maintenance is required to ensure the effective long-term operation of below ground modular storage systems. Maintenance responsibility for systems should be placed with a responsible organization. Maintenance requirements for modular systems are described in the table below. Maintenance plans and schedules should be developed during the design phase. Specific maintenance needs of the system should be monitored, and maintenance schedules adjusted to suit requirements.

### Modular systems – operation and maintenance requirements

Regular maintenance	Inspect and identify any areas that are not operating correctly. If required, take remedial action.	Monthly for 3 months, then six monthly
	Debris removal from catchment surface (where may cause risks to performance)	Monthly
	Where rainfall infiltrates from above, check surface of filter for blockage by silt, algae or other matter. Remove and replace surface infiltration medium as necessary.	Monthly (and after large storms)
	Remove sediment from pre-treatment structures	Annually, or as required
Remedial actions	Repair/rehabilitation of inlets, outlet, overflows and vents	As required
Monitoring	Inspect/check all inlets, outlets, vents and overflows to ensure that they are in good condition and operating as designed	Annually and after large storms

## Pipes (Including Oversized) & Manholes

Pipes are intended to be the main conveyance across the development. They are intended to be dry except for during rainfall events. These have been designed to be self-cleansing where possible for smaller diameter pipes, and for larger diameters the risk is reduced due to the overall pipe size.

Access for maintenance is provided through access chambers, manholes, rodding plates and rodding eyes.

Regular inspection and maintenance is important to identify areas which may have been obstructed/clogged and may not be drainage correctly thus exposing the development to a greater level of flood risk. Maintenance responsibility for the pipes should be placed with Landowner.

Sediment\material removal should be undertaken in consultation with the environmental regulator to confirm appropriate protocols, as run-off is taken from potentially contaminated areas such as car parks/service yards.

Maintenance Schedule	Required Action	Frequency
Monitoring (to be undertaken more regularly within the first year of operation and adjusted as required)	Initial inspection should be provided as post construction CCTV survey.	N/A
	Inspect for evidence of poor operation via water level in chambers. If required take remedial action.	3-monthly, 48 hours after large storms.
Occasional maintenance	Check and remove large vegetation growth near pipe runs.	6 monthly
Remedial actions	Rod through poorly performing runs as initial remediation.	As required.
	If continued poor performance jet and CCTV survey poorly performing runs.	As required.
	Seek advice as to remediation techniques suitable for the type of performance issue and location.	As required If above does not improve performance.

## Flow Control Devices – Hydro Brake, Orifice Plates

Maintenance to be undertaken according to manufacturer's specification. As a general guide, this should include the following:

Maintenance Schedule	Required Action	Typical Frequency
Routine Maintenance	Inspection	Quarterly
	Litter / debris removal	Monthly or as required
Occasional Maintenance	Sediment removal	6 monthly
Remedial Maintenance	Repair (as a result of damage or vandalism)	As required


All drainage will be maintained as required. It is envisaged that minimal maintenance would be needed of the proposed system.

**WATER BUTT SAMPLE**  
**Product References:**  
**Charles Bentley 210L Garden Round Plastic Water Butt.**  
 -Includes: Water exit tap, lockable lid, 3 part stand and downpipe filler kit.  
 -Dimensions: Water Butt - H97 x W57 x D57cm, Stand - L40.5 x W40.5 x H30.5cm.  
 -Materials: Polypropylene.  
 -Capacity: 210 litres.  
 -Weight: 8.2kg.  
**LINK:** <https://www.charlesbentley.com/210l-garden-round-plastic-water-butt-set-including-tap-with-stand-and-filler-kit.html>



**FORMPAVE SYSTEM:**  
 80mm thick Aquaflo, Concrete blocks  
 50mm thick 2-6mm clean crushed stone  
 Inbitex Geotextile  
 100mm thick 5-20mm sub-base stone  
 400mm thick 10-63mm sub-base stone  
 SC Intergrid  
 SC Membrane  
**FORMATION LEVEL=47.60 TBC BASED UPON 35% VOID RATIO**

**Maintenance:**  
 Annual inspection and removal of any debris accumulated to conserve capacity




**EXISTING DRAINAGE.**  
 1. Where existing runs and chambers are to be reused, their condition and suitability is first to be assessed and levels checked and verified. Any discrepancies or required alterations are to be reported to the engineer.  
**BACKDROPS**  
 2. Backdrops to suit depth of chambers and spurs.

**DO NOT SCALE DRAWING - IF IN DOUBT, ASK**

**GENERAL**  
 1. Do not scale from drawing.  
 2. All dimensions are in metres, unless stated otherwise.  
 3. This drawing to be read & printed in colour.  
 4. This drawing to be read in conjunction with other contract drawings.

**CONSTRUCTION**  
 1. Works shall comply with the current Department of Transport Specification for Highway Works.  
 2. Filling of voids formed by site clearance operations shall be measured under Series 800 of the Specification.  
 3. Contractor is to ensure that all voids are to be filled with granular sub base material Type 1.  
 4. All hard material broken out under the Contract is to be disposed of to contractor's tip.  
**CDM (RISKS & HAZARDS)**  
 1. Prior to commencement of construction the contractor is to liaise with all relevant statutory undertakers and protect / divert apparatus and to protect the workforce during the works. Any damage caused to the apparatus to be the responsibility of the contractor.  
 2. Contractor to undertake their own statutory plant checks on site prior to the commencement of excavation exercises.  
 3. The contractor is to make sure that any excavation should be adequately covered at night to protect both public and wildlife from becoming trapped.  
 4. Appropriate health and safety measures should be adhered to while working in close proximity to the existing overhead power lines.

**DISCLAIMERS**  
 1. The information contained in this drawing is based on a combination of OS and survey data provided by others and we shall not be liable for any inaccuracies or deficiencies.



P2	AN	AK	01.02.24	Revised to comments
P1	AN	AK	26.11.23	First Issue
Rev	Drawn	App'd	Date	Revision Description

**PRELIMINARY**

Syntegra House, 63 Milford Road, Reading, RG1 8LG  
 Tel: 0118 4028520  
 mail@syntegragroup.com www.syntegragroup.com

Client: \_\_\_\_\_

Project: **66 Pollard Hill North**

Title: **PROPOSED FOUL & SW DRAINAGE GA**  
 1 of 2

Scale: 1:100 @ A1 Drawn By: AN  
 Date: NOV 2023 Checked By: AK  
 Orig. No: **22-9600-6005** Rev: **P2**

**NOTES:**  
 1. This drawing should be read in conjunction with the standard details.  
 2. All building drainage works shall be carried out in accordance with the current British/European standards BS EN 752, the current building regulations and the local authority building control specifications and requirements.  
 3. For external finished ground levels refer to architects external works drawing.  
 4. External covers installed in areas of paving to be square with recessed cover and frames suitable for receiving the appropriate paved surface. cover positions to be co-ordinated with the architects external layout drawings to minimise paving cutting.  
 5. For chambers located beneath decking. Cover levels of chambers to be set at ground level.  
 6. Cover in vehicular trafficked areas to be class d400 covers in non-vehicular trafficked areas to be class b125.  
 7. For all setting out, dimensions and current site layout refer to architects drawing. Do not scale from this drawing.  
 8. Exact location of rainwater downpipes and all internal drainage points to be confirmed by architect. rainwater pipe outlets to be rodable.  
 9. The contractor shall allow for the protection, temporary and permanent support, and temporary and permanent diversion works, as necessary to all existing services.  
 10. The contractor shall allow for keeping trenches and excavations as dry as practicable by pumping from temporary sumps and de-watering as appropriate. the point and method of discharge to be agreed with the drainage authority and environment agency.  
 11. Disused foul and surface water drains up to 225mm diameter, together with any bed or haunch or surround within 1m of formation level shall be removed, drains over 1m below formation shall be left unless they conflict with proposed foundations of structural footprints. the ends of existing drains and sewers no longer required because of alterations to the drainage layout shall be sealed with gen3/c20 concrete. all trenches formed to removed abandoned drains shall be backfilled with selected site won material where available.  
 12. Contractor to verify the route, level and connectivity of the receiving foul and surface water sewers downstream

of the site and obtain all necessary approvals from ww prior to commencement.  
 13. All abandoned sewers to be surveyed by CCTV to identify and confirm presence of any retained/live lateral connection.  
 14. Room use and required drainage fixtures to be confirmed by architect.  
 15. Root barrier where with 5.0m of mature tree canopy.  
 16. Inspection chambers to have min class b125 single seal cover and frame.  
 17. Refer to drainage details.  
 18. Invert levels of all outfall points to be confirmed prior to commencing drainage works. Position size and depth of all existing drains and services shall be established prior to commencement on site and any discrepancies reported to engineer.  
 19. All drainage works to be constructed from the outfall towards the head of run to ensure the outfall can be achieved.  
 20. All foul private pipes to be 100mm diameter unless otherwise stated. Where connected to a minimum of 1 WC pipes to be laid at a minimum gradient of 1:80, otherwise min 1:40.  
 21. All surface private drainage pipes to be 100mm diameter with a min gradient of 1:100 unless otherwise stated.  
 22. Type Z pipe bedding to be applied where cover is less than 1.2m. For pipe with a cover greater than 1.2m a type S bedding is to be applied. Additionally pipes in the vicinity of buildings.  
 23. All SVP stacks to terminate with an air admittance valve at the head of a run where the SVP should terminate above roof level.  
 24. All drainage arrangements are to be carried out to the satisfaction of the Local Authority building Inspector onsite.  
 25. All pipes below 300mm diameter to be vitrified clay or similar approved. All pipes above 300mm diameter to be concrete or similar.  
 26. Vitrified clay pipes and fittings shall comply with the relevant provisions of BS EN 295-1.  
 27. Concrete pipes and fittings shall comply with the relevant provisions of BS EN 1916 and BS 5911-1.  
 28. All private drainage works to be carried out in

accordance with Building Regulations Part H.  
 29. Private foul water drainage route under slab are shown indicatively; bedding, pipe material and penetration of property wall details by others.  
 30. Locations and levels of existing manholes and outfalls to be verified onsite prior to commencement of works - very important.  
 31. Gradients are indicated for hydraulic not setting-out purposes.  
 32. Minimum backdrop height shall be 1m.  
 33. All levels shown are levels above Ordnance Datum.  
 34. Prior to infilling of ditches or abandonment of any existing drainage courses or piped sewers the contractor shall put in place measures to maintain or divert existing drainage routes and sewers pending completion of proposed drainage systems.  
 35. The presence of services on site should be verified prior to any construction work or intrusive investigations.

**TYPE(S) OF PAVING**  
 Permeable concrete block paving  
**REFERENCE**  
 Aquaflo  
**SIZE**  
 100 x 200 x 80 Thick  
**COLORS**  
 Red brick, Golden brindle, Natural, Charcoal, Burnt red.  
**SETTING OUT**  
 Aquaflo and Aquasetts.  
 800 herringbone with double stretcher course around all perimeters.  
**KERBS**  
 Standard kerb system or Forest Edging: both to be approved with concrete.  
**LAYING COURSE**  
 50mm depth of 5mm. single size clean crushed stone to BS882.  
**GEOTEXTILE**  
 Inbitex Geotextile as noted  
**SUB-BASE SPECIFICATION**  
 The granular sub-base material shall comprise crushed rock or concrete possessing well defined edges. It must be sound, clean, non friable and free from clay or other

deteriorous matter.  
 The material must be non plastic when tested in accordance with BS1377 Test No 4. \*The crushed stone used for the laying course and sub-base must have a minimum 10% fines value of 150KN when tested in accordance with BS812 Part 111.  
 The selected test samples not to be over dried and should be soaked in water at room temperature for 48-hours before the test. The 100mm deep upper layer of sub-base material should be graded 20mm-5mm to BS862.  
 The 63-10mm material should be graded as follows:-

BS Sieve size	%passing
100mm	100
90-100	90-100
37.5mm	60-80
20mm	15-30
10mm	0-5

**DEPTH OF SUB-BASE**  
 It is recommended that a minimum sub-base depth of 350mm should be used. The depth of sub-base may be varied at the discretion of the engineer.  
**Intergrid(S)** - SC Intergrid  
**SURFACE FINISH**  
 The blocks should be vibrated with a vibrating plate Type DVP75/22" or similar. Following the first pass with a vibrating plate a light dressing of 3mm single size clean stone should be applied to the surface and brushed in, approximately 2kg per m<sup>2</sup>. (available from Formpave in 40 kg bags). Blocks should again be vibrated and any debris brushed off.



**WATER BUTT SAMPLE**  
**Product References:**  
**Charles Bentley 210L Garden Round Plastic Water Butt**  
 -Includes: Water exit tap, lockable lid, 3 part stand and downpipe filler kit.  
 -Dimensions: Water Butt - H97 x W57 x D57cm, Stand - L40.5 x W40.5 x H30.5cm.  
 -Materials: Polypropylene.  
 -Capacity: 210 litres.  
 -Weight: 8.2kg.  
**LINK:** <https://www.charlesbentley.com/210l-garden-round-plastic-water-butt-set-including-tap-with-stand-and-filler-kit.html>



**Maintenance:**  
 Annual inspection and removal of any debris accumulated to conserve capacity

**EXISTING DRAINAGE**  
 1. Where existing runs and chambers are to be reused, their condition and suitability is first to be assessed and levels checked and verified. Any discrepancies or required alterations are to be reported to the engineer.  
**BACKDROPS**  
 2. Backdrops to suit depth of chambers and spurs.


**DO NOT SCALE DRAWING - IF IN DOUBT, ASK**

**GENERAL**  
 1. Do not scale from drawing.  
 2. All dimensions are in metres, unless stated otherwise.  
 3. This drawing to be read & printed in colour.  
 4. This drawing to be read in conjunction with other contract drawings.

**CONSTRUCTION**  
 1. Works shall comply with the current Department of Transport Specification for Highway Works.  
 2. Filling of voids formed by site clearance operations shall be measured under Series 800 of the Specification.  
 3. Contractor to ensure that all voids are to be filled with granular sub base material Type 1.  
 4. All hard material broken out under the Contract is to be disposed of to contractor's tip.

**CDM (RISKS & HAZARDS)**  
 1. Prior to commencement of construction the contractor is to liaise with all relevant statutory undertakers and protect / divert apparatus and to protect the workforce during the works. Any damage caused to the apparatus to be the responsibility of the contractor.  
 2. Contractor to undertake their own statutory plant checks on site prior to the commencement of excavation exercises.  
 3. The contractor is to make sure that any excavation should be adequately covered at night to protect both public and wildlife from becoming trapped.  
 4. Appropriate health and safety measures should be adhered to while working in close proximity to the existing overhead power lines.

**DISCLAIMERS**  
 1. The information contained in this drawing is based on a combination of OS and survey data provided by others and we shall not be liable for any inaccuracies or deficiencies.



Rev	Drawn	App'd	Date	Revision Description
P2	AN	AK	01.02.24	Revised to comments
P1	AN	AK	26.11.23	First Issue

Issue PRELIMINARY



Syntegra House, 63 Milford Road, Reading, RG1 8LG  
 Tel: 0118 4028520  
 mail@syntegragroup.com www.syntegragroup.com


Client

Project 66 Pollards Hill North

Title PROPOSED FOUL & SW DRAINAGE GA 2 of 2

Scale: 1:100 @ A1 Drawn By: AN  
 Date: NOV 2023 Checked By: AK

Orig. No. 22-9600-6006 Rev. P2



**NOTES:**  
 1. This drawing should be read in conjunction with the standard details.  
 2. All building drainage works shall be carried out in accordance with the current British/European standards BS EN 752, the current building regulations and the local authority building control specifications and requirements.  
 3. For external finished ground levels refer to architects external works drawing.  
 4. External covers installed in areas of paving to be square with recessed cover and frames suitable for receiving the appropriate paved surface cover positions to be co-ordinated with the architects external layout drawings to minimise paving cutting.  
 5. For chambers located beneath decking. Cover levels of chambers to be set at ground level.  
 6. Cover in vehicular trafficked areas to be class 400, covers in non-vehicular trafficked areas to be class b125.  
 7. For all setting out, dimensions and current site layout refer to architects drawing. Do not scale from this drawing.  
 8. Exact location of rainwater downpipes and all internal drainage points to be confirmed by architect. rainwater pipe outlets to be roddable.  
 9. The contractor shall allow for the protection, temporary and permanent support, and temporary and permanent diversion works, as necessary to all existing services.  
 10. The contractor shall allow for keeping trenches and excavations as dry as practicable by pumping from temporary sumps and de-watering as appropriate. the point and method of discharge to be agreed with the drainage authority and environment agency.  
 11. Disused foul and surface water drains up to 225mm diameter, together with any bed or haunch or surround within 1m of formation level shall be removed, drains over 1m below formation shall be left unless they conflict with proposed foundations of structural footprints. the ends of existing drains and sewers no longer required because of alterations to the drainage layout shall be sealed with gen3/c20 concrete. all trenches formed to removed abandoned drains shall be backfilled with selected site won material where available.  
 12. Contractor to verify the route, level and connectivity of the receiving foul and surface water sewers downstream




of the site and obtain all necessary approvals from ww prior to commencement.  
 13. All abandoned sewers to be surveyed by cctv to identify and confirm presence of any retained/lateral connection.  
 14. Room use and required drainage fixtures to be confirmed by architect.  
 15. Root barrier where with 5.0m of mature tree canopy.  
 16. Inspection chambers to have min class b125 single seal cover and frame.  
 17. Refer to drainage details.  
 18. Invert levels of all outfall points to be confirmed prior to commencing drainage works. Position size and depth of all existing drains and services shall be established prior to commencement on site and any discrepancies reported to engineer.  
 19. All drainage works to be constructed from the outfall towards the head of run to ensure the outfall can be achieved.  
 20. All foul private pipes to be 100mm diameter unless otherwise stated. Where connected to a minimum of 1 WC pipes to be laid at a minimum gradient of 1:80, otherwise min 1:40.  
 21. All surface private drainage pipes to be 100mm diameter with a min gradient of 1:100 unless otherwise stated.  
 22. Type Z pipe bedding to be applied where cover is less than 1.2m. For pipe with a cover greater than 1.2m a type S bedding is to be applied. Additionally pipes in the vicinity of buildings.  
 23. All SVP stacks to terminate with an air admittance valve at the head of a run where the SVP should terminate above roof level.  
 24. All drainage arrangements are to be carried out to the satisfaction of the Local Authority building Inspector onsite.  
 25. All pipes below 300mm diameter to be vitrified clay or similar approved. All pipes above 300mm diameter to be concrete or similar.  
 26. Vitrified clay pipes and fittings shall comply with the relevant provisions of BS EN 295-1.  
 27. Concrete pipes and fittings shall comply with the relevant provisions of BS EN 1916 and BS 5911-1.  
 28. All private drainage works to be carried out in

accordance with Building Regulations Part H.  
 29. Private foul water drainage route under slab are shown inductively; bedding, pipe material and penetration of property wall details by others.  
 30. Locations and levels of existing manholes and outfalls to be verified onsite prior to commencement of works - very important.  
 31. Gradients are indicated for hydraulic root setting-out purposes.  
 32. Minimum backdrop height shall be 1m.  
 33. All levels shown are levels above Ordnance Datum.  
 34. Prior to infilling of ditches or abandonment of any existing drainage courses or piped sewers the contractor shall put in place measures to maintain or divert existing drainage routes and sewers pending completion of proposed drainage systems.  
 35. The presence of services on site should be verified prior to any construction work or intrusive investigations.

**TYPE(S) OF PAVING**  
 Permeable concrete block paving  
**REFERENCE**  
 Aquaflo  
**SIZE**  
 100 x 200 x 80 Thick  
**COLORS**  
 Red brindle, Golden brindle, Natural, Charcoal, Burnt red.  
**SETTING OUT**  
 Aquaflo and Aquasette:  
 The blocks should be vibrated with a vibrating plate Type DVP75/22" or similar. Following the first pass with a vibrating plate a light dressing of 3mm single size clean stone should be applied to the surface and brushed in, approximately 2kg per m<sup>2</sup>. (available from Formpave in 40 kg bags). Blocks should again be vibrated and any debris brushed off.



**KERBS**  
 Standard kerb system or Forest Edging: both to be haunched with concrete.  
**LAYING COURSE:**  
 50mm depth of 5mm. single size clean crushed stone to BS82.  
**GEOTEXTILE**  
 Inbitex Geotextile as noted  
**SUB-BASE SPECIFICATION**  
 The granular sub-base material shall comprise crushed rock or concrete possessing well defined edges. It must be sound, clean, non friable and free from clay or other deleterious matter.

The material must be non plastic when tested in accordance with BS1377 Test No 4. The crushed stone used for the laying course and sub-base must have a minimum 10% fines value of 150kN when tested in accordance with BS812 Part 111.  
 The selected test samples not be over dried and should be soaked in water at room temperature for 48-hours before the test. The 100mm deep upper layer of sub-base material should be graded 20mm-5mm to BS82.  
 The 63-10mm material should be graded as follows:-  
 BS Sieve size %passing  
 100mm 100  
 63mm 90-100  
 37.5mm 60-80  
 20mm 15-30  
 10mm 0-5  
**DEPTH OF SUB-BASE**  
 It is recommended that a minimum sub-base depth of 350mm should be used. The depth of sub-base may be varied at the discretion of the engineer.  
**Intergrid(S) - SC Intergrid**  
**SURFACE FINISH**  
 The blocks should be vibrated with a vibrating plate Type DVP75/22" or similar. Following the first pass with a vibrating plate a light dressing of 3mm single size clean stone should be applied to the surface and brushed in, approximately 2kg per m<sup>2</sup>. (available from Formpave in 40 kg bags). Blocks should again be vibrated and any debris brushed off.




TUMBLING BAY JUNCTION (ACTUAL DETAILS WILL BE DEPENDENT ON THE TYPE OF PIPE USED)

IN SITU CONCRETE TO BE GEN3 (DESIGNED TO BRE SPECIAL DIGEST 1 CONCRETE IN AGGRESSIVE GROUND)



TYPICAL BACKDROP DETAIL



TYPICAL SECTION THROUGH CELLULAR ATTENUATION (END CONNECTION)

DO NOT SCALE DRAWING - IF IN DOUBT, ASK

- GENERAL**
- Do not scale from drawing.
  - All dimensions are in metres, unless stated otherwise.
  - This drawing to be read & printed in colour.
  - This drawing to be read in conjunction with other contract drawings.
- CONSTRUCTION**
- Works shall comply with the current Department of Transport Specification for Highway Works.
  - Filling of voids formed by site clearance operations shall be measured under Series 600 of the Specification.
  - Contractor is to ensure that all voids are to be filled with granular sub base material Type 1.
  - All hard material broken out under the Contract is to be disposed of to contractor's tip.
- CDM (RISKS & HAZARDS)**
- Prior to commencement of construction the contractor is to liaise with all relevant statutory undertakers and protect / divert apparatus and to protect the workforce during the works. Any damage caused to the apparatus to be the responsibility of the contractor.
  - Contractor to undertake their own statutory plant checks on site prior to the commencement of excavation exercise.
  - The contractor is to make sure that any excavation should be adequately covered at night to protect both public and wildlife from becoming trapped.
  - Appropriate health and safety measures should be adhered to while working in close proximity to the existing overhead power lines.
- DISCLAIMERS**
- The information contained in this drawing is based on a combination of OS and survey data provided by others and we shall not be liable for any inaccuracies or deficiencies.

P1	AN	AN	01/02/24	First Issue
Rev	Drawn	App'd	Date	Revision Description

Issue PRELIMINARY



Client

Project  
Wamil Court

Title  
Drainage Standard Details 2 of 2

Scale: 1:125 @ A1	Drawn By: A.Norris
Date: Jan 24	Checked By: A.Norris

Drw. No. 22-9600-6011	Rev. P1
--------------------------	------------


DO NOT SCALE DRAWING - IF IN DOUBT, ASK

- GENERAL**
- Do not scale from drawing.
  - All dimensions are in metres, unless stated otherwise.
  - This drawing to be read & printed in colour.
  - This drawing to be read in conjunction with other contract drawings.


- CONSTRUCTION**
- Works shall comply with the current Department of Transport Specification for Highway Works.
  - Filling of voids formed by site clearance operations shall be measured under Series 600 of the Specification.
  - Contractor is to ensure that all voids are to be filled with granular sub base material Type 1.
  - All hard material broken out under the Contract is to be disposed of to contractor's tip.
- CDM (RISKS & HAZARDS)**
- Prior to commencement of construction the contractor is to liaise with all relevant statutory undertakers and protect / divert apparatus and to protect the workforce during the works. Any damage caused to the apparatus to be the responsibility of the contractor.
  - Contractor to undertake their own statutory plant checks on site prior to the commencement of excavation exercise.
  - The contractor is to make sure that any excavation should be adequately covered at night to protect both public and wildlife from becoming trapped.
  - Appropriate health and safety measures should be adhered to while working in close proximity to the existing overhead power lines.

**DISCLAIMERS**


- The information contained in this drawing is based on a combination of OS and survey data provided by others and we shall not be liable for any inaccuracies or deficiencies.





TYPICAL SECTION THROUGH FORMPAVE AQUAFLOW ATTENUATION SYSTEM




TYPICAL POROUS PIPE OUTLET DETAIL



TYPICAL PERFORATED PIPE BELOW PAVING DETAIL




TYPICAL DETAILS WHERE DRAINAGE TRENCH IS DEEPER THAN FOUNDATIONS



(SCALE 1:20)

TYPICAL SECTION THROUGH ATTENUATION SYSTEM




CLASS S - 360° GRANULAR SURROUND PIPE BEDDING DETAIL

(SCALE 1:20)


CLASS Z - CONCRETE BED AND SURROUND PIPE BEDDING DETAIL

(COVER < 900mm IN VEHICULAR LOADING AND OPEN FIELD. COVER < 600mm ELSEWHERE EXCEPT UNDER BUILDINGS.)

(SCALE 1:20)



FULL HEIGHT RESTRAINT DETAIL




SADDLE CONNECTION TO EXISTING SEWER

(SCALE 1:20)

INSPECTION CHAMBER (PPIC) BASE DETAILS

(SCALE 1:20)



PIPE CROSSINGS DETAIL

(SCALE 1:20)

P1 AN AN 01/02/24 First Issue

Rev Drawn App'd Date Revision Description

Issue PRELIMINARY



Client

Project

66 Pollard Hill

Title

Drainage Standard Details

Scale: 1:125 @ A1

Drawn By: A.Norris

Date: Jan 24

Checked By: A.Norris

Dwg. No.

22-9600-6010

Rev.

P1