DO NOT SCALE

N

KEY	
	4.5x43m VISIBILITY SPLAY
	43m FORWARD VISIBILITY
	SITE BOUNDARY

NOTES

1. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL RELATED RICHARD JACKSON LTD, ARCHITECTS & SUB-CONTRACTORS DRAWINGS. IN THE CASE OF DISCREPANCIES BETWEEN DRAWINGS REFER TO RJHLC FOR CLARIFICATION.

2. TOPOGRAPHICAL SURVEY UNDERTAKEN BY SURVEY SOLUTIONS, DRAWING NUMBER 2675GSE-01, SURVEY DATE 27.07.20.

3. THIS DRAWING IS BASED THE ARCHITECTS LAYOUT, PRODUCED BY FRANZ SHAW ASSOCIATES LTD.

4. THE CONTRACTOR SHALL, BEFORE COMMENCING THE WORKS, VERIFY ALL SITE AND SETTING OUT DIMENSIONS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE TRUE AND PROPER SETTING OUT OF THE WORKS AND FOR THE CORRECTNESS OF THE POSITION, LEVELS, DIMENSIONS, AND ALIGNMENT OF ALL PARTS OF THE WORKS.

5. ALL ADOPTABLE HIGHWAY WORKS TO BE IN ACCORDANCE WITH SUFFOLK COUNTY COUNCIL REQUIREMENTS AND SPECIFICATIONS.

6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING AND PROTECTING ALL EXISTING SERVICES AFFECTED BY THE WORKS.

7. ALL ROAD MARKINGS TO BE IN ACCORDANCE WITH THE TRAFFIC SIGNS REGULATIONS AND GENERAL DIRECTIONS 2016.

8. ALL ADOPTABLE FOUL AND SURFACE WATER DRAINAGE SHALL BE IN ACCORDANCE WITH SEWERS FOR ADOPTION 6TH EDITION AND THE INTERIM TERMS APPENDIX NO. 1 - MAY 2011, TOGETHER WITH THE REQUIREMENTS AND FULL SATISFACTION OF ANGLIAN WATER.

9. ALL PIPEWORK CONNECTING TO THE ADOPTABLE MANHOLES OR SEWERS TO BE 100mm MINIMUM DIAMETER VITRIFIED CLAY AND LAID TO CONNECT WITH LEVEL SOFFITS.

REV	DATE	DESCRIPTION	DRAWN	CHKD
H	06/03/24	EXTENSION OF ACCESS ROAD TO PLOT 1600 SHOWN	S.L.S	J.J.T
G	03/08/23	REVISION CLOUDS ADDED TO SHOW AMENDMENTS TO LAYOUT	N.B.	M.G.
F	06/09/22	EMERGENCY ACCESS PLANNING APPLICATION	A.A.	N.B.
E	27/07/22	REV CLOUDS ADDED TO SHOW CHANGES IN LAYOUT	A.A.	M.G.
D	21/07/22	GATEWAY BOULEVARD BELLMOUTH REMOVED AND EMERGENCY ACCESS OF THE A1120 SHOWN	A.A.	N.B.
C	08/01/21	RBT EXIT & MILL LANE SPEED LIMIT	D.D.P.	M.G.
B	24/12/20	GATEWAY ROAD AMENDED	N.B.	M.G.
A	01/12/20	ROADS AMENDED TO LATEST LAYOUT	N.B.	M.G.

REVISIONS

This drawing is to be read in conjunction with all other Engineer's drawings and all other project information. Any discrepancy between the Engineer's drawings and other project information is to be reported to the Engineer immediately.

Project
GATEWAY 14
STOWMARKET
SUFFOLK

Title
HIGHWAY GENERAL ARRANGEMENT

Client
GATEWAY 14 LTD

Scale	Drawn	Date
1:1000 @ A0	A.T.	FEB 2017
Job Manager	Checked	Approved
M.G.	M.G.	M.G.

RichardJackson Engineering Consultants
B47 The Crescent, Colchester, Essex CO4 9YQ — Tel: 01206 229800
Unit 4040, 6th Floor, Aldgate Tower, 2 Leman Street, London E1 8FA — Tel: 020 7448 9918
5 Quern House, Mill Court, Great Shelford, Cambs CB22 5LD — Tel: 01223 314794
4 The Old Church, St. Matthews Road, Norwich, Norfolk NR1 1SP — Tel: 01603 230240
The Wheelhouse, Bonds Mill, Stonehouse, Gloucestershire GL10 3RF — Tel: 01172 029070
Email Address: mail@rj.uk.com — Website: http://www.rj.uk.com

Drawing No.	Revision
60417-P-SK05	H

Drawing Status
[X] INFORMATION [ ] APPROVAL [ ] COSTING
[ ] TENDER [ ] CONSTRUCTION [ ] AS CONSTRUCTED

REPRODUCED FROM ORDNANCE SURVEY MAP WITH THE PERMISSION OF THE CONTROLLER OF HER MAJESTY'S STATIONERY OFFICE. © CROWN COPYRIGHT RICHARD JACKSON LTD - ACC No. 100002572.

A0

© Richard Jackson Ltd