

SCHEDULE OF WORK. REF. DEAN.ST.2024

Erect scaffolding allowing for safe working access to roof.

Provide skip to dispose of rubbish and discarded roofing materials.

Strip existing ridge tiles, slate, battens and roofing felt and discard.

Clean down and denail rafters.

Lay eave trays along eaves of roof.

Lay new felt and fix to rafters.

Batten using 2x1 set out at correct gauge for slates.

Lay new fibre cement slates of same size and colour as existing.

Install new ridge tiles in same material and colour as existing ridge tiles.

Lead work in valleys and around chimneys including front apron, soakers, back gutter and flashing all carried out in accordance with the lead sheet association guidelines.

Clear site and dispose of any rubbish.