



Shenzhen Absen Optoelectronic Co., Ltd.

AW2.8- Specifications

Version: V20220704

Parameter		Value
Physical Parameter	LED Type	SMD 3in1 1515
	Pixel Pitch (mm)	2.84
	Panel Dimensions (WxHxD)/(mm)	500x750x83
	Pixel Per Panel	176x264
	Panel Weight (kg)	9.6
	Panel Material	Die Casting Aluminum
	Module Dimensions (WxH)/(mm)	250x250
Optoelectronic Parameter	Brightness (nit)	5000
	Refresh Rate (Hz)	7620
	Gray scale (Bit)	15
	Contrast Ratio	3200:1
	Color Temperature (K)	7500
	Viewing Angle (H/V) (°)	160/160
	Driving Type	1/11
	AC Operating Voltage (V)	100~240
	Power Consumption (Max./Avg.)(W/m ²)	660/220
Application Parameter	Storage Temperature (°C)	-40~+60
	Operating Temperature (°C)	-20~+50
	Storage Humidity (RH)	10%~85%
	Operating Humidity (RH)	10%~90%
	IP Rating (Front/Rear)	IP65/IP54
	Module Maintenance	Front
	PSU & Others Maintenance	Front
	Panel Installation Type	Fixed
	Max Rigging QTY.	/
	Certificate	CE

Remark: Power consumption tolerance: $\pm 15\%$, according to the actual situation.

SHENZHEN ABSEN OPTOELECTRONIC CO.,LTD 2001-2022 ALL RIGHTS RESERVED