

# Rubber & Cork Mounting Strips



## Flexi



# Rubber and Cork Mounting Strips

Anti-Vibration Mounting Strips are a low cost option for mounting air conditioning units, air source heat pumps and other equipment providing vibration reduction and sound dampening. Available in recycled rubber and cork-rubber in various sizes.

### Features

- Up to 30 dB(A) reduction in sound
- UV stable

### Related Products

**Mounting Blocks**

### The Package

- 1 Rubber Strip or Cork Strip •

Part Code	Description	Length	Width	Thickness
AVMS-1	Anti-Vibration Mounting Strip – RUBBER	500mm	50mm	15mm
AVMS-2	Anti-Vibration Mounting Strip – RUBBER	1000mm	75mm	15mm
AVMS-3	Anti-Vibration Mounting Strip – RUBBER	1200mm	75mm	15mm
AVMS-4	Anti-Vibration Mounting Strip – RUBBER	1000mm	100mm	15mm
AVMS-CR-3	Anti-Vibration Mounting Strip – CORK	1200mm	75mm	12.5mm
AVMS-CR-4	Anti-Vibration Mounting Strip – CORK	1200mm	100mm	12.5mm

Cork – Rubber Strips	
Rubber	Natural Granulated Cork – 1.0 to 3.0mm Chloroprene Rubber
Density	600 kg/m <sup>3</sup>
Tensile Strength	2.2mpa
Compressibility	25-40%
Recovery	80%
Hardness	50 SHORE A
Working Temperature	- 20°C to +135°C

Rubber Strips	
Rubber	Recycled Rubber
Density	900 kg/m <sup>3</sup>
Tensile Strength	2.1mpa
Elongation at Break	125%
Hardness	60 SHORE A

The Pump House sales team are available to answer your questions or queries on this product. Our experts are waiting for your call **+44 (0)115 900 5858** or if you prefer send an email to **sales@pumph.co.uk** or visit **www.pumph.co.uk**

