

Tree Survey Report

Client: Mr & Mrs Webb
 Site: Rocksveld, Culverden Park Road



Condition	No. trees
Fair	1
Good	9
Total	
	10

Ref.	Species	Description	Measurements	Survey Notes	Condition	Recommendations
G001	Horse chestnut (<i>Aesculus hippocastanum</i>) Oak x3 (<i>Quercus sp.</i>) Norway maple (<i>Acer platanoides</i>)	A group of trees on a steep bank with the road on the topside and houses below.	Height (m): 18 DBH (cm): 80 Trees: 5 Life Stage: Mature Life Exp.: 50+ Years	The Oaks have a moderate amount of minor deadwood. The Horse Chestnut tree has two stems from the base with a weak union between them and an old decayed pruning wound at the top of the larger stem. The Laurel growing around them limits inspection.	Good	Cleanout all deadwood. Reduce the overall canopy of the Horse Chestnut tree by 3-4 metres, canopy lift all trees overhanging the road to 5.2 metres.
T002	Oak (<i>Quercus sp.</i>)	Close to the bottom of a steep bank.	Height (m): 20 DBH (cm): 165 Life Stage: Mature Life Exp.: 30+ Years	There is an old wound on the east side at the base. There has been a substantial canopy reduction in the past and growth is now a little sparse. There are weak branch attachments at the old pruning points.	Fair	Reduce by 3 metres to the previous pruning points.
T003	Beech (<i>Fagus sp.</i>)	Close to the bottom of a steep bank.	Height (m): 15 DBH (cm): 185 Life Stage: Mature Life Exp.: 50+ Years	Substantially reduced in the past with associated large pruning wounds. There will be decay in these pruning wounds.	Good	Reduce the overall canopy by approximately 5 metres to prevent the loss of branches from weak attachment points.
T004	Holly (<i>Ilex sp.</i>)	At the bottom of a steep bank and close to the neighbouring house.	Height (m): 14 DBH (cm): 90 Life Stage: Mature Life Exp.: 50+ Years	This tree has been drawn up between other mature trees to make a tall, narrow specimen that is heavily infested with Ivy.	Good	Reduce height by 6 metres and cut the ivy at the base.
T005	Oak (<i>Quercus sp.</i>)	At the bottom of a steep bank and close to the neighbouring house.	Height (m): 16 DBH (cm): 80 Life Stage: Early Mature Life Exp.: 50+ Years	This tree has been heavily pruned back from the neighbouring house.	Good	Reduce height by 8 metres to maintain a visual screen whilst removing the need for frequent pruning.

Ref.	Species	Description	Measurements	Survey Notes	Condition	Recommendations
T006	Beech (<i>Fagus sp.</i>)	Part way down a steep bank.	Height (m): 20 DBH (cm): 150 Life Stage: Mature Life Exp.: 50+ Years	No evidence of disease or basal decay, the upper canopy is in good condition with evidence of previous thinning and reduction works.	Good	No action required.