

Webster's Arboricultural Services Ltd

13 Nightingale Gardens
Sandhurst
Berkshire
GU479DQ
07939589339
info@webarb.co.uk
www.webarb.co.uk



Webster's
Arboricultural
Services Ltd

Client Oliver Pearce

Site Address Little Stubbings Burchetts Green Lane Burchetts Green Berkshire SL6 3QP

Date of Quotation March 15th 2024

T1 Beech tree located on the left hand boundary in the rear garden

Scope of works

The tree is becoming overmature for its location and is beginning to suppress the surrounding garden; however the canopy of the tree does provide a good screen to the neighbouring commercial buildings.

I advise the tree is re structured by approximately 60%

This action will allow the tree to regenerate at a smaller size still providing a screen but significantly reducing the trees impact.

Method of works

The trees canopy will be accessed using rope and harness. All pruning cuts will be made using powered hand saws in conjunction with aerial pruning techniques.

The trees canopy will be dismantled into sections leaving the primary limbs to create the shape of the new canopy.

T2 Sycamore located in the front garden adjacent to the front boundary

Scope of works

There has been some evidence of the tree shedding dead wood and some still remains within the canopy. I can't see any other causes for concern with the trees health and it appears to be in good vigour.

The canopy of the tree is starting to encroach upon the driveway and entrance to the property. Therefore I advise the removal of any dead wood over 30 mm in diameter and to laterally reduce the lower canopy by up to 2.5 metres from the branch tips back to suitable growth points.

Also to raise the canopy to 4m from ground level by removing the lowest limb back to where it originates.

This action will help to contain and shape the tree.

Method of Works

The trees canopy will be accessed using rope and harness. All pruning cuts will be made using powered hand saws in conjunction with aerial pruning techniques.

Webster's Arboricultural Services Ltd

13 Nightingale Gardens
Sandhurst
Berkshire
GU479DQ
07939589339
info@webarb.co.uk
www.webarb.co.uk



Webster's
Arboricultural
Services Ltd

G1 Silver birch x2 located on the verge closest to the entrance

Scope of Works

The trees have been planted underneath overhead services and now pose a maintenance issue.

As the trees are still quite young I advise the trees are reduced to approximately 1.5m below the phone lines and the remaining canopy pruned to shape.

This action will help to contain and shape the trees.

Method of Works

The canopy of the trees will be accessed using an "A" frame platform and extended pole pruners.

G2 Group of 4x Sycamore trees located on the verge adjacent to G1

Scope of Works

The trees are semi mature in age and as a result of growing in close proximity the canopies are asymmetrical and leggy.

Due to the species age and form of this group of trees I feel it is best to remove the trees down to ground level and to remove the stumps to allow for re planting of a more suitable species that will bring a greater amenity value to the area.

Method of work

The trees canopy will be accessed using rope and harness. All pruning cuts will be made using powered hand saws in conjunction with aerial pruning techniques.

The trees will be sectionally dismantled down to ground level and the resulting stumps will be removed using a stump grinder.

Our charge to complete these works will be

All works carried out will be in accordance with BS3998 and all resulting arisings will be processed on site and removed.

All areas will be left clean and tidy.

The red line is an indication of the suggested pruning points

Webster's Arboricultural Services Ltd

13 Nightingale Gardens

Sandhurst

Berkshire

GU479DQ

07939589339

info@webarb.co.uk

www.webarb.co.uk



Webster's
Arboricultural
Services Ltd



G1



T2



T1