

**Old Quad Staircase 1-7 and Tower**

Room Ref.	Room Name
1.3	HR Officer's Office
1.4	HR Manager's Office
1.5	Accounts Office
1.5a	Head Accountant's Office
1.5b	Store
1.6	Scouts' Cleaning Store
1.ST	Stair
2.1	Guest Bedroom
2.1a	Guest Bedroom - Kitchenette
2.1b	Guest Bedroom - Bathroom
2.2	Fellow's Office / General Purpose
2.2a	Fellow's Office - Bathroom
2.3	Fellow's Office
2.3a	Fellow's Office - Bathroom
2.11	Kitchenette
2.12	Lobby
2.ST	Stair
3.3	Middle Common Room (MCR)
3.3a	MCR Store
3.3b	MCR Store
3.4	Middle Common Room (MCR)
3.4a	MCR Bar
3.4b	MCR WC
3.4c	MCR Kitchenette
3.ST	Stair
4.3	Shared Office / research centre
4.3a	Shared Office - Ancillary
4.3b	Shared Office - Ancillary
4.4	Fellow's Office
4.4a	Fellow's Office - Ancillary
4.4b	Fellow's Office - Store
4.9	Scouts' Cleaning Store
4.10	Lobby
4.ST	Stair
5.2	Fellow's Office
5.2a	Fellow's Office - Store
5.2b	Fellow's Office - Store
5.2c	Fellow's Office - Store
5.3	Fellow's Office - Ancillary
5.3	Fellow's Office
5.3a	Fellow's Office - Kitchenette
5.3b	Fellow's Office - Bathroom
5.ST	Stair
6.4	Fellow's Office
6.4a	Fellow's Office - Store
6.4b	Fellow's Office - Store
6.5	Fellow's Office
6.5a	Fellow's Office - Bathroom
6.5b	Fellow's Office - Ancillary
6.ST	Stair
7.2	Fellow's Office
7.2a	Fellow's Office - Kitchenette
7.2b	Fellow's Office - Bathroom
7.3	Fellow's Office
7.3a	Fellow's Office - Bathroom
7.3b	Fellow's Office - Kitchenette
7.ST	Stair
BR.7	Senior Common Room Mezzanine
T.08	Bursar's Office
T.09	Non-academic office
T.ST	Stair




**Key - existing and proposed**

- Existing fabric
- Proposals

**Key - Floor Finishes**

- Flooring Type 1** - Replace existing carpet with non-slip sheet flooring. (Note - where indicated on the plans, the existing flooring is exposed timber floorboards rather than carpet)
- Flooring Type 2** - Reinstate carpet over exposed timber floorboards
- Flooring Type 3a** - Exposed timber stair with historic patinated finish. No works proposed.
- Flooring Type 3a** - Existing exposed timber stair where historic patinated finish is not apparent. Surface to be sanded and refinished. Insensitive patch repairs to be made good.
- Flooring Type 3b** - Carpeted stair with applied nosings. Carpet to be removed to expose the underlying timber stair. Timber stair to be refinished and repaired as appropriate (to be confirmed once carpet is removed). Brass nosings to be added.
- Flooring Type 4** - Light refurbishment of historic stone flagstone flooring. Flagstones to be cleaned, loose stones to be re-set, joints to be re-pointed.
- Flooring Type 5** - Existing floorboards to be sanded down and refinished. Gaps between boards to be filled

Notes



0 5 10 15 20 M

Rev Date Amendment  
15.03.24 Issued for Planning

**WALTERS & COHEN**  
ARCHITECTS

**Pembroke College Rokos and Old Quad**

2 Wilkin Street  
London  
NW5 3NL  
Telephone 020 7428 9751  
mail@waltersandcohen.com

**Floor Finishes Plan - First Floor**

Checked by	Scale	Date Drawn	Job No.	Drawing No.	Revision
TL	1:200@A1	30.11.23	2313	PD-1402	-

© This drawing is copyright. Check dimensions on site

**PLANNING**