

LDC 500-900 Silencer

Round, for air handling units

Item Number: [450281](#)

Silencer

Easily-fitted silencer for circular ducts, fitted with a connection that complies with the spiral duct standard. The LDC effectively reduces noise in the duct. Two silencers can be used together in installations where noise reduction is a particularly strong requirement. This is very effective. For the most effective noise reduction, the silencer should be fitted immediately behind a fan or bend. The silencer should be used together with an insulated fan where there is a requirement for noise reduction both in the duct and in the surroundings as a whole. The silencer is delivered with two separate spigots. Insulation thickness 100 mm.

Good attenuation in 125 and 250 Hz bands.



Technical parameters

Dimensions and weights

Duct dimension; Circular, inlet	500 mm
Duct dimension; Circular, inlet	500 mm
Duct dimension; Circular, outlet	500 mm
Duct dimension; Circular, outlet	500 mm
Weight	30 kg

Others

Duct connection type	Circular
----------------------	----------

Dimension

