

Matclad Limited

Unit 51, Rhosddu Industrial Estate
Wrexham
LL11 4YL
Tel: 01978 291133
sales-team2021@matclad.co.uk

Manufacturers of clay brick slip tiles for facing and engineering applications in a full range of colours, textures and finishes. Our expertise and skill in making clay products enables you to complete the most demanding of architectural details

Description

Bed tiles are a good alternative for flooring and similar in finish to traditional quarry tiles that were made at manufacturers like Platts and Dennis of Ruabon for many years.

Traditional quarry tiles were extruded and have the characterful irregularity seen in many properties across the UK.

They are very hard wearing and do not require sealing due to their being fired hot enough and long enough to make them almost fully vitrified (< 3% water absorption)

Additional Information

Lead-time	Call the office for lead-time (dependent on quantity), Samples on request
Minimum Joint Width	8mm Joint Width
Specials Available	REL (Round Edge Long Side), RELS (Round Edge Long and Short), RES (Round Edge Short Side), External Return, Internal Return, Step tread
Pieces per M2	40 (10mm Joint)
Width	150
Height	150
Thickness	15
Colour	Orange, Red
Requires Sealing	No
Surface Finish	Unsanded
Suitable for External Use	External and Internal Use (Frost Resistant)
Water Absorption	Less than 3%

Size Tolerances:

All stated sizes are nominal. Declaration of Performance for each product is available on request.

