

PRODUCT DATA SHEET

Bauder WB Native Wildflower Blanket

A British growth vegetation Blanket designed for use on green roofs. Containing a broad mix of UK native wildflower species. Suitable to be laid on Bauder (FLL Compliant) Biodiverse substrate.

Intended Use

Bauder WB Native Wildflower Blanket contains a broad mix of British Wildflowers grown in substrate on a coir carrier. The natural fibres of the coir carrier promote the rapid rooting of the blanket into the substrate. The product is installed over Bauder, FLL Compliant Biodiverse Substrate (see Product Data Sheet). The vegetation is a mix of hardy Wildflowers, annuals and herbs. The vegetation is cut back in the summer prior to delivery to reduce plant stress.



PRODUCT INFORMATION AND TECHNICAL PERFORMANCE		
Characteristic	Unit	Value
Maximum saturated weight	kg/m ²	≤ 30
Thickness	mm	30 to 40
Species	Nos	36 wildflower species + 4 grass species (≤10%)
pH Value	pH	6.5 to 7
Material		Substrate and wildflower plants, grown on a coir mat carrier (100% Natural product)
Typical roll size	m	0.5 x 2m
Rolls per pallet	Rolls	Typically 30-40 rolls-Dependant on weight (40m ²)
Pallets per articulated lorry	Pallets	26 pallets – Dependant on weight (1040m ²)




UNITED KINGDOM

Bauder Ltd
70 Landseer Road, Ipswich, Suffolk IP3 0DH
T: +44 (0)1473 257671 E: info@bauder.co.uk
bauder.co.uk

IRELAND

Bauder Ltd
O'Duffy Centre, Carrickmacross, Co. Monaghan
T: +353 (0)42 9692 333 E: info@bauder.ie
bauder.ie

PRODUCT DATA SHEET

CERTIFICATION AND ENVIRONMENTAL INFORMATION	
International Standards Organisation (ISO)	ISO 9001:2015 Quality Management Certificates EN1271 (UK) and 70499/03-15_e (Germany).
Flora Locale – Membership	
Perfect for Pollinators	
Endorsed by Buglife (the invertebrate charity)	
Recycled content	≥ 95% recycled material

INSTALLATION GUIDANCE

Normally installed directly onto levelled Biodiverse Substrate. WB Blanket should be installed as soon as possible on delivery. Care should be taken not to traffic the Blanket. WB Blanket should be laid by skilled operative. See Bauder's Green Roof Installation Guide for full details.

The correct watering and aftercare is required for this product.

Bauder reserves the right to amend information and product specifications without prior notice. All reasonable care has been taken to ensure that all data is current at the time of print, however because Bauder pursues a policy of constant development we recommend ensuring that your copy of this information is current by contacting our Technical Department at technical@bauder.co.uk

Recommendations for use should be verified as to the suitability and compliance with actual requirements, specifications, installation techniques and any applicable laws and regulations.

UNITED KINGDOM

Bauder Ltd
70 Landseer Road, Ipswich, Suffolk IP3 0DH
T: +44 (0)1473 257671 E: info@bauder.co.uk
bauder.co.uk

IRELAND

Bauder Ltd
O'Duffy Centre, Carrickmacross, Co. Monaghan
T: +353 (0)42 9692 333 E: info@bauder.ie
bauder.ie