


Visual Tree Assessment (VTA) Tree Survey Schedule

													Survey Reference Number: D3089.V1.0 Client: Grayshott Parish Council Site: Various Sites - See location plan for address Date of Survey: 13th of March 2024 Surveyed by: Tom Butterfield Tagged: YES - Previously			
Site	Prefix	ID	Name	No of Trees	Stems	Height (m)	Crown Rad (m)	DBH (mm)	Age	Vitality	Structure	Notes and Observations	Recommended works	Priority	Re-inspect	Completed
Site 11 - Applegarth Farm	T	4	Common Lime	1	1	20	7	800	M	G	G	Basal growth. Prohibiting full inspection	Remove basal growth	3 (12Months)	24	
Site 11 - Applegarth Farm	T	66	Common Oak	1	1	22	7	1000	M	G	G	Missing tag. Significant volume of medium sized dead wood throughout the crown and over the road	Remove dead wood Over road	2 (03Months)	24	
Site 11 - Applegarth Farm	G	68.1	Common Ash	5	1	10	2	200	SM	P	P	Ash Dieback Disease - CLASS 3 50%-26% of the crown remains. Group of Ash adjacent to the road. Trees marked with paint	Fell marked trees	2 (03Months)	NA	
Site 11 - Applegarth Farm	T	82	Common Lime	1	1	20	5	650	M	G	G	Basal growth. Prohibiting full inspection	Remove basal growth	3 (12Months)	24	
Site 11 - Applegarth Farm	T	87	Beech	1	1	21	6	900	M	P	P	Significnat crown die-back. Sparse crown. Peeling bark on stem. Stem death	Fell	2 (03Months)	NA	
Site 11 - Applegarth Farm	T	91	Beech	1	1	20	8	1100	M	G	P	Stem bifurcates above 1.5m. Multiple stems above 1.5m. Included stem union. Unbalanced crown shape	Install non-invasive cable brace in upper one third of the crown to support weak union. Reduce leaning stem by 3m in height and 3m off the side	3 (12Months)	24	
Site 11 - Applegarth Farm	T	175	Sycamore	1	1	21	7	980	M	G	F	Ivy on tree. Stem bifurcates at ground level. Stem bifurcates above 1.5m. Included stem union. Leaning stem. Heavily weighted stems	Sever and remove 1.5m of Ivy from ground level. Install non-invasive cable brace in upper one third of the crown to support weak union. Reduce crown height by 3m. Reduce crown spread by 2m	3 (12Months)	24	
Site 11 - Applegarth Farm	G	182	Common Lime	9	1	13	4	250	SM	P	F	Group of trees. Ash Dieback Disease - CLASS 3 50%-26% of the crown remains. Ash Dieback Disease - CLASS 4 25%-0% of the crown remains. Marked with paint	Fell marked trees. Leave Limes	3 (12Months)	24	
Site 11 - Applegarth Farm	T	187	Ash	1	1	13	3	250	SM	P	P	Ash Dieback Disease - CLASS 3 50%-26% of the crown remains. Marked with paint	Fell	3 (12Months)	NA	
Site 11 - Applegarth Farm	T	188	Ash	1	1	13	3	250	SM	P	P	Ash Dieback Disease - CLASS 3 50%-26% of the crown remains. Marked with paint	Fell	3 (12Months)	NA	
Site 11 - Applegarth Farm	T	335	Common Oak	1	1	18	3	440	EM	G	F	Stem bifurcates above 1.5m. Included stem union. Leaning stem. Crown bias to the East. Leaning East	Reduce crown height by 3.5m. Reduce crown spread by 3m.	3 (12Months)	24	
Site 11 - Applegarth Farm	G	IVY	IVY	/	/	/	/	/	/	/	/	Ivy colonised many of the trees in the area, prohibiting full inspection	Sever and remove 1.5m of Ivy from ground level from all trees	3 (12Months)	24	

Trees in TPO