

# Technical Data Sheet

## The Conservation Rooflight

### Product Description

The Conservation Rooflight is the original low profile skylight, combining the highest modern performance standards with an authentic traditional appearance. Favoured by English Heritage, the National Trust and Planning / Conservation Officers, it is available in a wide range of sizes, along with a Bespoke Design Service.

### Manufactured From

3mm mild steel with a protective polyester powder coating to BS EN ISO 12944.

The standard frame is finished in a textured semi gloss paint finish in black RAL 9005 (other RAL colour options are available).

All Conservation Rooflights have internal linings which have a multi coat paint finish applied and sealed with a white coating (to a 10% gloss level).

COASTAL: Please note, for properties that reside within 5km of the coastline or large estuary, we recommend calling our Customer Services Team on 01993 833155 to discuss an appropriate alternative of stainless steel. All Conservation rooflights are hot zinc sprayed.

### Testing



The Conservation Rooflight range is UKCA marked in accordance with BS EN 14351-1. The Conservation Rooflight is also CE marked in accordance with EN 14351-1.

The Conservation Rooflight meets the requirements of BS6375-1:2015+A1:2016 exposure category 2000.



### Standard Glazing

4mm Toughened Outer.

16mm 90% Argon Cavity.

4mm Low Emissivity (Low e) Toughened inner.

Whole unit u-value (U<sub>w</sub>) as low as 1.4 W/m<sup>2</sup>K in accordance with BS EN ISO 10077-2:2012.

Other glazing specifications are available upon request, contact us for more information.

### Sizes and Prices (for an 'on the rafter' installation)

<b>CR06-1</b>	(W) 412mm x (L) 520mm	<b>£621</b>
<b>CR07-2</b>	(W) 463mm x (L) 622mm	<b>£632</b>
<b>CR01-2</b>	(W) 565mm x (L) 725mm	<b>£640</b>
<b>CR03-2</b>	(W) 565mm x (L) 1028mm	<b>£729</b>
<b>CR08-2</b>	(W) 615mm x (L) 875mm	<b>£788</b>
<b>CR09-2</b>	(W) 717mm x (L) 1028mm	<b>£851</b>
<b>CR10-2</b>	(W) 717mm x (L) 1180mm	<b>£929</b>
<b>CR14-2</b>	(W) 717mm x (L) 1333mm	<b>£959</b>
<b>CR15-2</b>	(W) 717mm x (L) 1635mm	<b>£1114</b>
<b>CR11-3</b>	(W) 869mm x (L) 1028mm	<b>£957</b>
<b>CR01-3</b>	(W) 1021mm x (L) 725mm	<b>£854</b>
<b>CR13-3</b>	(W) 1021mm x (L) 1180mm	<b>£1058</b>
<b>CR14-3</b>	(W) 1021mm x (L) 1333mm	<b>£1112</b>
<b>CR15-3</b>	(W) 1021mm x (L) 1635mm	<b>£1334</b>
<b>E1LG</b>	(W) 888mm x (L) 1114mm	<b>£1121</b>
<b>E1RG</b>	(W) 888mm x (L) 1114mm	<b>£1121</b>

Prices exclude accessories, VAT and delivery.

Sizes above are clear structural opening dimensions for an 'on the rafter' installation. Please consult with us for 'between the rafter' sizes.

All prices are correct at the time of going to press.

## Pitch

Suitable for pitched roof installations with a 17.5°-65° roof pitch.

## Opening Options

### Manual hand winders

Available in brass or chrome with opening distances of either 150mm or 300mm.

### Manual pole winder

Winding crank for out of reach opening. Available in brass or chrome with opening distances of 150mm or 300mm. Poles are available in varying lengths from 1m to 3m.

### Motors

Motorised opening options are available for out of reach rooflights and can be controlled by a switch or remote. Contact us for more information.

### Fixed Shut

A fixing bracket for a fixed shut roof window. The fixing bracket is white as standard.

## Optional Extras and Blinds

Roller blinds available in 7 colours.

Pleated blinds available in 6 colours.

Rain sensors, temperature sensors and other accessories are available on request. Please consult with us directly for compatibility.

## Flashing Kits

The Flashing Kit can be used for 'on the rafter' and 'between the rafter' installations, where the roof depth (above the rafter) does not exceed 75mm.

For more information see Flashing Kit in Sizes Options and Prices.

## Lead Time

The Conservation Rooflight subject to availability. The usual lead time is 5 working days for standards. Egress roof windows are 14 days. Please call if you require sooner.

## Installation

The Conservation Rooflight Installation Manual and Installation Drawings are available to download from our website.

BIM Objects can also be downloaded.

## Warranty

Don't forget to extend your warranty for free.

Our steel rooflights benefit from an extended warranty of up to ten years\*. Upon receipt of your rooflight, please register your product.

\*Terms and conditions apply.

Upon product registration with us, the standard warranty can be extended to ten years, as set out in our Terms and Conditions, provided that the appropriate products have been installed to suit their location and that these are regularly maintained, with these actions recorded in accordance with our maintenance instructions. Register your product at

[www.therooflightcompany.co.uk/contact/register-a-product](http://www.therooflightcompany.co.uk/contact/register-a-product)

