



SECTION A-A

- Code 4 lead flashings
- Proprietary valley gutters to wall abutments
- White upvc framework
- White upvc standard gutters
- Pilkington SSB Sunshade Blue (warm edge) glazing

- 102mm facing brick outer leaf
- 100mm cavity with dri therm insulation
- 5 No wall ties per M²
- 100mm blockwork inner leaf
- Insulating cavity closers to external openings
- Mechanical fixings or toothing at wall abutments

- 50mm sand cement screed
- 100mm 25N concrete floor slab
- 1000g visqueen damp proof membrane
- 125mm floormate insulation
- 150mm clean well compacted hardcore

REAR GROUND FLOOR CONSERVATORY
 12 DENMARK CLOSE
 CORBY

Scale: 1:50